

## 617-2020 ADDENDUM 2

### WESTWOOD WASTEWATER PUMPING STATION UPGRADES

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
TENDER**

ISSUED: October 8, 2020  
BY: Blair Moore, P.Eng.  
TELEPHONE NO. (204) 453-2301 Ext. 4013

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE TENDER AND SHALL FORM A PART  
OF THE CONTRACT DOCUMENTS**

Template Version: A20190115

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Tender, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.**

---

#### **PART D – SUPPLEMENTAL CONDITIONS**

Revise: D3.2 (d) to read:

(d) structural:

- (i) Adding topping to the main floor in a wet well room.
- (ii) Repair wet well door thresholds.
- (iii) Remove existing concrete topping and asphaltic on top of dry well.
- (iv) Install new concrete topping and insulation on top of the dry well.
- (v) Provision of new openings on the main floor and the motor room floor.
- (vi) Provision of reinforcement at new openings.
- (vii) Provision of hoist beams in the motor room and pump room for installing the City supplied motorized hoist.
- (viii) Modify existing hatch opening.
- (ix) Remove a ladder and replace with alternate tread stairs.
- (x) Remove and replace working platforms.
- (xi) Provision of new alternate tread stairs to working platforms.
- (xii) Remove and replace bearing beams in the pump floor.
- (xiii) Provision of removable guard rails.
- (xiv) Miscellaneous structural improvements and reinforcement to the existing building.

Revise: D3.2 (e) to read:

(e) architectural:

- (i) Remove and replace roofing material.
- (ii) Painting of superstructure walls and ceilings, substructure wall and ceilings, and spiral stairs.
- (iii) Remove and replace wet well man door.
- (iv) Provision of graffiti coating on the exterior walls and doors.

#### **DRAWINGS**

Replace: 617-2020\_Drawing\_C-01-R0 with 617-2020\_Addendum 2-Drawing\_C-01-R1