



DILLON CONSULTING LIMITED 3200 DEZIEL DRIVE, SUITE 608, WINDSOR, ONTARIO, N9W 5K8, PHONE (519) 948-5000, FAX (519) 948-5054


PLOT DATE: 2020-09-08 2:13:35 PM
FILE NAME: U:\dms26582023\6-04-WP\WPV-CO.N.plt




MAIN FLOOR PLAN
SCALE: 1 : 50



MOTOR ROOM FLOOR PLAN
SCALE: 1 : 50



PUMP ROOM PLATFORM PLAN
SCALE: 1 : 50



PUMP ROOM FLOOR PLAN
SCALE: 1 : 50

CONSTRUCTION NOTES:

- LIGHTING FIXTURES TO BE CEILING MOUNTED ON MAIN FLOOR AND MOTOR ROOM FLOOR WHERE POSSIBLE, OR WALL MOUNTED NO HIGHER THAN 3m FROM FINISHED FLOOR. PUMP ROOM LIGHTS TO BE WALL MOUNTED NO HIGHER THAN 3m FROM FINISHED FLOOR OR PLATFORM.
- CONDUIT AND CABLEING TO BE INSTALLED AS TO NOT IMPARE OPERATION OF THE HOISTING BEAMS.

LEGEND:

- § LIGHT SWITCH
- § 3-WAY LIGHT SWITCH
- § COMBO EXIT/EMERGENCY LIGHT
- § REMOTE EMERGENCY LIGHT
- § EXTERIOR LIGHT

LUMINAIRE SCHEDULE					
TYPE	MANUFACTURER	CAT. NO.	LAMP	VOLTAGE	REMARKS
A	AIMLITE METALUX DAY-BRITE	VWP4-LA1A-4-40K-SS-10KV 4VT3-LD5-4000-G-UNV-L840-SSL-U DWAE-43L-840-4-UNV-SSL	LED	120 V	CORROSION RESISTANT
X	AIMLITE BEGHELLI EMERGH-LITE	CRPN-12-036-1-WHT-2-ATD-5W FT2-C-RM-12-40-L-1-OLR-U-5W-LED-AT-BB ENC1W12N60L1	LED	120 V	NEMA 4X, COMB. EXIT/EMERG. LIGHT W/BATTERY BANK
Y	AIMLITE BEGHELLI EMERGH-LITE	RMN2-12-24V-5W-LA-WHT BOL-WP-R-2-12V5W-LED EF39PDM-LI	LED	12-24 V	DUEL HEAD REMOTE EMERGENCY LIGHT
Z	COPPER LIGHTING GARDCO	ENV-801-LED-E1-BL2-BZ-PC-WG 104L-16L-530-WW-G1-2-UNV-PCB-BZ	LED	120 V	CORROSION RESISTANT, PROVIDE PHOTOCELL, WIRE GUARD

TENDER

NOT FOR CONSTRUCTION



			ENGINEER'S SEAL			
DESIGNED BY BKB			CHECKED BY BLM		WESTWOOD WASTEWATER PUMPING STATION UPGRADES	
DRAWN BY SK			APPROVED BY BLM		CITY DRAWING NUMBER 1-0194L-E0006-001	
HOR. SCALE 1 : 50			RELEASED FOR CONSTRUCTION		SHEET 22 OF 23	
VERTICAL			DATE SEPTEMBER 2020		CONSULTANT DRAWING NUMBER E-05	
NO. REVISIONS			DATE		CONSULTANT PROJECT NUMBER 20-2316	