



754-2020 ADDENDUM 6

LANDFILL CELL SITE WORK AND LINER CONSTRUCTION

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: March 23, 2021
BY: A. Raichura
TELEPHONE NO. 204 986-2962

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

NMS SPECIFICATIONS

Section 31 23 33.02 Fill

Revise: 2.3.1 to read:

The Granular Drainage Blanket shall be clean stone meeting the gradation requirements below. Contractor shall provide particle size analysis of a representative sample of the proposed material to the Contract Administrator for approval.

100.0 mm sieve 100% passing

75.0 mm sieve 95 - 100% passing

40.0 mm sieve 60 - 100% passing

20.0 mm sieve 0 - 10% passing

14.0 mm sieve 0 - 5% passing

0.080 mm sieve 0 - 2% passing