



139-2021 ADDENDUM 3

PUBLIC WORKS DEPARTMENT SECURITY AND ACCESSIBILITY UPGRADES – 1155 PACIFIC AVENUE

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: March 24, 2021
BY: Lou Chubenko
TELEPHONE NO. 204 470-7881

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART E – SPECIFICATIONS

DRAWINGS

Replace: 139-2021_Drawing_A4.0-R0 with 139-2021_Addendum_3_Drawing_A4.0-R1

QUESTIONS AND ANSWERS

- Q1: Who is responsible for supplying and installing automatic door hardware components, as per Drawing A1.4?
- A3: The Contractor is fully responsible for supply and installation of door hardware components. Hardware to include new card access components that shall be wired using B-wire gel filled connectors; door electric strikes (setup for fail-secure) with strike surge protection at device ends; door contacts; and Request-To-Exit devices wired with 4-state, double-end-of-line 1k ohms resistors in the N/C state at device ends.
- Card access components shown on Drawing E1.4, Door Hardware Schedule, shall read "REFER TO ELECTRICAL". All card access components supplied and installed, as per Electrical Drawings.
- Q2: Where is the card access cabinet (head end) located in the building?
- A2: Card access cabinet (head end) is located in Electrical Room, as indicated on Drawing E1. Refer to KEY PLAN, under "crawlpace hatches also in basement corridors".