



## 478-2021 ADDENDUM 1

### 2021 LOCAL IMPROVEMENT ALLEYS

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
BID/PROPOSAL**

ISSUED: July 27, 2021  
BY: Blair Cockrell  
TELEPHONE NO. 204 928-8431

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID/PROPOSAL AND SHALL FORM  
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

---

#### **PART E – SPECIFICATIONS**

Add: E12. WORKING AROUND MANITOBA HYDRO POLES

##### GENERAL REQUIREMENTS

- E12.1 When completing roadway excavation around Manitoba Hydro wood poles, Manitoba Hydro Safety Watch will be required. The Contractor shall provide equipment capable of stabilizing the pole while excavation and placement of granular sub-base materials to full thickness is completed. Equipment shall be acceptable to Manitoba Hydro and the Contract Administrator.
- E12.2 Manitoba Hydro personnel will be responsible for securing the Contractor's equipment to each wood pole, except where a primary dip is located on the wood pole. If the primary dip is present, Manitoba Hydro will complete the stabilization.

##### MEASUREMENT AND PAYMENT

- E12.3 The Work described in this specification shall be considered incidental to "Excavation" and no measurement or payment will be made.