



737-2021 ADDENDUM 3

KEEWATIN STREET NORTHBOUND REHABILITATION – INKSTER BOULEVARD TO ADSUM DRIVE

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL

ISSUED: Dec 22, 2021
BY: Craig Rowbotham
TELEPHONE NO. 204 318-2051

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read:

The Submission Deadline is 12:00 noon Winnipeg time, January 20, 2022.

PART D – SUPPLEMENTAL CONDITIONS

Add: D16.2 (a) (x) the Accessibility Plan specified in E20.

Replace: D19 Work By Others in its entirety with:

D19. WORK BY OTHERS

D19.1 Further to C6.25, the Contractor's attention is directed to the fact that other Contractors, the personnel of Utilities and the staff of the City may be working with in the project limit, approach roadway, adjacent roadways or right-of-way. The activities of these agencies may coincide with the Contractors execution of work and it will be the Contractor's responsibility to cooperate to the fullest extent with other personnel working in the area, and such cooperation is an obligation of the Contractor under the terms of Contract.

D19.2 Work by others on or near the Site will include but not necessarily be limited to:

- (a) Shaw Communications.
- (b) Manitoba Hydro
 - (i) De-energizing/energizing new street light plant
 - (ii) Lowering of gas services, as required
- (c) City of Winnipeg Traffic Services
 - (i) Traffic Signing
 - (ii) Lane Markings

- (d) Winnipeg Transit's Contractor
 - (i) Contractor for installation of new concrete pads, sidewalks, and services for future heated bus shelters.
- (e) Winnipeg Transit
 - (i) Temporary bus stop relocations and/or modifications.
 - (ii) Installation of heated Bus Shelters.

D19.3 Further to D19.1 the Contractor shall cooperate and coordinate all activities with all parties performing required Work by Others. The Contractor must include and accommodate Work by Others identified in D19.2 or additional parties, in their construction schedule as per D15 and accommodate the necessary area on site required for the Work by Others to complete the Work.

Revise: D21.1 to read:

D21.1 The Contractor shall achieve Substantial Performance within Forty-two (42) consecutive Working Days of the commencement of the Work as specified in D16.

Revise: D22.1 to read:

D22.1 The Contractor shall achieve Total Performance within Forty-Seven (47) consecutive Working Days of the commencement of the Work as specified in D16.

Page numbering on some forms may be changed as a result.

PART E – SPECIFICATIONS

Revise: E2.4 (a) (v) to read:

(v) Development, and implementation of the Accessibility Plan as per E20; and

Add: E2.4 (a) (vi) Other job related items.

Add: E2.4 (b) (v)

(v) Monitoring, maintenance, and reporting of the Accessibility Plan as per E20.

Add: E2.10

E2.10 Pay Reduction for Accessibility Plan

- (a) The Demobilization payment will be reduced by the number of pay adjustments incurred in accordance with E20 and as determined by the Contract Administrator.

Add: Section E20 as follows:

E20. SITE REQUIREMENTS FOR ACCESSIBILITY

- E20.1 The Contractor shall provide the Contract Administrator with an Accessibility Plan at least five (5) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract Documents, if applicable.
- E20.2 The Accessibility Plan shall demonstrate how the Contractor will accommodate the safe passage of pedestrians and cyclists in accordance with the Manual of Temporary Traffic Control, the Contract Drawings, Staging Plans, and Streets By-Law No. 1481/77 at all times for the duration of the Construction. Unless noted in the Contract, the Accessibility Plan must include a written plan for the following:
- (a) How the Contractor will maintain at least one crossing in each direction for each intersection (one north/south crosswalk and one east/west crosswalk).
 - (b) How the Contractor will maintain access to bus stops within the site.
 - (c) How the Contractor will maintain access to pedestrian corridors and half signals.
 - (d) How the Contractor will maintain cycling facilities.
 - (e) How the Contractor will maintain access to residents and businesses unless otherwise noted in the Contract.
 - (f) Any required detour signage at adjacent crossings to facilitate sidewalk or active transportation pathway closures.
- E20.3 The Accessibility Plan may also include figures, sketches, or drawings to demonstrate the proposed plan.
- E20.4 The Accessibility Plan shall include written details on how the Contractor intends to review, maintain, and document all items related to the Accessibility Plan on-site during Construction, including, but not limited to:
- (a) Signage
 - (b) Temporary Ramping
 - (c) Transit Stops
 - (d) Detour Signage
- E20.5 At minimum, the Contractor shall review the site conditions on a daily basis to ensure all features related to the Accessibility Plan are in place. The site review is intended to correct deficiencies as a result of unforeseen events such as wind, traffic, or the general public. Deficiencies that are direct result of the Contractors actions must be corrected immediately.
- E20.6 Any changes to the Accessibility Plan must be submitted to the Contract Administrator a minimum of 5 Working Days prior to the required change for approval.
- E20.7 Upon request from the Contract Administrator, the Contractor shall provide records demonstrating that the site has been maintained.
- E20.8 Failure to produce records that demonstrate that the site was maintained in compliance with the Accessibility Plan or deficiencies as a direct result of actions by the Contractor that are not immediately corrected may result in a pay adjustment. The rate of pay adjustment will be as per the following schedule:
- (a) First Offence – A warning will be issued and documented in the weekly site meeting.
 - (b) Second Offence – A field instruction to immediately correct the site will be issued by the Contract Administrator.
 - (c) Third and subsequent Offences – A pay reduction will be issued in the amount of \$250.00 per instance, per day.

Add: Section E21 as follows:

E21. ASBESTOS-CONCRETE WATER MAINS WORK RESTRICTIONS

E21.1 Note for all work in proximity to Asbestos-Concrete Watermains:

- (a) Use of vibratory heavy equipment within 3.0 meters horizontally of the asbestos-concrete water main centerline is prohibited. This restriction does not apply to the use of vibratory rollers on the pavement surface layer.
- (b) Concrete demolition and removal within 3.0 meters horizontally of the asbestos-concrete water main shall be completed by saw cutting or use of hand-held jackhammers. Use of machine mounted concrete breakers above asbestos-concrete water mains is prohibited.