

ASSET NUMBER	STREET NAME	LOCATION DESCRIPTION	FLOW TYPE	WORK TYPE NAME	EST COST	COMMENTS	HEIGHT	WIDTH	TOTAL LENGTH
S-MA50013611	ARCHIBALD ST	1ST MH N OF MISSION ST TO 2ND MH N OF MISSION ST	CS	FULL SEGMENT LINER	\$540,900		2950	1950	32.6
S-MA70019579	DAWSON RD N	1ST MH SE OF PLINGUET RD TO MH @ PLINGUETRD (SPL)	CS	FULL SEGMENT LINER	\$645,300	LARGE AREAS OF MISSING BRICK LINER - RECENTLY GROUTED	2700	1800	67.7
S-MA70032662	DAWSON RD N	MH@ PLINGUET RD (SPL) TO 1ST MH N OF PLINGUET RD	CS	FULL SEGMENT LINER	\$467,100	LARGE AREAS OF MISSING BRICK LINER - RECENTLY GROUTED STABILIZATION MAY BE REQUIRED IN SOME LOCATIONS PRIOR TO LINING - TNT	2700	1800	46.4
S-MA50013486	DAWSON RD N	5TH MH SE OF RUE MESSIER TO 4TH MH SE OF RUE MESSIER	CS	FULL SEGMENT LINER	\$904,500	LARGE AREAS OF MISSING BRICK LINER - RECENTLY GROUTED. Possible stabilization required at 95-100m	2750	1625	101.6
S-MA40011001	GATEWAY RD	3RD MH S OF NAIRN AV OVERPASS TO 1ST MH E OF ARCHIBALD AV	CS	FULL SEGMENT LINER	\$333,000		2060	1625	68.0