



# 866-2021 ADDENDUM 1

## 2021 Regional Street Program – Nairn Avenue Reconstruction and Watermain Renewal

ISSUED: March 22, 2022  
BY: Taran J Peters, P.Eng.  
TELEPHONE NO. 204 453-2301

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL**

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

### **FORM B: PRICES**

Replace: 866-2021\_Form\_B-Prices with 866-2021\_Addendum\_1-Form\_B-Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R1):

Add: Item A.8

Revise: Items A.19 i), A.19 ii), A.21 ii), A.21 iii), A.21 iv), A.21 v), A.21 vi), A.21 vii), C.12, C.13, C.14

Page numbering and item numbering on some forms may be changes as a result.

### **PART D – SUPPLEMENTAL CONDITIONS**

Revise: D15.2 to read:

The Contractor shall not commence any Work on the Site until:

- (a) the Contract Administrator has confirmed receipt and approval of:
  - (i) evidence of authority to carry on business specified in D8;
  - (ii) evidence of the workers compensation coverage specified in C6.15;
  - (iii) the twenty-four (24) hour emergency response phone number specified in D5.2;
  - (iv) the Safe Work Plan specified in D9;
  - (v) evidence of the insurance specified in D10;
  - (vi) the Contract security specified in D11;
  - (vii) the Subcontractor list specified in D12;
  - (viii) the equipment list specified in D13;
  - (ix) the detailed Work schedule specified in D14;
  - (x) the direct deposit application form specified in D28; and
  - (xi) the Accessibility Plan specified in E2.**
- (b) the Contractor has attended a pre-construction meeting with the Contract Administrator, or the Contract Administrator has waived the requirement for a pre-construction meeting.

Revise: D15.3 to read:

The Contractor shall commence the Watermain Renewal Work on the Site no later than **April 25, 2022**, as directed by the Contract Administrator and weather permitting.

Delete: D15.4

Revise: D15.5 to read:

The City intends to award this Contract by **April 20, 2022**.

## **PART E – SPECIFICATIONS**

Revise: E1.4 to also include:

<u>Drawing No.</u>	<u>Drawing Name/Title</u>	<u>Drawing (Original) Sheet Size</u>
S-1154	TRAFFIC SIGNALS NAIRN AVE. & STADACONA ST.	A1
S-1608	TRAFFIC SIGNALS NAIRN AVE. & WATT ST.	A1
S-2150	TRAFFIC SIGNALS ALLAN ST. & STREET AVE.	A1

Revise: E2.8 to read:

Failure to produce records that demonstrate that the Site was maintained in compliance with the Accessibility Plan or deficiencies as a direct result of actions by the Contractor that are not immediately corrected may result in a pay adjustment. The rate of pay adjustment will be as per the following schedule:

- (a) First Offence – A warning will be issued and documented in the weekly Site meeting;
- (b) Second Offence – A field instruction to immediately correct the Site will be issued by the Contract Administrator; and
- (c) Third and subsequent Offences – A pay reduction will be issued in the amount of two hundred fifty dollars (\$250.00) per instance and per day.

Add: E3.10 Pay Reduction for Accessibility Site Plan

- (a) The Demobilization payment will be reduced by the number of pay adjustments incurred in accordance with E2 and as determined by the Contract Administrator.

Add: E8.1 (e)

E8.1 Further to Clause 3.7 of CW 1130:

- (e) During paving operations for the westbound median lane, as indicated on the drawings as “Stage 2”, the Contractor will be permitted to reroute the westbound traffic to Talbot Avenue, similar to “Stage 1” traffic staging, only on the weekend and as approved by the Contract Administrator.

Add: E32. Supply and Placement of Clay Fill Material

### **E32. SUPPLY AND PLACEMENT OF CLAY FILL MATERIAL**

#### **DESCRIPTION**

E32.1 This Specification shall amend and supplement City of Winnipeg Standard Construction Specification CW 3170 R3 – Earthwork and Grading, and cover the supply and placement of clay fill material along the south back of curb of Nairn Avenue between Stadacona Street and Desalaberry Avenue.

## MATERIALS

E32.2 Approved clay fill material shall consist of high plastic clays, uniform in texture and suitable for compaction. The clay fill material can be suitable site material or imported material.

## CONSTRUCTION METHODS

E32.3 Subsequent to CW 3170-R3, the placement of clay fill, as indicated on the Drawings and as directed by the Contract Administrator, shall be placed in the location behind the back of the curb on the south side of Nairn Avenue between Stadacona Street and Desalaberry Avenue to build a clay plug in order to prevent seepage and maintain the function of the primary dike along Nairn Avenue.

## MEASUREMENT AND PAYMENT

E32.4 The supply and placement of clay fill material will be measured on a volume basis and paid for at the Contract Unit Price per cubic metre for "Supplying and Placing Clay Fill Material". The volume to be paid for shall be the total number of cubic metres compacted in place in accordance with this Specification, accepted and measured by the Contract Administrator. No payment will be made for material placed outside of the limits of placement as directed by the Contract Administrator.

Add: E33. Slip Form and Hand Place Paving Operations

## **E33. SLIP FORM AND HAND PLACE PAVING OPERATIONS**

### DESCRIPTION

E33.1 This Specification shall amend and supplement City of Winnipeg Standard Construction Specification CW 3310 R17 – Portland Cement Concrete Pavement Works, and covers the slip form and hand place paving operations paving operations along Nairn Avenue between Stadacona Street and Watt Street.

### CONSTRUCTION METHODS

E33.2 Subsequent to CW 3310 R17, slip form paving operations is to be used at all times when possible. Hand place paving operations will be used for curb lanes adjacent to hydro poles.

### MEASUREMENT AND PAYMENT

E33.3 The measurement and payment will be as per CW 3310-R17.

## **DRAWINGS**

Replace: 866-2021\_Drawing\_Cover\_Page-R0 with 866-2021\_Addendum\_1-Drawing\_Cover\_Page-R1

Replace: 866-2021\_Drawing\_P-3556-10-R0 with 866-2021\_Addendum\_1-Drawing\_P-3556-10-R1

Add: 866-2021\_Addendum\_1-Drawing\_S-1154-R1

Add: 866-2021\_Addendum\_1-Drawing\_S-1608-R1

Add: 866-2021\_Addendum\_1-Drawing\_S-2150-R1