

ROOM FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	NORTH WALL	SOUTH WALL	EAST WALL	WEST WALL	CEILING	CEILING HEIGHT	NOTES
1:29	OFFICE	CPT-1	RB-1	N/A	N/A	N/A	N/A	N/A	EX.	
1:30	OFFICE	CPT-1								
1:31	OFFICE	CPT-1								
1:32	OFFICE	CPT-1								
1:33B	CHECKOUT	CPT-1								
1:72	BROWSING COLLECTION	CPT-1								
1:43	CHILDREN'S LIBRARY ENTRY	CPT-1								
1:48	YOUNG ADULTS READING RM.	CPT-1								
1:49	YOUNG ADULTS COLLECTION	CPT-1								
1:50	CHILDREN'S LIBRARY	CPT-1								NOTE 1
1:51	PROGRAM ROOM	CPT-1								
1:58	FICTION COLLECTION	CPT-1								
1:57	OFFICE	CPT-1								
1:58	OFFICE	CPT-1								
1:59	OFFICE	CPT-1								
1:60	OFFICE	CPT-1								
1:66	MAIN STREET	N/A								COLUMNS ONLY
1:74	READING TERRACES	CPT-1	N/A							
2:10	OFFICE	CPT-1	RB-1							
2:12	OFFICE	CPT-1								
2:13	OFFICE	CPT-1								
2:26	LOBBY	CPT-1								
2:27	MEETING ROOM	CPT-1								
2:28	MEETING ROOM	CPT-1								
2:29	HALLWAY	CPT-1								
2:29A	HALLWAY	CPT-1								
2:35	AUDITORIUM	CPT-1								
2:35.5	STORAGE?	CPT-1								
2:42	RECEPTION	CPT-1								
2:44	CORRIDOR	CPT-1								
2:45	SEMINAR	CPT-1								
2:46	COLLECTIONS AREA	CPT-1/CPT-2/CPT-3								NOTE 1
2:51	READING AREA	CPT-1								
2:54	GAMES ROOM	CPT-1								
2:55	ALCOVE	CPT-1								
2:58	OFFICE	CPT-1								
2:59	TUTORIAL ROOM	CPT-1								
2:59A	TUTORIAL ROOM	CPT-1								
2:60	SEMINAR ROOM	CPT-1								
2:61	OFFICE	CPT-1								
2:62	COPIERS	CPT-1								
2:67	READING TERRACE LANDING	CPT-1	N/A							
2:68	READING TERRACES	CPT-1	N/A							
3:08	RECEPTION	CPT-1	RB-2							NOTE 4
3:09	COATS	CPT-1								NOTE 4
3:10	OFFICE	CPT-1								NOTE 4
3:11	ADMINISTRATION WORK AREA	CPT-1								NOTE 4
3:12	OFFICE	CPT-1								NOTE 4
3:13	OFFICE	CPT-1								NOTE 4
3:15	OFFICE	CPT-1								NOTE 4
3:16	OFFICE	CPT-1								NOTE 4
3:17	OFFICE	CPT-1								NOTE 4
3:18	WORK AREA	CPT-1								NOTE 4
3:19	MEETING ROOM	CPT-1								NOTE 4
3:20	OFFICE	CPT-1								NOTE 4
3:21	CORRIDOR	CPT-1								NOTE 4

ROOM FINISH SCHEDULE CONTD

ROOM NO.	ROOM NAME	FLOOR	BASE	NORTH WALL	SOUTH WALL	EAST WALL	WEST WALL	CEILING	CEILING HEIGHT	NOTES
3:24	COPY ROOM	CPT-1	RB-2	N/A	N/A	N/A	N/A	N/A	EX.	NOTE 4
3:26	OFFICE									NOTE 4
3:27	FILE STORAGE									NOTE 4
3:28	OFFICE									NOTE 4
3:30	OFFICE									NOTE 4
3:34	OFFICE									NOTE 4
3:33	OFFICE									NOTE 4
3:35	OFFICE									NOTE 4
3:34	CORRIDOR									NOTE 4
3:35	COATS									NOTE 4
3:36	CONTROL ROOM	CPT-1/RB-2/RB-3								NOTE 4
3:38	OFFICE	CPT-1	RB-1							
3:39	OFFICE	CPT-1								
3:40	OFFICE	CPT-1								
3:47	OFFICE	CPT-1								
3:56	OFFICE	CPT-1								
3:57	OFFICE	CPT-1								
3:58	OFFICE	CPT-1								
3:59	OFFICE	CPT-1								
3:65	TRAINING ROOM	CPT-1	RB-2							NOTE 4
3:66	COATS	CPT-1								NOTE 4
3:67	OFFICE	CPT-1								NOTE 4
3:68	OFFICE	CPT-1	RB-1							
3:69	OFFICE	CPT-1								
3:72	COLLECTIONS AREA	CPT-1								
3:76	COLLECTIONS	CPT-1								
3:79	QUIET STUDY	CPT-1								
3:80	HALL	CPT-1								
3:86	OFFICE	CPT-1								
3:90	READING TERRACE LANDING	CPT-1	N/A							
3:91	READING TERRACES	CPT-1	N/A							
4:01	COLLECTIONS AREA	CPT-1	RB-1							NOTE 3
4:02	SERVICE COUNTER	RF-1	N/A							NOTE 3, 5
4:06	DISPLAY	CPT-1	RB-1							NOTE 3
4:09	READING AREA	CPT-1								NOTE 3
4:12	READING AREA	CPT-1								NOTE 3
4:18	CORRIDOR	CPT-1								NOTE 3
4:19	STAFF WORK AREA	CPT-1	PT-1							NOTE 2, 3
4:19A	OFFICE	CPT-1								NOTE 3
4:20	STAFF WORK AREA	CPT-1/RB-1	N/A							NOTE 3
4:21	CORRIDOR	CPT-1								NOTE 3
4:24	OFFICE	CPT-1								NOTE 3
4:34	LOCAL HISTORY ROOM	CPT-1								NOTE 3
4:35	COMPUTER TRAINING ROOM	CPT-1								NOTE 3
4:36	TUTORIAL ROOM	CPT-1								NOTE 3
4:37	STORAGE	CPT-1								NOTE 3
4:40	READING TERRACE LANDING	CPT-1	N/A							NOTE 3

ABBREVIATIONS: CPT - CARPET TILE RB - RUBBER FLOORING EX - EXISTING CB - CARPET BASE RB - RUBBER BASE PT - PAINT

FINISH SCHEDULE NOTES:

NOTE 1.: CARPET TO CARPET TRANSITIONS TO BE BUTTED WHETHER NEW TO NEW, OR NEW TO EXISTING.
 NOTE 2.: WALLS TO BE CLEANED & PATCHED AS NECESSARY PRIOR TO PAINTING. PATCH AND FILL HOLES.
 NOTE 3.: INSTALLATION METHOD ON RAISED FLOOR SYSTEM TO BE ADHESIVE DOT SYSTEM. CONTRACTOR TO CONFIRM SPEC WITH MANUFACTURER.
 NOTE 4.: 4.5" RUBBER BASE TO BE USED WHERE REPLACING EXISTING CARPET BASE.
 NOTE 5.: EXISTING RUBBER FLOORING UNDER SERVICE DESK TO BE REUSED IF FEASIBLE. OTHERWISE, SUPPLY & INSTALL NEW.

NOTES:

THESE DRAWINGS SHALL NOT BE SCALED.
 THE CONTRACTOR SHALL VERIFY THE SITE AND SANSIFY THEREOF ALL DIMENSIONS, DATA AND FIELD INFORMATION SHOWN ARE CORRECT.
 THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS AND CEILINGS PRIOR TO THE BEGINNING OF CONSTRUCTION AND ALL OPENINGS NOT SHOWN ON DRAWINGS.
 ALL OPENINGS THROUGH THE ASSEMBLIES ARE TO BE PRE STOPPED AND SEALED WITH UIC APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION AND PROVIDE A SMOKE TIGHT BARRIER.
 ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS & APPLICABLE CODES.
 THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING AND MAINTAINING ALL EXISTING CONDITIONS IDENTIFIED BY THE REMOVAL OF ALL TIES FORMING THE PART OF THE REMOVAL WORK.
 WHERE NEW FLOORING AND BASE IS TO BE INSTALLED IN EXISTING AREAS REFER TO FLOOR PLAN AND ROOM SCHEDULE THE EXISTING FLOORING SURFACE AND BASE MUST BE REMOVED, UNLESS OTHERWISE NOTED. ALL FLOOR SURFACES SHALL BE PREPARED IN ACCORDANCE TO MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF NEW FLOOR.
 WHERE EXISTING CEILING WALLS IS INDICATED ON THE ROOM SCHEDULE, THESE WALLS MUST BE CLEANED OF ANY EXISTING WALL COVERING, PATCHED & REPAIRED TO ACCEPT NEW MATERIAL, UNLESS OTHERWISE NOTED.

GENERAL NOTES:

1. ALL FINISHES LISTED ON THE FINISH LEGEND ON DRAWING A3.2 ARE SELECTED FOR DURABILITY AND OPERATIONAL FUNCTIONALITY. HOWEVER ALTERNATE FINISHES AND OR PRODUCTS MAY BE CONSIDERED AS AN APPROVED SUBSTITUTE AS PER MATERIALS MANAGEMENT POLICIES. CONTRACTOR TO REVIEW AND APPROVE ANY PROPOSED SUBSTITUTES IN ADVANCE.
 2. REFER TO DRAWINGS FOR CARPET TILE DIRECTION. MAIN CARPET TILE IS CPT-1.
 3. ALL PAINTS AND ADHESIVES TO BE LOW-VOC.
 4. ADHESIVE TO BE FULL SPREAD UNLESS OTHERWISE NOTED (REFER TO ROOM FINISH SCHEDULE FOR NOTED EXCEPTIONS). CONTRACTOR TO CONFIRM SPEC WITH MANUFACTURER.
 5. CONTRACTOR TO CONFIRM SUFFICIENT QUANTITIES OF CPT-1 AVAILABLE AND SUPPLY ADDITIONAL IF NECESSARY.

NO.	REVISION/DESCRIPTION	BY	DATE
0	ISSUED FOR CONSTRUCTION	CEA	02.18.2022
0	ISSUED FOR FINAL CLIENT APPROVAL	CEA	11.04.2021
0	ISSUED FOR CLIENT REVIEW	CEA	10.29.2021

SEALS

DRAWN BY	CHECKED BY	APPROVED
SERCEA	SERCEA	
2021.11.03	USER APPROVAL	

CITY OF WINNIPEG
 ASSETS & PROJECT MANAGEMENT DEPARTMENT
 MUNICIPAL ACCOMMODATIONS DIVISION

PROJECT
 TENDER NO. 139-2022
 INTERIOR RENOVATIONS FOR
 MILLENNIUM LIBRARY
 251 DONALD STREET

ROOM FINISH SCHEDULE AND NOTES