



187-2022 ADDENDUM 1

ADDITIONAL MEASURES TO CORRECT AIR INTAKE SNOW INFILTRATION - WPS HQ - 245 SMITH STREET

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL

ISSUED: April 13, 2022
BY: Jason Wiebe
TELEPHONE NO. 204 770-0245

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 4:00 p.m. Winnipeg time, **April 20, 2022**.

QUESTIONS AND ANSWERS

Q1: Is painting of the new duct insulation and drain line to match the existing required?

A1: Yes, paint new duct insulation and drain line to match existing.

Q2: There are some water stained ceiling tiles above the electrical room door, these would need to be removed to run the new electrical and controls. Will these damaged tiles need to be replaced?

A2: No, these existing ceiling tiles can remain.

Q3: Drawing M2 – 4.4 – Are the TS, HS, Snow-detector and Rain sensor provided by the Munters DFS manufacturer or integrated into the unit? If not please provide information on required sensors.

A3: Yes, these detector and sensors will be provided by manufacturer.

Q4: Drawing M1 – Note 2 – Drain line is to be heat traced but no power requirements are mentioned on the electrical drawings. Is this being powered by the snow/droplet separator?

A4: Revise Drawing M1 – Note 2 to read: “New 3” Diameter drain line from the new snow and droplet separator c/w insulation, **HEAT TRACE NOT REQUIRED**”