SEWER JUNCTION INFORMATION FROM SEWER VIDEO INSPECTION		
SEWER ID S-MA20015377		
DISTANCE FROM MH2013884		
DISTANCE	DIAMETER	CLOCK
4.2	200	7:00
4.2	150	10:00
9.4	150	10:00
19.6	150	10:00
19.6	150	11:00
19.6	150	2:00
23.9	150	12:00
27.3	150	10:00
27.3	150	2:00
35.6	150	10:00
35.6	150	1:00
35.6	150	2:00
42.8	150	10:00
42.8	150	2:00
49.6	150	10:00
49.6	150	2:00
49.8	150	11:00
57.4	150	10:00
57.4	150	2:00
64.7	150	10:00
64.7	150	2:00
66.1	200	10:00
66.1	200	2:00
72.4	150	10:00
72.4	150	2:00
79.0	150	11:00
80.5	150	11:00
80.5	150	2:00
83.4	150	2:00
88.0	150	10:00
88.0	150	2:00
95.6	150	10:00
95.6	150	2:00
103.3	150	10:00
103.3	150	2:00
110.6	150	10:00
110.6	150	2:00
118.8	150	10:00
118.8	150	2:00
126.0	150	10:00
126.0	150	2:00

WARNING

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:

1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.

2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.

SEE PROVINCIAL REGULATION 140/92 FOR DETAILS

WALNUT STREET

REMOVE AND REPLACE TOP 0.3m BRICK RISERS BELOW FRAME w/750 PRECAST CONC. RISERS.

S-MH20013884
RIM 232.440
INV W 225.310
INV E 225.310

REMOVE AND REPLACE TOP 0.9m CONC. RISERS BELOW FRAME w/750 PRECAST CONC. RISERS.

S-MH20013863
RIM 232.510
INV N 225.110
INV S 225.110

PURCELL AVE

127.8 OF 1200x1550 CONC CS TO BE LINED
S-MA20015377
(FULLY DETERIORATED)

PRESTON AVE

FOR INDEX SEE 13042

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
Stantec Consulting Ltd.
No. 1301

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

1:750 0 7.5 22.5 37.5m

TENDER NO. 212-2022

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE _____ DATE _____

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M.
ELEV.

NO.	REVISIONS	DATE	BY
2	ISSUED FOR TENDER	22.05.06	RS
1	ISSUED FOR REVIEW	22.04.29	RS

Stantec
311 Portage Avenue, Winnipeg, Manitoba
Tel 204-489-5900 Fax 204-453-9012

DESIGNED BY	RS	CHECKED BY	RS
DRAWN BY	OS	APPROVED BY	RS
HOR. SCALE: 1:750 VERTICAL:		RELEASED FOR CONSTRUCTION: SC	
DATE 22.03.15		DATE 22.05.04	

ENGINEER'S SEAL

CONSULTANT DRAWING NO.
C-102

Winnipeg

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT

2022 SEWER RENEWALS BY CIPP LINING (LARGE DIAMETER)
CONTRACT 3
WALNUT STREET
MH AT PRESTON AVE
TO MH AT PURCELL AVE

SHEET 04 OF 12

CAD FILE DRAWING NUMBER
20592c-101.dwg

CITY DRAWING NUMBER
13044

V:\1112\active\111220592\0300_drawing\0302_sheet_files\02_civil\20592c-101.dwg