



TENDER NO. 427-2022 ADDENDUM NO. 1

2022 SEWER RENEWALS BY CIPP LINING – CONTRACT 8

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: August 29, 2022
BY: Stacy Cournoyer
TELEPHONE NO. 204 986-2142

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

FORM B: PRICES

Replace: 427-2022 Electronic Form B: Prices with 427-2022 Addendum NO. 1 – Electronic Form B: Prices.

The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Added Temporary Pavement Restoration to Part C: Provisional Items.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, September 1, 2022.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D18.1 to read: The Contractor shall achieve Substantial Performance by June 2, 2023.

Revise: D19.1 to read: The Contractor shall achieve Total Performance by June 16, 2023.

PART E – SPECIFICATIONS

Revise: E13.3 (a) to read: Surface restoration shall be measured and paid in accordance with:

- (i) CW 3230 and CW3310 for concrete pavement restoration.
- (ii) CW 3325 for concrete sidewalk restoration.
- (iii) CW 3235 for miscellaneous concrete slab restoration.
- (iv) CW 3410 for asphaltic pavement restoration.

Add: E16 TEMPORARY SURFACE RESTORATIONS

E16. TEMPORARY SURFACE RESTORATIONS

E16.1 Further to clause 3.3 of CW 1130, the Contractor shall temporarily restore surfaces as follows:

- (a) backfill and level boulevards and grassed areas to match existing surface elevations,

- (b) cap excavations in street pavement with a 100 millimetre thick layer of “Concrete for Temporary Restoration of Utility Pavement Cuts” as specified in CW 3310,
- (c) cap excavations in sidewalk pavement with a 50 millimetre thick layer of “Concrete for Temporary Restoration of Utility Pavement Cuts” as specified in CW 3310,
- (d) insulate temporary concrete where required during 24hr curing period,
- (e) where curb has been removed as part of the pavement cut pour temporary curb using “Concrete for Temporary Restoration of Utility Pavement Cuts” as specified in CW 3310.
- (f) remove all temporary pavements prior to permanent restorations.

E16.2 The Contractor shall monitor and maintain temporarily restored surfaces as required until permanent restoration is complete.

E16.3 If, in the opinion of the Contract Administrator, temporarily restored surfaces are not being adequately maintained or were not properly constructed and pose a danger to the public, maintenance or reconstruction will be done by the City forces with no advance notification the Contractor.

E16.4 All costs associated with the maintenance or reconstruction of temporary pavement incurred by the City shall be deducted from future payments to the Contractor.

E16.5 Temporary surface restorations shall be measured on an area basis and paid for at the contract unit price for “Temporary Surface Restorations”, “a) street pavement” or “b) sidewalk”. The area to be paid for shall be the total number of square metres of street pavement or sidewalk temporarily restored, accepted and measured by the Contract Administrator.

E16.5.1 No measurement or payment will be made for the temporary restoration of barrier or lip curb.

E16.5.2 No measurement or payment will be made for the temporary restorations of boulevards and grassed areas/

E16.5.3 No measurement or payment will be made for the removal of temporary pavement prior to permanent restoration.

Add: E17 BACKFILL UNDER TEMPORARY SURFACE RESTORATIONS

E17. BACKFILL UNDER TEMPORARY SURFACE RESTORATIONS

E17.1 Use class 2 back fill in excavation under temporary street pavement and sidewalk where Class 3 backfill cannot be jetted and flooded due to cold weather.

E17.2 Class 2 backfill may be compacted in 600mm lifts where backhoe operated pneumatic plate compactors are used.

E17.3 Jet and flood Class 2, Class 3 and Class 5 backfilled excavations in spring when ground is not frozen prior to permanent restoration.

E17.4 No extra payment will be made for the installation of Class 2 backfill under temporary street pavement and sidewalk.