

# **APPENDIX 'B'**

# **GEOTECHNICAL REPORT**

April 7, 2022

KGS Group  
865 Waverley Street  
Winnipeg, Manitoba R3T 5P4

Attention: Mr. Craig Rowbotham, P.Eng.  
Municipal Assistant Department Head

**Re: 2022 Redwood Avenue Reconstruction – Winnipeg, Manitoba  
Report of Geotechnical Investigation and Test Results**

Dear Mr. Rowbotham

This letter summarizes KGS Group’s geotechnical results for the 2022 Redwood Avenue Reconstruction Project in Winnipeg, Manitoba. KGS Group’s scope of services for this project was outlined in our proposal no. 22-000-0100 titled “2022 Redwood Avenue Reconstruction - Geotechnical” dated February 3, 2022.


KGS Group was retained to complete subsurface investigations along Redwood Avenue. This report details the results of the investigation.

## 1.0 PAVEMENT INVESTIGATIONS

### 1.1 Coring and Sampling

Coring and sampling were completed at five (5) locations along Redwood Avenue between Main Street and Salter Street, in accordance with the City of Winnipeg RFP 476-2021 Appendix B – CoW Site Investigation Requirements for Public Works Street Projects. Figure 1 shows the locations of the test holes and Table 1 provides the location descriptions and coordinates of the test holes.

**FIGURE 1: TEST HOLE LOCATION PLAN**



**TABLE 1: TEST HOLE LOCATION DESCRIPTIONS AND COORDINATES**

Location ID	Locations	Approximate UTM Coordinates <sup>1</sup>		Surface Elevation (m)
		Northing (m)	Easting (m)	
TH22-01	Redwood Ave - 2m from EB curb, 36m E of Salter St.	5,531,321	633,725	231.27
TH22-02	Redwood Ave - 2m from EB curb, 14m W of Aikins St.	5,531,259	633,852	231.44
TH22-03	Redwood Ave - 2m from EB curb, 79m E of Aikins St.	5,531,215	633,947	231.01
TH22-04	Redwood Ave - 2m from EB curb, 15m E of Charles St.	5,531,157	634,067	231.14
TH22-05	Redwood Ave - 2m from EB curb, 25m W of Main St.	5,531,133	634,122	231.06

**Notes:** 1. Test hole locations were recorded in the field using a handheld GPS unit with accuracy of ±5m.

Test holes were advanced to sufficient depth below the pavement surfacing to explore subgrade and subsurface soil, moisture and groundwater conditions. Test holes TH22-01 to TH22-03 were only drilled to depths of 1.5 m (5 ft) due to limited utility locate information in the area north of Aikins Street. Test holes TH22-04 and TH22-05

were drilled to the planned depths of 3.0 m (10 ft). Test holes were backfilled with auger cuttings and patched at the surface with 100 mm of asphalt cold patch.

Subsurface soil samples were retrieved every 0.3 m (1 ft) throughout the subgrade investigations. Bulk samples of the pavement subgrade material was also retrieved from each test hole to be used for moisture-density relationship (standard Proctor) and California Bearing Ratio (CBR) tests.

## 1.2 Laboratory Testing

Laboratory tests were completed on select soil samples. Testing was completed in a Winnipeg, Manitoba laboratory certified by the Canadian Council of Independent Laboratories (CCiL). Laboratory testing included 30 moisture contents, four (4) Atterberg Limits, four (4) particle size analysis. One composite sample of subgrade soil collected from TH22-03, TH22-04 and TH22-05 was tested for standard Proctor, and CBR.

## 2.0 INVESTIGATION RESULTS

### 2.1 Pavement Surfacing

Coring and sampling were completed for five (5) test holes along Redwood Avenue. The 150 mm diameter cores obtained of the existing pavement were measured in the field, and pavement types and thicknesses are shown in Table 2 below. Upon completion of coring, KGS measured the base and investigated the subgrade below the pavement structure using a truck mounted drill rig.

**TABLE 2: PAVEMENT SURFACING THICKNESSES**

<b>Location ID</b>	<b>Pavement Type</b>	<b>Pavement Thickness (mm)</b>	<b>Subgrade / Base Type</b>	<b>Base Thickness (mm)</b>
TH22-01	Asphalt over Concrete	101 over 180	Clay (CH)	-
TH22-02	Asphalt over Concrete	25 over 203	Clay (CH)	-
TH22-03	Asphalt over Concrete	76 over 177	Gravel (GP)	104
TH22-04	Asphalt over Concrete	114 over 152	Sandy Gravel (GP)	38
TH22-05	Asphalt over Concrete	76 over 229	Clay (CH)	-

Five (5) test holes were drilled rather than the six (6) as mentioned in the proposal because the project team agreed that sufficient data would be collected from five (5) evenly spaced test holes along Redwood Ave., and would also allow the drilling investigation be completed in less time.

A photo log of the road surfacing cores is attached in Appendix A.

## 2.2 Stratigraphy

The attached Figure 2, Section A-A', provides a profile of the stratigraphy encountered between each test hole and summary test hole logs are attached in Appendix B. The results of the laboratory testing are incorporated with soil type descriptions listed below. A summary table of index tests and the laboratory test reports are attached in Appendix C. Descriptions of the general stratigraphy encountered in the test holes are summarized below.

**Asphalt** – Asphalt surfacing was encountered at all five (5) test hole locations. The asphalt was black with 25 mm (max) diameter sub-rounded aggregate and ranged in thickness from 25 to 114 mm.

**Concrete** – Concrete was encountered underlying the asphalt in all five (5) test holes. The concrete was grey with 40 mm (max) rounded aggregate and ranged in thickness from 152 to 229 mm.

**Poorly Graded Gravel (GP)** – 40mm (1.6 in) of poorly graded gravel base was observed underlying the concrete pavement in test holes TH22-03 and TH22-04. The gravel was brown in colour, damp, compact and frozen.

**Clay (CH)** – High plasticity clay was encountered below the surfacing pavement in test holes TH22-01, TH22-02 and TH22-05 and underlying the poorly graded gravel in TH22-03 and TH22-04. The clay was dark brown in colour, moist and frozen.

Undrained shear strength of the clay was estimated in the field during drilling using a handheld Torvane and ranged from 50 to 90 kPa below the frost. Two (2) Atterberg limits completed on clay soil samples from a depth of 0.3 m (1 ft) classified the material as having high plasticity. An Atterberg limit on a sample from 0.9 m (3 ft) was classified as having low plasticity. Grain size analyses completed on the same samples indicated 0% gravel, 2% sand, 36 to 76% silt and 22 to 62% clay. Moisture contents ranged from 26 to 51%.

A standard Proctor was completed on a composite sample from test holes TH22-03, TH22-04 and TH22-05 from depths ranging from 0.30 to 0.91 m. The test indicated a standard proctor maximum dry density (SPMDD) of 1,520 kg/m<sup>3</sup> and an optimum moisture content of 24.5%. The CBR-value for the same sample recompacted to 95% of the SPMDD at 0.1% above optimum, was measured to be 2.

**Clay (CL)** – A 1.2 m (3.9 ft) thick layer of low plasticity clay was encountered at a depth of 0.6 below grade in test hole TH22-05. The clay was light brown in colour, moist, soft, frozen and contained trace sand.

An Atterberg limit completed on the clay soil from a depth of 0.6 m (2 ft) classified the soil as having low plasticity. A grain size analysis completed on the same sample indicated 0% gravel, 1% sand, 79% silt and 20% clay. Moisture contents ranged from 22 to 28%.

**Silt (ML)** – Low plasticity silt was encountered below the clay in test holes TH22-01 and TH22-03. The silt was light brown in colour, damp to moist, soft, frozen and contained trace clay and trace sand. Moisture contents in the silt ranged from 23 to 48%.

### 3.0 CLOSURE

Should you have any questions regarding the enclosed information or require additional information, please contact the undersigned.

Prepared By:



Trevor Schellenberg, P.Eng.  
Geotechnical Engineer

Approved By:



Taunya Ernst, P.Eng., P.E., P.G.  
Senior Geotechnical Engineer

KH/te/cs  
Attached

## STATEMENT OF LIMITATIONS AND CONDITIONS

### Limitations

This report has been prepared for KGS Group in accordance with the agreement between KGS Group's Geotechnical and Municipal departments (the "Agreement"). This report represents KGS Group's professional judgment and exercising due care consistent with the preparation of similar reports. The information, data, recommendations and conclusions in this report are subject to the constraints and limitations in the Agreement and the qualifications in this report. This report must be read as a whole, and sections or parts should not be read out of context.

This report is based on information made available to KGS Group by KGS Group. Unless stated otherwise, KGS Group has not verified the accuracy, completeness or validity of such information, makes no representation regarding its accuracy and hereby disclaims any liability in connection therewith. KGS Group shall not be responsible for conditions/issues it was not authorized or able to investigate or which were beyond the scope of its work. The information and conclusions provided in this report apply only as they existed at the time of KGS Group's work.

### Third Party Use of Report

Any use a third party makes of this report or any reliance on or decisions made based on it, are the responsibility of such third parties. KGS Group accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions undertaken based on this report.

### Geotechnical Investigation Statement of Limitations


The geotechnical investigation findings and recommendations of this report were prepared in accordance with generally accepted professional engineering principles and practice. The findings and recommendations are based on the results of field and laboratory investigations, combined with an interpolation of soil and groundwater conditions found at and within the depth of the test holes drilled by KGS Group at the site at the time of drilling. If conditions encountered during construction appear to be different from those shown by the test holes drilled by KGS Group or if the assumptions stated herein are not in keeping with the design, KGS Group should be notified in order that the recommendations can be reviewed and modified if necessary.

# FIGURE 2

---

Section A-A'

FENCE W/O WELL DATA PLOT C:\USERS\KGAUTHIER\DRIVE - KGS GROUP\FM\22-0535-006\22-0535-006 REDWOOD AVE\_GEOTECHNICAL LOGS.GPJ



Horizontal Scale (meters)  
Vertical Exaggeration: 48x

**Lithology Graphics**

- Asphalt
- Concrete
- Clay (CH, high plasticity)
- Silt (ML)
- Poorly Graded Gravel (GP)
- Clay (CL, low plasticity)

**Legend**

- Test Hole ID
- Test Hole Lithology
- Water Level During Drilling
- Water Level Upon Completion
- Water Level Static/Remeasured
- SPT, N-Value
- Torvane Cu (kPa)
- Moisture Content (%)
- >> N-value greater than 100

<b>KGS</b> <small>GROUP</small>	<b>KGS GROUP</b>
2022 Redwood Reconstruction Project - Geotech	
<b>A-A'</b>	
<b>Apr 2022</b>	<b>Figure 02</b>

# APPENDIX A

---

Core Photo Log



Photo 1: TH22-01 Core Surface



Photo 2: TH22-01 Core Profile



Photo 3: TH22-02 Core Surface



Photo 4: TH22-02 Core Profile



Photo 5: TH22-03 Core Surface



Photo 6: TH22-03 Core Profile



Photo 7: TH22-04 Core Surface



Photo 8: TH22-04 Core Profile



Photo 9: TH22-05 Core Surface



Photo 10: TH22-05 Core Profile

# APPENDIX B

---

Test Hole Logs

<b>CLIENT</b>	<b>KGS GROUP</b>	<b>PROJECT NO.</b>	22-0535-006
<b>PROJECT</b>	<b>2022 Redwood Reconstruction Project - Geotech</b>	<b>SURFACE ELEV.</b>	231.27 m
<b>LOCATION</b>	Winnipeg, Manitoba	<b>DATE DRILLED</b>	2-25-2022
<b>DESCRIPTION</b>	Redwood Ave - 2m from EB curb, 36m E of Salter St.	<b>UTM (m)</b>	N 5,531,321 E 633,725 Zone 14
<b>DRILL RIG / HAMMER</b>	Mobile B40 Truck Mounted Drill Rig		
<b>METHOD(S)</b>	0.0 m to 0.3 m: Roadway coring 0.3 m to 1.5 m: 125 mm $\phi$ SSA		

ELEVATION (m)	DEPTH (m) (ft)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEV (m)	WATER LEVEL	SAMPLE TYPE	NUMBER / RUN	PL MC LL		
								Cu TORVANE (kPa) ◆	qu POCKET PEN (kPa) ★	SPT (N) BLOWS/0.30 m ▲
			<b>ASPHALT</b> - 101 mm, Black, sub-angular granular.	231.2			S1			
			<b>CONCRETE</b> - 180 mm, Grey, sub-rounded granular (diameter < 40mm).	231.0			S2			
231			<b>CLAY (CH)</b> - Dark brown, moist, stiff, high plasticity, and silt, trace sand, frozen. - LL=74, PL=24, PI=50 at 0.3 m. - PSA: 0% gravel, 2% sand, 38% silt, 60% clay at 0.3 m.  - silty, trace sand, light brown, low plasticity below 0.6 m.	230.5			S3	◆	★	▲
			<b>SILT (ML)</b> - Light brown, damp to moist, soft, low plasticity, trace clay, frozen.	229.7			S4	◆	★	▲
	1						S5	◆	★	▲
230							S6	◆	★	▲
	5		- not frozen below 1.4 m.							
			Notes: 1. End of test hole at 1.5 m. 2. Test hole caved to 1.3 m upon completion of drilling. 3. Test hole backfilled with auger cuttings. 4. Test hole sealed at the surface with 100mm of asphalt cold patch.							
	2									
229										
	3									
228	10									

<b>WATER LEVELS</b>	∇ During Drilling/Digging	on 2-25-2022 None Encountered
	▼ Upon Completion	on 2-25-2022 Dry

<b>CONTRACTOR</b> Maple Leaf Drilling Ltd.	<b>INSPECTOR</b> K. GAUTHIER
<b>APPROVED</b> DRAFT	<b>DATE</b>

KGS\_LOG\_C:\USERS\KGAUTHIER\DRIVE - KGS GROUP\FMS\22-0535-006\22-0535-006\22-0535-006 REDWOOD AVE\_GEO TECHNICAL LOGS.GPJ


<b>CLIENT</b>	KGS GROUP	<b>PROJECT NO.</b>	22-0535-006
<b>PROJECT</b>	2022 Redwood Reconstruction Project - Geotech	<b>SURFACE ELEV.</b>	231.44 m
<b>LOCATION</b>	Winnipeg, Manitoba	<b>DATE DRILLED</b>	2-25-2022
<b>DESCRIPTION</b>	Redwood Ave - 2m from EB curb, 14m W of Aikins St.	<b>UTM (m)</b>	N 5,531,259 E 633,852 Zone 14
<b>DRILL RIG / HAMMER</b>	Mobile B40 Truck Mounted Drill Rig		
<b>METHOD(S)</b>	0.0 m to 0.2 m: Roadway coring 0.2 m to 1.5 m: 125 mm $\phi$ SSA		

ELEVATION (m)	DEPTH (m) (ft)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	WATER LEVEL	SAMPLE TYPE	NUMBER / RUN	SPT (N) BLOWS/0.30 m ▲			
							20	40	60	80
			<p><b>ASPHALT</b> - 25 mm, Black, sub-angular granular (diameter &lt; 25mm). /231.4</p> <p><b>CONCRETE</b> - 203 mm, Grey, rounded granular (diameter &lt; 40mm). 231.2</p> <p><b>CLAY (CH)</b> - Dark grey, moist, stiff, high plasticity, frozen.</p> <p>- silty, brown below 0.8 m.</p> <p>- not frozen below 1.4 m.</p>			S1				
231						S2	●			
	1					S3	●			
	5					S4	●			
230						S5	●			
			<p>Notes:</p> <ol style="list-style-type: none"> <li>End of test hole at 1.5 m.</li> <li>Test hole remained open to 1.5 m upon completion of drilling.</li> <li>Test hole backfilled with auger cuttings.</li> <li>Test hole sealed at the surface with 100mm of asphalt cold patch.</li> </ol>							
	2									
	10									
229										
	3									
228										

<b>WATER LEVELS</b>	∇ During Drilling/Digging	on 2-25-2022 None Encountered	<b>CONTRACTOR</b>	<b>INSPECTOR</b>
	▼ Upon Completion	on 2-25-2022 Dry	Maple Leaf Drilling Ltd.	K. GAUTHIER
			<b>APPROVED</b>	<b>DATE</b>
			DRAFT	

KGS\_LOG\_C:\USERS\KGAUTHIER\DRIVE - KGS GROUP\FMS\22-0535-006\22-0535-006 REDWOOD AVE\_GEOTECHNICAL LOGS.GPJ


<b>CLIENT</b>	<b>KGS GROUP</b>	<b>PROJECT NO.</b>	22-0535-006
<b>PROJECT</b>	<b>2022 Redwood Reconstruction Project - Geotech</b>	<b>SURFACE ELEV.</b>	231.01 m
<b>LOCATION</b>	Winnipeg, Manitoba	<b>DATE DRILLED</b>	2-25-2022
<b>DESCRIPTION</b>	Redwood Ave - 2m from EB curb, 79m E of Aikins St.	<b>UTM (m)</b>	N 5,531,215 E 633,947 Zone 14
<b>DRILL RIG / HAMMER</b>	Mobile B40 Truck Mounted Drill Rig		
<b>METHOD(S)</b>	0.0 m to 0.3 m: Roadway coring 0.3 m to 1.5 m: 125 mm $\phi$ SSA		



KGS\_LOG\_C:\USERS\KGAUTHIER\DRIVE - KGS GROUP\FMS\22-0535-006\22-0535-006 REDWOOD AVE\_GEOTECHNICAL LOGS.GPJ

<b>WATER LEVELS</b>	▽ During Drilling/Digging	on 2-25-2022 None Encountered	<b>CONTRACTOR</b>	<b>INSPECTOR</b>
	▼ Upon Completion	on 2-25-2022 Dry	Maple Leaf Drilling Ltd.	K. GAUTHIER
			<b>APPROVED</b>	<b>DATE</b>
			DRAFT	


<b>CLIENT</b>	<b>KGS GROUP</b>	<b>PROJECT NO.</b>	22-0535-006
<b>PROJECT</b>	<b>2022 Redwood Reconstruction Project - Geotech</b>	<b>SURFACE ELEV.</b>	231.14 m
<b>LOCATION</b>	Winnipeg, Manitoba	<b>DATE DRILLED</b>	2-25-2022
<b>DESCRIPTION</b>	Redwood Ave - 2m from EB curb, 15m E of Charles St.	<b>UTM (m)</b>	N 5,531,157 E 634,067 Zone 14
<b>DRILL RIG / HAMMER</b>	Mobile B40 Truck Mounted Drill Rig		
<b>METHOD(S)</b>	0.0 m to 0.3 m: Roadway coring 0.3 m to 3.0 m: 125 mm $\phi$ SSA		



KGS\_LOG\_C:\USERS\KGAUTHIER\DRIVE - KGS GROUP\FMS\22-0535-006\22-0535-006 REDWOOD AVE\_GEOTECHNICAL LOGS.GPJ

<b>WATER LEVELS</b>	▽ During Drilling/Digging	on 2-25-2022 None Encountered	<b>CONTRACTOR</b>	<b>INSPECTOR</b>
	▼ Upon Completion	on 2-25-2022 Dry	Maple Leaf Drilling Ltd.	K. GAUTHIER
			<b>APPROVED</b>	<b>DATE</b>
			DRAFT	

<b>CLIENT</b>	<b>KGS GROUP</b>	<b>PROJECT NO.</b>	22-0535-006
<b>PROJECT</b>	<b>2022 Redwood Reconstruction Project - Geotech</b>	<b>SURFACE ELEV.</b>	231.06 m
<b>LOCATION</b>	Winnipeg, Manitoba	<b>DATE DRILLED</b>	2-25-2022
<b>DESCRIPTION</b>	Redwood Ave - 2m from EB curb, 25m W of Main St.	<b>UTM (m)</b>	N 5,531,133
<b>DRILL RIG / HAMMER</b>	Mobile B40 Truck Mounted Drill Rig		E 634,122 Zone 14
<b>METHOD(S)</b>	0.0 m to 0.3 m: Roadway coring 0.3 m to 3.0 m: 125 mm $\phi$ SSA		



KGS\_LOG\_C:\USERS\KGAUTHIER\DRIVE - KGS GROUP\FMS\22-0535-006\22-0535-006 REDWOOD AVE\_GEO TECHNICAL LOGS.GPJ

<b>WATER LEVELS</b>	$\nabla$ During Drilling/Digging	on 2-25-2022 None Encountered	<b>CONTRACTOR</b>	<b>INSPECTOR</b>
	$\nabla$ Upon Completion	on 2-25-2022 Dry	Maple Leaf Drilling Ltd.	K. GAUTHIER
			<b>APPROVED</b>	<b>DATE</b>
			DRAFT	

# KEY TO SYMBOLS

## LITHOLOGIC SYMBOLS

-  Asphalt
-  Clay (CH, high plasticity)
-  Clay (CL, low plasticity)
-  Concrete
-  Poorly Graded Gravel (GP)
-  Silt (ML)

## SAMPLER SYMBOLS

-  Auger Grab
-  Core Barrel

## WELL CONSTRUCTION SYMBOLS

## ABBREVIATIONS

- |   |   |
|---|---|
| <ul style="list-style-type: none"> <li>LL - Liquid Limit</li> <li>PL - Plastic Limit</li> <li>PI - Plastic Index</li> <li>MC - Moisture Content</li> <li>DD - Dry Density</li> <li>NP - Non-Plastic</li> <li>-200 - Percent Passing No. 200 Sieve</li> <li>TV - Torvane (kPa)</li> <li>PP - Pocket Penetrometer (kPa)</li> <li>PSA - Particle Size Analysis</li> <li>TOC - Top Of Casing</li> </ul> | <ul style="list-style-type: none"> <li>PN - Pneumatic Piezometer</li> <li>VW - Vibrating Wire Piezometer</li> <li>PID - Photoionization Detector</li> <li>ppm - Parts Per Million</li> <li>∇ - Water Level During Drilling</li> <li>▼ - Water Level Upon Completion of Drilling</li> <li>∇ - Water Level Remeasured/Static</li> </ul> |
|---|---|

# APPENDIX C

---

Laboratory Testing Results

# SUMMARY OF INDEX TESTS

Sheet 1 of 1

Test Hole ID	Depth (m)	Classification	Liquid Limit	Plastic Limit	Plasticity Index	Maximum Size (mm)	%<75 µm Sieve	Water Content (%)	Dry Density (kN/m <sup>3</sup> )	Specific Gravity	Saturation (%)	Void Ratio
TH22-01	0.3	CH	74	24	50	1.18	98.1	35				
TH22-01	0.6	CH						29				
TH22-01	0.9	ML						27				
TH22-01	1.2	ML						48				
TH22-02	0.3	CH						27				
TH22-02	0.6	CH						26				
TH22-02	0.9	CH						26				
TH22-02	1.2	CH						29				
TH22-03	0.3	CH						44				
TH22-03	0.6	CH						37				
TH22-03	0.9	ML	28	17	11	4.75	98.1	28				
TH22-03	1.2	ML						23				
TH22-04	0.3	CH						51				
TH22-04	0.6	CH						44				
TH22-04	0.9	CH						34				
TH22-04	1.2	CH						32				
TH22-04	1.5	CH						28				
TH22-04	1.8	CH						35				
TH22-04	2.1	CH						34				
TH22-04	2.4	CH						40				
TH22-04	2.7	CH						49				
TH22-05	0.3	CH	87	22	65	2	97.9	37				
TH22-05	0.6	CL	29	16	13	4.75	98.5	28				
TH22-05	0.9	CL						22				
TH22-05	1.2	CL						24				
TH22-05	1.5	CL						23				
TH22-05	1.8	CH						36				
TH22-05	2.1	CH						49				
TH22-05	2.4	CH						50				
TH22-05	2.7	CH						49				


\* Moisture conditioned and remolded sample.  
 \*\* Assumed specific gravity.



**CLIENT** KGS GROUP  
**PROJECT NAME** 2022 Redwood Reconstruction Project - Geotech  
**TESTED BY** Stantec

**PROJECT NO.** 22-0535-006  
**LOCATION** Winnipeg, Manitoba  
**DATE TESTED** March 2022

# ATTERBERG LIMITS



	HOLE	DEPTH (m)	SAMPLE #	LL	PL	PI	SAND (%)	SILT (%)	CLAY (%)	SILT & CLAY (%)	MC (%)	CLASSIFICATION
●	TH22-01	0.3	S3	74	24	50	2	38	60	98	35	CH
■	TH22-03	0.9	S4	28	17	11	2	76	22	98	28	CL
▲	TH22-05	0.3	S2	87	22	65	2	36	62	98	37	CH
★	TH22-05	0.6	S3	29	16	13	1	79	20	99	28	CL


A:\LINE PLOT C:\USERS\KGAUTHIER\DRIVE - KGS GROUP\FMS\22-0535-006\22-0535-006 REDWOOD AVE\_ GEOTECHNICAL LOGS.GPJ



**CLIENT** KGS GROUP  
**PROJECT NAME** 2022 Redwood Reconstruction Project - Geotech  
**TESTED BY** Stantec

**PROJECT NO.** 22-0535-006  
**LOCATION** Winnipeg, Manitoba  
**DATE TESTED** March 2022

# GRAIN SIZE DISTRIBUTION



GRAVEL		SAND			SILT	CLAY
coarse	fine	coarse	medium	fine		

	HOLE	DEPTH (m)	SAMPLE #	GRAVEL (%)	SAND (%)	SILT (%)	CLAY (%)	SILT & CLAY (%)	Cu	Cc	CLASSIFICATION
●	TH22-01	0.3	S3	0	2	38	60	98			CH
⊠	TH22-03	0.9	S4	0	2	76	22	98			CL
▲	TH22-05	0.3	S2	0	2	36	62	98			CH
★	TH22-05	0.6	S3	0	1	79	20	99			CL

SIEVE ANALYSIS C:\USERS\KGAUTHIER\ONEEDRIVE - KGS GROUP\FMS\22-0535-006\22-0535-006 REDWOOD AVE\_GEO TECHNICAL LOGS.GPJ



**CLIENT** KGS GROUP  
**PROJECT NAME** 2022 Redwood Reconstruction Project - Geotech  
**TESTED BY** Stantec

**PROJECT NO.** 22-0535-006  
**LOCATION** Winnipeg, Manitoba  
**DATE TESTED** March 2022

# PROCTOR TEST REPORT

TO KGS Group Inc.  
3rd Floor - 865 Waverley St  
Winnipeg, MB  
R3T 5P4

CLIENT KGS Group Inc.  
C.C. KGS Group Inc.

ATTN: Kayden Gauthier

PROJECT Redwood Avenue

PROJECT NO. 123315924


PROCTOR NO. 1

DATE SAMPLED 2022.Mar.04

DATE RECEIVED 2022.Mar.08

DATE TESTED 2022.Mar.11

INSITU MOISTURE	3.7 %	COMPACTION STANDARD	Standard Proctor, ASTM D698
TESTED BY	Donald Eliazar	COMPACTION PROCEDURE	A: 101.6mm Mold, Passing 4.75mm
MATERIAL IDENTIFICATION		RAMMER TYPE	Manual
MATERIAL USE	Subgrade	PREPARATION	Dry
MAX. NOMINAL SIZE		OVERSIZE CORRECTION METHOD	None
MATERIAL TYPE	Clay	RETAINED 4.75mm SCREEN	
SUPPLIER	Existing material		
SOURCE	Composite		



TRIAL NUMBER	WET DENSITY (kg/m <sup>3</sup> )	DRY DENSITY (kg/m <sup>3</sup> )	MOISTURE CONTENT (%)
1	1696	1461	16.1
2	1798	1497	20.1
3	1887	1519	24.2
4	1906	1486	28.3

	MAXIMUM DRY DENSITY (kg/m <sup>3</sup> )	OPTIMUM MOISTURE CONTENT (%)
CALCULATED	1520	24.5
OVERSIZE CORRECTED		

COMMENTS

Material tested is a composite sample obtained from TH22-03, S06, TH22-04, S11 & TH22-05, S02.

REVIEWED BY  Jason Thompson, C.E.T.



## ASTM D1883 - CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOILS

TO KGS Group Inc.  
 3rd Floor - 865 Waverley St.  
 Winnipeg, MB  
 R3T 5P4

PROJECT Redwood Avenue

PROJECT NO. 123315924

ATTN: Taunya Ernst

REPORT NO. 1 (Data page - see Page 2 for Chart)

DATE SAMPLED: 2022.Mar.04

DATE RECEIVED: 2022.Mar.08

DATE TESTED: 2022.Mar.14

SAMPLED BY: KGS Group Inc.

SUBMITTED BY: KGS Group Inc.

TESTED BY: Donald Eliazar

**MATERIAL IDENTIFICATION**

MATERIAL USE	Subgrade	SUPPLIER	Existing Material
MAX. NOMINAL SIZE	< 4.75 mm	SOURCE	Redwood Avenue
MATERIAL TYPE	Clay	SAMPLE LOCATION	Testholes
SPECIFICATION	Not Applicable	STANTEC SAMPLE NO.	4105


IMMERSION PERIOD	96 ± 2 hr	TARGET MAX. DRY DENSITY	1520 kg/m <sup>3</sup>
CONDITION OF SAMPLE	Soaked	TARGET OPTIMUM MOISTURE	24.5 %
SURCHARGE MASS	4.54 kg	AS-COMPACTED MAX. DRY DENSITY	1444 kg/m <sup>3</sup>
SWELL OF SAMPLE	4.2%	AS-COMPACTED MOISTURE CONTENT	24.6 %
		POST-TEST MOISTURE CONTENT (TOP 25 mm)	37.4 %

<b>CBR VALUE AT 2.54 mm PENETRATION</b>	<b>2.0</b>
<b>CBR VALUE AT 5.08 mm PENETRATION</b>	<b>1.8</b>

**COMMENTS:**

Sample prepared to 95% of the maximum dry density at the optimum moisture content as determined from ASTM D698.  
 Material tested is a composite sample obtained from TH22-03 S06, TH22-04 S11 & TH22-05 S02.  
 We appreciate the opportunity to assist you on this project. Please contact the undersigned if you have any questions regarding this report.

REPORT DATE 2022.Mar.21

REVIEWED BY  Jason Thompson, C.E.T.  
 Principal - Manager of Materials Testing Services

Reporting of these test results constitutes a testing service only. Engineering interpretation or evaluation of the test results is provided on written request. The data presented is for sole use of client stipulated above. Stantec is not responsible, nor can be held liable, for the use of this report by any other party, with or without the knowledge of Stantec.

## ASTM D1883 - CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOILS

TO KGS Group Inc.  
 3rd Floor - 865 Waverley St.  
 Winnipeg, MB  
 R3T 5P4

PROJECT Redwood Avenue

PROJECT NO. 123315924

ATTN: Taunya Ernst

REPORT NO. 1 (Chart page - See Page 1 for Data)

DATE SAMPLED: 2022.Mar.04

DATE RECEIVED: 2022.Mar.08


DATE TESTED: 2022.Mar.14

SAMPLED BY: KGS Group Inc.

SUBMITTED BY: KGS Group Inc.

TESTED BY: Donald Eliazar

**LOAD PENETRATION CURVE**



REPORT DATE 2022.Mar.21

Reporting of these test results constitutes a testing service only. Engineering interpretation or evaluation of the test results is provided on written request. The data presented is for sole use of client stipulated above. Stantec is not responsible, nor can be held liable, for the use of this report by any other party, with or without the knowledge of Stantec.