



54-2022 ADDENDUM 3

KILDONAN-REDWOOD FEEDER MAIN CROSSING REHABILITATION

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: February 17, 2022
BY: N. Kehler
TELEPHONE NO. 204-928-7436

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

FORM B: PRICES

Replace: 54-2022 Addendum 2-Form B: Prices with 54-2022 Addendum 3 - Form B: Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R2): Add Items No. 3(a) and 3(b).

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: B2.1 The Submission Deadline is 12:00 noon Winnipeg time, February 23, 2022.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D19.1 to read: The Contractor shall achieve Substantial Performance within thirty (30) Working Days of the commencement of the Work as specified in D16, or by August 15, 2022, whichever comes first.

PART E – SPECIFICATIONS

Add: E11.5.2(a)(iv) In lieu of blast cleaning, the West Tunnel Shaft pipe penetrations may be prepared to bare metal by approved mechanical means to SSPC SP11.

Revise: E12.2.1(b)(i) to read: The existing feeder main crossing was constructed with an interior coal tar epoxy lining. The Contractor shall select appropriate cleaning methods and undertake reasonable efforts to preserve the existing interior pipe coatings wherever it is possible and practical to do so.

Revise: E12.7.1(a) to read: Pipeline Cleaning will be paid on a daily basis with an hourly overtime rate, at the respective unit rates for "600 mm Feeder Main Cleaning and Lining Preparation Work" as listed in Form B: Prices.

Add: E12.7.1(d): Time measured will be based on on-site availability of the Contractor's crews, from the time crews are present on site until work is complete and site is secured for the shift, as certified by the Contract Administrator.

- Add E12.7.1(e): Daily Cleaning Rate will apply for each day of cleaning activity, up to a maximum of 10 hours. Hourly overtime rate will apply for each hour or measurable portion thereof in excess of the daily maximum of 10 hours per day.
- Add E12.7.1(f): The supply of pigs and other consumable materials for pipeline cleaning will be considered incidental to "600 mm Feeder Main Cleaning and Lining Preparation Work" and will not be measured for payment.
- Add E12.7.1(g): Flushing of pipelines for the purposes of debris removal will be considered incidental to "600 mm Feeder Main Cleaning and Lining Preparation Work" and will not be measured for payment.