

2 L-103 PLANTING PLAN
Scale: 1:200

north

LEGEND

- APPROX. LIMIT OF CONSTRUCTION
- PROPERTY LINE
- SETBACK
- CIP CONC. BENCH W/ WOOD TOP
- BOLLARD
- REGULATORY SIGN
- PARKING RECEPTACLE - SEE ARCHITECTURAL
- FLAGPOLE
- EXTERIOR POST LIGHTING - SEE ELECTRICAL
- LIGHT STANDARDS
- EXISTING TREE TO BE PROTECTED - SEE SPECS.

Plant Schedule

Qty	Common Name	Botanical Name	Size	Comments
Deciduous Trees				
4	**American Linden**	Tilia americana	65 mm cal.	12 major branches in well formed head 1.5m above grade, B&B, wire basket. Double stake.
5	**Tatarian Maple**	Acer Tataricum 'Hot Wings'	65 mm cal.	12 major branches in well formed head 1.5m above grade, B&B, wire basket. Double stake.
9	**Dropmore Linden**	Tilia x Flavescens 'Dropmore'	65 mm cal.	12 major branches in well formed head 1.5m above grade, B&B, wire basket. Double stake.
Coniferous Trees				
4	**White Spruce**	Picea glauca	1.8 m ht.	Evenly branched, full bushy trees, no broken leaders, well branced to grade. B&B or tree mover, wire basket.
Deciduous Shrubs				
80	**Alpine Currant**	Ribes alpinum 'Schmidt'	400 to 500 mm ht.	Well formed bushy shrub, min. 5 major basal branches, even growth. Container stock, 3 gal. pot min.
102	**Goldflame Spirea**	Spiraea x bumalda 'Goldflame'	400 to 500 mm ht.	Well formed bushy shrub, min. 5 major basal branches, even growth. Container stock, 3 gal. pot min.
Coniferous Shrubs				
18	**Hughes Juniper**	Juniperus horizontalis `Hughes`	400-500 mm dia.	Well formed bushy shrub with min. 5 major basal branches. Container stock. (3 gal pot min.)
20	**Calgary Carpet Juniper**	Juniperus sabina 'Calgary Carpet'	400-500 mm dia.	Well formed bushy shrub with min. 5 major basal branches. Container stock. (3 gal pot min.)
6	**Dwarf Mugo Pine**	Pinus mugo	400-500 mm dia.	Well formed bushy shrub with min. 5 major basal branches. Container stock. (3 gal pot min.)
Perennials				
9	**Virginia Creeper**	Parthenocissus quinquefolia	#2 Size Pot	1 yr. plants from division. No. 1 grade, well branched, with not less than 3 runners, 300 mm and up and vigorous, well developed root system. Stake.

Cibinel Architecture Ltd
560 ACADEMY ROAD WINNIPEG MB R3N 0E3
T. 204 989 8910
ARCHITECT

HTFC PLANNING & DESIGN
500-115 Bannatyne Avenue East Winnipeg, MB R3B 0R3
PHONE 204 944 9907 WEB htfc.ca
CONSULTANT

PLANTING PLAN NOTES

1.ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SPECIFIED.

2. ENSURE THE LOCATION OF ALL EXISTING SERVICES BOTH OLD AND RECENTLY INSTALLED ARE CLEARLY LOCATED ON SITE WITH THE CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION.

3. THE CONTRACT ADMINISTRATOR WILL BE RESPONSIBLE FOR REPAIRING ALL DAMAGE CAUSED TO SERVICES DURING CONSTRUCTION.

4. STAKE OUT AND CONFIRM THE LOCATION OF TREES WITH THE CONTRACT ADMINISTRATOR PRIOR TO INSTALLATION.

5. LAYOUT SHRUBS AND PERENNIALS IN BEDS AND OBTAIN CONTRACT ADMINISTRATOR APPROVAL PRIOR TO PLANT MATERIAL AND MULCH INSTALLATION.

NO.	DATE	REVISION / ISSUANCE
00	2023.02.03	ISSUED FOR CONSTRUCTION

Seal

the manitoba association of landscape architects
JAMES HUDSON
Member No. 186
2023-02-03

Project
WFPS STATION 9
1083 AUTUMNWOOD DRIVE

Sheet Title
PLANTING PLAN

Project No.
2150

Sheet
L-103

CIBINEL - Arch D - 24" X 36"