

1 A605 KITCHEN - ENLARGED PLAN
1:50



2 A605 INTERIOR ELEVATIONS - KITCHEN
1:50



3 A605 INTERIOR ELEVATIONS - KITCHEN
1:50



4 A605 INTERIOR ELEVATIONS - KITCHEN
1:50



5 A605 INTERIOR ELEVATIONS
KITCHEN
SCALE



6 A605 INTERIOR ELEVATIONS
KITCHEN
1:50



7 A605 INTERIOR ELEVATIONS - LOUNGE
1:50



7.1 A605 INTERIOR ELEVATIONS
FITNESS AREA WEST ELEVATION
1:50



8 A605 INTERIOR ELEVATIONS
FITNESS AREA NORTH ELEVATION
1:50



9 A605 INTERIOR ELEVATIONS
EAST WALL @ KITCHEN, DAYROOM, AND FITNESS ROOM
1:50

GENERAL NOTES

1. ALL KITCHEN MILLWORK TO BE STAINLESS STEEL UNLESS OTHERWISE NOTED
2. ALL OPEN SHELVING TO BE FINISHED ALL SIDES. PROVIDE STAINLESS STEEL PANEL AT BACK OF OPEN SHELVING - TYP.
3. STEEL STUD HEADER REQUIRED AT ALL INTERIOR CURTAINWALL. COORDINATE PERFORMANCE REQUIREMENTS WITH SPECIFICATION.
4. REFER TO ACCESSORY MOUNTING HEIGHT SCHEDULE SECTION 10 06 22
5. CONFIRM CLEAR OPENING DIMENSIONS WITH EQUIPMENT MANUFACTURER SPECIFICATIONS
6. REFER TO REFLECTED CEILING PLANS FOR ALIGNMENT AND POSITION OF LIGHT FIXTURES

KEYNOTES

1. REMOVABLE STAINLESS STEEL COVER ABOVE RANGE HOOD. EXTEND TO U/S OF THE CEILING.
2. LINE OF BULKHEAD ABOVE
3. INTEGRAL SINK
4. WATERFALL END
5. PULL OUT GARBAGE WITHIN DRAWER
6. PROVIDE BLOCKING BEHINDWALL MOUNTED TV. CONFIRM FINAL LOCATION OF TV, BLOCKING, POWER AND DATA RECEPTACLES WITH OWNER PRIOR TO CONSTRUCTION - SEE ELEC.
7. SPACE FOR STORING BAKING SHEETS UPRIGHT
8. UNDERCOUNTER MICROWAVE. PROVIDE STAINLESS STEEL TRIM PIECE AT FACE OF CABINET AS REQUIRED.
9. SUPPORT FOR STAINLESS STEEL FAUCET - BY MISC. METAL SUPPLIER
10. DRAWER
11. DINING TABLE
12. FLOOR BOX TO BE LOCATED BELOW. FINAL LOCATION TO BE CONFIRMED BY OWNER PRIOR TO CONSTRUCTION.
13. FINISH GABLE END OF COUNTER AND CABINET BASE AND UPPERS IN SAME MATERIAL AS EXPOSED FRONT FACE OF CABINET
14. CENTRE WALL ASSEMBLY ON GRIDLINE
15. WALL MOUNTED SHELF
16. WHITEBOARD
17. TACKBOARD
18. BOTTLE FILLING STATION. ALIGN U/S OF BOTTLE FILLING STATION WITH WINDOW SILL AS SHOWN.
19. RECEPTACLES MOUNTED BELOW COUNTER, PROVIDE STAINLESS COVER BACK TO CABINET. REFER TO DETAILS
20. WASTEBASKET
21. MAINTAIN CLEARANCE BETWEEN REFRIGERATOR AND FREEZER AS PER MANUFACTURERS REQUIREMENTS
22. FIXED STAINLESS STEEL PANEL TO CONCEAL SINK
23. COORDINATE WIDTH OF DRAWER C/W BRACING WITH WASTE CONTAINERS.
24. STEEL STUD BEAM AT TOP OF CURTAINWALL TO BE DESIGN BY STEEL STUD CONTRACTOR FOR CURTAINWALL HEAD SUPPORT.
25. ALIGN EDGE OF WALL WITH BEAM ABOVE AS SHOWN.
26. SPRINKLER. PROVIDE OPENING THROUGH WOOD BEAM TO ACCOMMODATE SPRINKLER LINE. ALLOW FOR ESCUTCHEON PLATE AT OPENING
27. FIRE EXTINGUISHER CABINET
28. PA SYSTEM PAGING STATION. REFER TO ELECTRICAL

Cibinel
Architecture Ltd
560 ACADEMY ROAD WINNIPEG MB R3N 0E3
T. 204 989 8910
ARCHITECT

NO.	DATE	REVISION / ISSUANCE
00	2023.02.03	ISSUED FOR CONSTRUCTION

Seal



Project
WFPS STATION 9
1083 AUTUMNWOOD DRIVE

Sheet Title
INTERIOR ELEVATIONS

Project No.
2150

Sheet
A605

CIBINEL - Arch D - 24" X 36"