

DEMOLITION NOTES:

- GENERAL CONTRACTOR TO REMOVE AND DISPOSE OF EXISTING WOOD DESK AND SHELVING
- ALL EXISTING SIGNAGE, COMPUTER AND IT EQUIPMENT TO BE REMOVED BY THE CITY OF WINNIPEG AND STORED ON SITE FOR RE-INSTALL.
- CONTRACTOR TO REMOVE AND RELOCATE ALL EXISTING POWER, DATA, PHONE LINES AND VOICE INTERCOM SYSTEM TO SUIT NEW DESK DESIGN. REFER TO ELECTRICAL DRAWINGS.
- CONTRACTOR TO REMOVE EXISTING CARPET TILE AND TRANSITION STRIPS AS NEEDED TO SUIT NEW DESK DESIGN. PREPARE FLOOR TO RECEIVE RUBBER FLOOR TILE.
- CONTRACTOR TO REMOVE AND REPLACE ANY DAMAGED RUBBER FLOOR TILE AND CARPET TILE WITH NEW TILE TO MATCH AFTER DESK IS REMOVED. REFER TO FLOORING SPECIFICATIONS.
- CONTRACTOR TO REMOVE AND DISPOSE EXISTING METAL EDGE PROFILE. WHERE RUBBER FLOOR TILE MEETS EXISTING FLOOR TILE IT MAY NOT BE POSSIBLE TO REMOVE EDGE PROFILE. ALTERNATE SOLUTIONS TO BE PROVIDED BY FLOORING CONTRACTOR. SITE CONFIRM.
- SHURE WIRELESS VOICE RECEIVER EQUIPMENT TO BE REMOVED BY CITY OF WINNIPEG RADIO SHOP DEPARTMENT FROM THE TEMPORARY DESK. TO BE STORED OFF SITE BY THE RADIO SHOP PRIOR TO DESK DEMOLITION.

NEW CONSTRUCTION DRAWING NOTES:

- NEW 24"x24" RUBBER FLOORING TILE REQUIRED UNDER NEW DESK. REFER TO FINISH SCHEDULE ON DRAWING A2 FOR RF-1. RUBBER FLOORING CONTIGUES UNDER COUNTERS. RUBBER FLOORING TO BE INSTALLED FIRST, WITH ALL MILLWORK INSTALLED AFTER.
- INSTALL NEW RUBBER FLOORING AROUND ANY RELOCATED FLOOR POWER PEDESTALS AND CONDUITS PIPES. REFER TO ELECTRICAL DRAWINGS AND SITE CONFIRM LOCATIONS.
- NEW RUBBER TRANSITION EDGE STRIPS TR-1 TO SUIT FLOORING TRANSITION BETWEEN CARPET TILE AND RUBBER FLOORING. CONTRACTOR TO CONFIRM PROFILE TO SUIT TRANSITION ON SITE.
- SOLID SURFACE COUNTERTOP FINISHES AND EDGES TO BE MATTE FINISH AND LOW POLISH. ALL CORNERS TO BE ROUNDED- NO SHARP EDGES PERMITTED. ALL EDGES TO BE MATTE FINISH AND POLISHED. REFER TO NEW 4TH FLOOR DESK FINISH.
- INSIDE OF ALL CABINETS, ALL SUPPORT GABLES AND BRACKETS TO RECEIVE PLAM-1 FINISH.
- STREET NAMES INDICATED ON FLOOR PLAN 2/A1 ARE FOR REFERENCE PURPOSES ONLY.
- ANY PENETRATIONS THROUGH CONCRETE FLOOR VIA PARKADE LEVEL FOR ANY ELECTRICAL CONDUIT WORK MUST BE COORDINATED WITH CITY OF WINNIPEG ASBESTOS AND BUILDING SERVICES TEAM PRIOR TO CORING.
- ANY PENETRATIONS THROUGH CONCRETE FLOOR VIA PARKADE LEVEL FOR ANY NEW ELECTRICAL CONDUIT OR REMOVED ELECTRICAL. NEW FIRESTOPPING IS REQUIRED TO MEET CURRENT BUILDING CODE. REFER TO ELECTRICAL SPECIFICATIONS ON DWG E02.

EQUIPMENT LIST:



- SINGLE MONITOR ARM: ESI: MODEL: EVOLVE 1-M-BLK; BLACK FINISH GROMMET INSTALL METHOD. TO BE SUPPLIED AND INSTALLED BY CITY OF WINNIPEG. SITE CONFIRM LOCATION WITH LIBRARY STAFF PRIOR TO INSTALL.
- KEYBOARD TRAY TYPE 1: TO BE CONFIRMED TO BE SUPPLIED AND INSTALLED BY CITY OF WINNIPEG
- CORNER KEYBOARD TRAY TYPE 2: TO BE CONFIRMED TO BE SUPPLIED AND INSTALLED BY CITY OF WINNIPEG
- CABLE/ WIRE MANAGEMENT- HUMANSCALE NEATLINKS-24" LONG COLOR: BLACK; MOUNTED UNDERNEATH THE DESK. TO BE SUPPLIED AND INSTALLED BY CITY OF WINNIPEG.
- EXISTING PA SYSTEM MICROPHONE-ON SLIDE OUT SHELF. EXISTING SHURE WIRELESS RECEIVER TO BE RELOCATED BY CITY OF WINNIPEG RADIO SHOP FROM TEMPORARY DESK. POWER REQUIRED. REFER TO ELECTRICAL DRAWINGS.
- EXISTING TELEPHONE- ON SLIDE OUT SHELF. TELEPHONE LINES TO BE RELOCATED BY CONTRACTOR. REFER TO ELECTRICAL DRAWINGS.
- CABLE/ WIRE MANAGEMENT- HUMANSCALE NEATLINKS-18" LONG COLOR: BLACK; MOUNTED UNDERNEATH THE DESK. TO BE SUPPLIED AND INSTALLED BY CITY OF WINNIPEG. SITE CONFIRM.
- GROMMET COVER- 2" Ø ROUND BLACK. SUPPLIED AND INSTALLED BY MILLWORK CONTRACTOR. CONFIRM WITH LIBRARIES QUANTITY REQUIRED AT EACH STATION. CONFIRM EXACT LOCATION WITH IT DEPARTMENT.
- DESK CHAIRS- SUPPLIED BY CITY OF WINNIPEG. NOT IN CONTRACT.
- ALL COMPUTER EQUIPMENT IS EXISTING AND TO BE RELOCATED BY CITY OF WINNIPEG CMS IT DEPARTMENT.

GENERAL NOTES

- THESE DRAWINGS SHALL NOT BE SCALED.
- THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY ONESELF ALL DIMENSIONS, DATUM AND DETAILED INFORMATION SHOWN ARE CORRECT.
- THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.
- ALL OPENINGS THROUGH FIRE ASSEMBLIES ARE TO BE FIRE STOPPED AND SEALED WITH ULC APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE A SMOKE-TIGHT BARRIER.
- ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS & APPLICABLE CODES.
- THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE REMOVAL OF ALL ITEMS FORMING THE PART OF THE RENOVATION WORK.
- WHERE NEW FLOORING AND BASE IS TO BE INSTALLED IN EXISTING AREAS (REFER TO FLOOR PLAN AND ROOM SCHEDULE) THE EXISTING FLOORING SURFACE AND BASE MUST BE REMOVED, UNLESS OTHERWISE NOTED. ALL FLOOR SURFACES SHALL BE PREPARED IN ACCORDANCE TO MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF NEW FLOOR.
- WHERE PAINTING OF EXISTING WALLS IS INDICATED ON THE ROOM SCHEDULE, THESE WALLS MUST BE CLEANED OF ANY EXISTING WALL COVERING, PATCHED & PREPARED TO ACCEPT NEW MATERIAL, UNLESS OTHERWISE NOTED.

ASBESTOS

ASBESTOS MAYBE PRESENT BEHIND WALLS, CEILING SPACES & FLOORS. IF ASBESTOS OR ANY HAZARDOUS MATERIAL IS FOUND, STOP WORK IMMEDIATELY AND CONTACT CITY OF WINNIPEG CENTRAL CONTROLS @ 204 986-2351.



No.	REVISION/DESCRIPTION	BY	DATE
0	ISSUED FOR CONSTRUCTION	KJN	01 2024

TENDER # 1080-2023

DRAWN	CHECKED	DESIGNED	APPROVED
KJN			

DATE: 2024.01.10 USER APPROVAL

THE CITY OF WINNIPEG  
ASSETS & PROJECT MANAGEMENT  
DEPARTMENT  
MUNICIPAL ACCOMMODATIONS DIVISION  
3-65 GARRY STREET, R3C 4K4

PROJECT  
MILLENNIUM LIBRARY  
NEW READER SERVICES DESK

251 DONALD STREET

SHEET TITLE  
NEW CONSTRUCTION PLAN  
DEMOLITION PLAN

SCALE	PROJECT No:	SHEET No:
AS SHOWN	2023-057	A1