A1 SIZE – 594mm x 841mm

GENERAL NOTES:

1. THE INFORMATION ON THIS DRAWING IS BASED ON INFORMATION PROVIDED ON EXISTING DRAWINGS AND MAY NOT HAVE BEEN VERIFIED.
2. THE EXTENT OF THE DESIGN INCLUDES THE DEMOLITION OF THE EQUIPMENT AS SHOWN.
3. PROVIDE DEMOLITION OF EXISTING CABLING, AND ASSOCIATED CONDUIT OF ALL EQUIPMENT BEING REMOVED.

PRE–DEMOLITION NOTES:

1. COORDINATE WITH MANITOBA HYDRO AND THE CITY OF WINNIPEG EXAMINATION DEPARTMENT TO ARRANGE FOR A SERVICE UPGRADE.
2. NO TEMPORARY POWER FROM MANITOBA HYDRO IS REQUIRED FOR THE FLOOD PUMPS WHILE DEMOLITION/CONSTRUCTION IS UNDERWAY. A TEMPORARY GENERATOR WILL NEED TO BE PROVIDED FOR LOADS ASSOCIATED WITH HEATING, LIGHTING, ETC DURING DEMOLITION AND NEW CONSTRUCTION. OTHERWISE THE CONTRACTOR WILL NEED TO PROVIDE A TEMPORARY SERVICE AND CONSULT WITH MANITOBA HYDRO. THE STATION CONTAINS DOMESTIC WATER PIPING. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THE DOMESTIC WATER PIPING DOES NOT FREEZE DURING CONSTRUCTION WORK. THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGES RESULTING FROM DOMESTIC WATER PIPING FREEZING.

SPECIFIC NOTES:

- (A) DEMOLISH EXISTING PRESSURE AND FLOW SWITCHES AS WELL AS ALL UPSTREAM ASSOCIATED CABLING AND CONDUIT.
- (B) DEMOLISH EXISTING SUMP PUMP AS WELL AS ALL ASSOCIATED CABLING AND CONDUIT.
- (C) DEMOLISH EXISTING UNIT HEATER AS WELL AS ANY ASSOCIATED CABLING AND CONDUIT.
- (D) DEMOLISH EXISTING RECEPTACLES, LIGHTS AND SWITCHES AS WELL AS ALL ASSOCIATED UPSTREAM CABLING AND CONDUIT.



LOWER LEVEL PLAN EL. 224.516 m

SCALE: 1 : 30

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
SNC-Lavalin Inc.
No. 4489

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

1m 0.5m 0 0.5m 1m 1.5m

1 : 30

NO.	REVISIONS	DATE	DESIGN	CHECK
00	ISSUED FOR CONSTRUCTION, TENDER 167–2023	2023/03/02	MS	BC

SNC·LAVALIN
SNC–LAVALIN INC.
148 Nature Park Way
Winnipeg, MB, Canada R3P 0X7
204–786–8080

DESIGNED BY: N. ESCHUK	CHECKED BY: B. CLEVEN
DRAWN BY: B. WILKS	APPROVED BY: B. CLEVEN
SCALE: 1:30	ISSUED FOR CONSTRUCTION BY: K. ZUREK
DATE: 2022/06/23	DATE: 2023/03/02
CONSULTANT NO.:	

ENGINEER'S SEAL
PROVINCE OF MANITOBA
M. SARIC
Member
46571
REGISTERED PROFESSIONAL ENGINEER
2023-03-02

REV. 00

Winnipeg
THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT

BANNATYNE FLOOD PUMPING STATION
2023 UPGRADES
ELECTRICAL PLAN LAYOUT
DRY WELL AREA
DEMOLITION

CITY DRAWING NUMBER	SHEET	REV.	SIZE
1–0118F–E0004	001	00	A1

1–0118F–E0004–001_Rev00.dwg

LAST SAVE: 2023/03/02 – 3:52pm
PATH: \\Winpdc1\proj$\691232\4ENG\47ELE\DD – General DWG\1–0118F–E0004–001_Rev00.dwg