



-08 -08

FOR DWG

NORTH BOUND

ROBLIN BOULEVARD

SOUTH BOUND

THE STATE OF THE S CRESCENT

1. ALL WORK AND MATERIALS TO BE IN ACCORDANCE WITH THE LATEST REVISION OF THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS. C. CONTRACTOR TO CONFIRM THE LOCATION OF ALL UTILITIES/SERVICES IN THE FIELD PRIOR TO CONSTRUCTION.

3. RENEW CURB, SPLASH STRIP, BULLNOSE, AND SIDEWALK AS IDENTIFIED BY CONTRACT ADMINISTRATOR.

4. ALL PRIVATE WALKWAYS TO BE ADJUSTED TO NEW SIDEWALK OR TOP OF CURB ELEVATION, AS REQUIRED. ADJUST MH FRAMES, CB RIMS, CURB INLETS, AND VALVES TO NEW GRADES, AS REQUIRED.

MODIFIED BARRIER CURB TO BE CONSTRUCTED AT ALL INTERSECTION RADII AND BACK LANE RADII.

LAMP STANDARDS, HYDRO POLES, AND ANCHORS THAT REQUIRE TEMPORARY SUPPORT, REMOVAL OR

REPLACEMENT, TO BE DONE SO AT THE EXPENSE OF THE CONTRACTOR AS NECESSARY.

CONTRACTORS TO TAKE PRECAUTIONARY STEPS TO PROTECT EXISTING TREES WITHIN THE LIMITS OF CONSTRUCTION FROM DAMAGE FROM CONSTRUCTION ACTIVITIES AS OUTLINED IN THE SPECIFICATIONS.

9. ALL BOULEVARDS TO BE SODDED UNLESS OTHERWISE NOTED.

10. FULL AND PARTIAL DEPTH JOINT REPAIRS, AND SLAB RENEWALS TO BE FINALIZED IN THE FIELD PRIOR TO CONSTRUCTION. THE REPAIRS IDENTIFIED ON THIS DRAWING ARE FOR TENDER PURPOSE ONLY. . INSTALL PAVEMENT REPAIR FABRIC AS DIRECTED BY THE CONTRACT ADMINISTRATOR.

٠,								
23	_III	TRANSIT STOP	EDGE OF SIDEWALK					
2023	HP ●	HYDRO POLE		/	FENCE			
1	0	MANHOLE			PROPERTY LINE			
00-		CATCH BASIN			EDGE OF CONCRETE & ASPHALT			
\2023\231-02074-	Δ	CURB INLET			SIDEWALK RENEWAL			
		HYDRANT			DIAMOND GRINDING LIMITS			
	\otimes	VALVE			FULL DEPTH REPAIRS			
	3	CURB STOP			ASPHALT RENEWAL	***************************************		
		ANCHOR			CONCRETE PRESERVATION			
	#111	CIVIC ADDRESS			BOULEVARD GRADING	(//////////////////////////////////////		
<u>е</u> .	EXISTING	LEGEND-PLAN	PROPOSED	EXISTING	LEGEND-PLAN	PROPOSED		

WHOLE NUMBERS INDICATE MILLIMETRES DECIMALIZED NUMBERS INDICATE METRES

ENGINEERS
GEOSCIENTISTS
MANITOBA Certificate of Authorization WSP Canada Inc. No. 5750

METRIC

_	PRELIMINARY					
	NOT FOR CONSTRUCTION					

Winnipeg			

THE CITY OF WINNIPEG PUBLIC WORKS DEPARTMENT ENGINEERING SERVICES DIVISION

2023 STREET MAINTENANCE PRESERVATION PROGRAM ROBLIN BOULEVARD - SOUTH BOUND ASPHALT MILL AND FILL STA. 6+80 TO STA. 13+30

ITY DRAWING NUMBER						
N/A						
HEET		OF				
	07	16				
TENDER NO. 187-2023						

G.B ELE				11	SD	W	WSP Canada Inc. 1600 Buffalo Place /innipeg, MB R3T 6B8 t. 204.477.6650	ENGINEER'S SEAL
H G							f. 204.474.2864 www.wsp.com	3 / /
F				DESIGNED BY	M.S.	CHECKED BY	V.M.	REGION TO PROFI
Е								1 1
D				DRAWN BY	S.B.	APPROVED BY	J.M.	PROFI
С								MARAGA
В	ISSUED FOR TENDER	04/06/2023	J.M.	HOR. SCALE	HOR. SCALE 1:500		RELEASED FOR	
А	PRELIMINARY DESIGN REVIEW	04/04/2023	J.M.	VERTICAL	N/A	CONSTRUCTION		CONSULTANT ACAD D
NO.	REVISIONS	DATE	BY	DATE	03/02/2023	DATE		231-0207

J.S.F. IAGNE MEMBER 31236

231-02074-00-07