

 $\longrightarrow$ 

**EXISTING** 

ANCHOR

CIVIC ADDRESS

LEGEND-PLAN

ALL WORK AND MATERIALS TO BE IN ACCORDANCE WITH THE LATEST REVISION OF THE CITY OF WINNIPEG

STANDARD CONSTRUCTION SPECIFICATIONS. CONTRACTOR TO CONFIRM THE LOCATION OF ALL UTILITIES/SERVICES IN THE FIELD PRIOR TO CONSTRUCTION. RENEW CURB, SPLASH STRIP, BULLNOSE, AND SIDEWALK AS IDENTIFIED BY CONTRACT ADMINISTRATOR.

ALL PRIVATE WALKWAYS TO BE ADJUSTED TO NEW SIDEWALK OR TOP OF CURB ELEVATION, AS REQUIRED. ADJUST MH FRAMES, CB RIMS, CURB INLETS, AND VALVES TO NEW GRADES, AS REQUIRED. MODIFIED BARRIER CURB TO BE CONSTRUCTED AT ALL INTERSECTION RADII AND BACK LANE RADII. LAMP STANDARDS, HYDRO POLES, AND ANCHORS THAT REQUIRE TEMPORARY SUPPORT, REMOVAL OR REPLACEMENT, TO BE DONE SO AT THE EXPENSE OF THE CONTRACTOR AS NECESSARY. CONTRACTORS TO TAKE PRECAUTIONARY STEPS TO PROTECT EXISTING TREES WITHIN THE LIMITS OF CONSTRUCTION FROM DAMAGE FROM CONSTRUCTION ACTIVITIES AS OUTLINED IN THE SPECIFICATIONS. ALL BOULEVARDS TO BE SODDED UNLESS OTHERWISE NOTED.

10. FULL AND PARTIAL DEPTH JOINT REPAIRS, AND SLAB RENEWALS TO BE FINALIZED IN THE FIELD PRIOR TO CONSTRUCTION. THE REPAIRS IDENTIFIED ON THIS DRAWING ARE FOR TENDER PURPOSE ONLY. 1. ALL JOINTS AND CRACKS TO BE SEALED AFTER DIAMOND GRINDING IS COMPLETED.

TRANSIT STOP EDGE OF SIDEWALK HYDRO POLE **FENCE** ------MANHOLE PROPERTY LINE CATCH BASIN EDGE OF CONCRETE & ASPHALT CURB INLET  $\triangle$ SIDEWALK RENEWAL HYDRANT DIAMOND GRINDING LIMITS -ф-

**EXISTING** 

CONCRETE PRESERVATION

BOULEVARD GRADING

LEGEND-PLAN

PROPOSED

WSP Canada Inc. ENGINEER'S SEAL G.B.M. N/A 1600 Buffalo Place 1151) ELEV. -Winnipeg, MB R3T 6B8 t. 204.477.6650 f. 204.474.2864 www.wsp.com CHECKED APPROVED S.B. J.M. 1:500 RELEASED FOR B ISSUED FOR TENDER 04/06/2023 J.M. CONSULTANT ACAD DWG. NO. N/A A PRELIMINARY DESIGN REVIEW 04/04/2023 J.M. 231-02074-00-16 NO. REVISIONS DATE BY 03/02/2023 DATE

J.S.F. MAGNE MEMBER

ENGINEERING SERVICES DIVISION

**PRELIMINARY** 

NOT FOR CONSTRUCTION

2023 STREET MAINTENANCE PRESERVATION PROGRAM STRADBROOK AVENUE - WEST BOUND CONCRETE PRESERVATION AND DIAMOND GRINDING HARKNESS AVE TO MAIN ST

THE CITY OF WINNIPEG

PUBLIC WORKS DEPARTMENT

N/A 16 TENDER NO. 187-2023

**METRIC** 

WHOLE NUMBERS INDICATE MILLIMETRES

DECIMALIZED NUMBERS INDICATE METRES

ENGINEERS GEOSCIENTISTS

Certificate of Authorization

WSP Canada Inc.

No. 5750

MANITOBA

12. DIAMOND GRINDING LIMITS TO BE FINALIZED IN THE FIELD PRIOR TO CONSTRUCTION, AS DIRECTED BY THE CONTRACT ADMINISTRATOR. FULL DEPTH REPAIRS VALVE CURB STOP ASPHALT RENEWAL

PROPOSED