TESTHOLE 1

REFERENCE NOTES:

A. PAVEMENT DIMENSIONS ARE TO BACK OF CURB
B. BASELINE IS CENTRE LINE ROADWAY
C. PROPERTY LINES OBTAINED FROM CITY OF WINNIPEG L.B.I.S., AND NO SCALE FACTOR WAS APPLIED
D. REFER TO AECOM FIELD BOOK NO. 5133

CONSTRUCTION NOTES:

1. MILL EXISTING ASPHALT PAVEMENT AND PLACE NEW ASPHALT PAVEMENT OVERLAY TYPE 1A (50-100mm AVG. THICKNESS)
2. REMOVE EXISTING CONCRETE PAVEMENT AND INSTALL NEW 150mm REINFORCED CONCRETE PAVEMENT
3. ADJUST EXISTING CATCH BASIN / MANHOLE TO GRADE
4. INSTALL CAST IRON RISER RING
5. REMOVE EXISTING FRAME AND COVER AND INSTALL NEW STANDARD FRAME AND SOLID COVER
6. ADJUST EXISTING WATER VALVE TO GRADE
7. REMOVE EXISTING BARRIER CURB
8. INSTALL NEW CONCRETE MODIFIED BARRIER CURB (150mm REVEAL HT. DOWELLED)
9. INSTALL NEW STANDARD FRAME WITH GRATED COVER c/w CATCH PIT AND CONNECT TO EXISTING CATCH BASIN
10. REMOVE EXISTING CATCH PIT
11. MH60011413 - INSTALL NEW MANHOLE
12. MH60011427 - REPLACE RISER TO 0.8m

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
AECOM Canada Ltd.
No. 4671 Date: 04/11/2023

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

EXISTING	LEGEND - PLAN	PROPOSED	EXISTING	LEGEND - PLAN	PROPOSED	EXISTING	LEGEND - PROFILE	PROPOSED
150 mm W.M.	WATERMAIN	150 mm W.M.		HYDRO			℄ PROFILE	
	HYDRANT			M.T.S.			SOUTH/INNER EDGE OF CONCRETE	
	VALVE			CONCRETE			NORTH/OUTER EDGE OF CONCRETE	
300mm L.D.S.	LAND DRAINAGE SEWER	300mm L.D.S.		ASPHALT				
250mm W.W.S.	WASTEWATER SEWER	250mm W.W.S.		PROPERTY LINE			SOUTH/INNER PROPERTY LINE	
	MANHOLE			SURVEY BAR				
	CATCH BASIN		235.750	ELEVATION	235.750		NORTH/OUTER PROPERTY LINE	
	CATCH PIT		500ø	TREE				
	JUNCTIONS			SIDEWALK RAMP				
	CULVERT			CONCRETE SIDEWALK				
	GAS			FENCE				

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE — DATE

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE, BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M. NORTHING/EASTING EST. FROM ZONE: 53 #31 - N.W. Cor. Baltimore Rd. & Hay St., Brass plug in 14.8 m Conc. pile, 2.4 m E. of W.L. Hay St., 2.4 m S. of N.L. Baltimore Rd.
ELEV. EL: EST. FROM ZONE 64: #44 84R587 = 232.097

NO.	REVISIONS	DATE	BY
0	ISSUED FOR TENDER	04/11/23	BC
A	ISSUED FOR REVIEW	03/20/23	BC

AECOM

DESIGNED BY	JT	CHECKED BY	BC
DRAWN BY	JT	APPROVED BY	TF
HOR. SCALE:	1:250	RELEASED FOR CONSTRUCTION BY:	
VERTICAL:	1:10		
DATE	02/14/2023	DATE	

ENGINEER'S SEAL
PROVINCE OF MANITOBA
T.L. FINDLAY
Member
23820
2023-04-05
REGISTERED PROFESSIONAL ENGINEER

CONSULTANT DRAWING NO.
CT-35

Winnipeg
THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

2023 LOCAL STREET
RENEWAL PROGRAM

CITY DRAWING NUMBER
SHEET 35 OF 38

WILDWOOD G PARK
AC RESURFACE
STATION 0+230 TO SOUTH DRIVE