TESTHOLE 4

TYPICAL DE LEGLISE AVENUE CROSS SECTION

Scale NTS

REFERENCE NOTES:

A. PAVEMENT DIMENSIONS ARE TO BACK OF CURB
B. BASELINE IS CENTRE LINE ROADWAY
C. PROPERTY LINES OBTAINED FROM CITY OF WINNIPEG L.B.I.S., AND NO SCALE FACTOR WAS APPLIED
D. REFER TO AECOM FIELD BOOK NO. 5131

CONSTRUCTION NOTES:

1. REMOVE EXISTING ASPHALT PAVEMENT AND PLACE NEW ASPHALT PAVEMENT OVERLAY (50mm TYPE 1A & 75mm TPYE III)
2. REMOVE EXISTING PAVEMENT AND CONSTRUCT NEW 150mm REINFORCED CONCRETE PAVEMENT
3. RENEW EXISTING 100mm CONCRETE SIDEWALK
4. CONSTRUCT NEW CONCRETE BARRIER CURB AND GUTTER (600mm WIDTH, 150mm HT.)
5. CONSTRUCT NEW CONCRETE MODIFIED BARRIER CURB AND GUTTER (600mm WIDTH, 180mm HT.)
6. CONSTRUCT NEW CONCRETE LIP CURB AND GUTTER (600mm WIDTH, 40mm HT.)
7. CONSTRUCT NEW CONCRETE CURB RAMP AND GUTTER (600mm WIDTH, 10-12mm HT.)
8. INSTALL NEW 100mm CONCRETE SIDEWALK
9. REMOVE EXISTING ASPHALT PAVEMENT AND PLACE NEW 50-100mm ASPHALT PAVEMENT TYPE 1A
10. REGRADE EXISTING GRANULAR MATERIAL AND ADD ADDITIONAL GRANULAR MATERIAL IF REQUIRED
11. REGRADE EXISTING INTERLOCKING PAVING STONES
12. ADJUST EXISTING WATER VALVE TO GRADE
13. ADJUST EXISTING MANHOLE/ CATCH BASIN TO GRADE
14. INSULATE EXISTING WATER SERVICES
15. REMOVE EXISTING LIGHT STANDARD AND INSTALL NEW STREET-LIGHTING IN ACCORDANCE WITH MANITOBA HYDRO DRAWINGS
16. INSTALL NEW DETECTABLE WARNING SURFACE TILE

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
AECOM Canada Ltd.
No. 4671 Date: 04/11/2023

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

EXISTING	LEGEND - PLAN	PROPOSED	EXISTING	LEGEND - PLAN	PROPOSED	EXISTING	LEGEND - PROFILE	PROPOSED
150 mm W.M.	WATERMAIN	150 mm W.M.		HYDRO			℄ PROFILE	
	HYDRANT			M.T.S.			SOUTH GUTTER	
	VALVE			CONCRETE			NORTH GUTTER	
300mm L.D.S.	LAND DRAINAGE SEWER	300mm L.D.S.		ASPHALT			S PROPERTY LINE	
250mm W.W.S.	WASTEWATER SEWER	250mm W.W.S.		PROPERTY LINE			N PROPERTY LINE	
	MANHOLE			SURVEY BAR				
	CATCH BASIN		235.750	ELEVATION	235.750			
	CATCH PIT		500ø	TREE				
	JUNCTIONS			SIDEWALK RAMP				
	CULVERT			CONCRETE SIDEWALK				
	GAS			FENCE				

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE — DATE

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE. BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M. ELEV. #11 - W. side Rue Landry, Tblt. in E. Conc. foundation of No. 15 Rue Landry, 3.3m S. & 0.5m below stucco from N.E. Cor. of dwelling EL: 233.529

NO.	REVISIONS	DATE	BY
0	ISSUED FOR TENDER	04/11/23	BC
A	ISSUED FOR REVIEW	03/20/23	BC

AECOM

DESIGNED BY	JT	CHECKED BY	BC
DRAWN BY	JT	APPROVED BY	TF
HOR. SCALE:	1:250	RELEASED FOR CONSTRUCTION BY:	
VERTICAL:	1:10		
DATE	02/28/2023	DATE	

ENGINEER'S SEAL
PROVINCE OF MANITOBA
FINDLAY
Member
23820
2023-04-05
REGISTERED PROFESSIONAL ENGINEER

CONSULTANT DRAWING NO.
CT-16

Winnipeg
THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

2023 LOCAL STREET
RENEWAL PROGRAM

CITY DRAWING NUMBER

SHEET 16 OF 38

DE LEGLISE - RUE CAMPEAU TO RUE ST.PIERRE
ASPHALT PAVEMENT RECONSTRUCTION
RUE CAMPEAU TO STATION 0+210