NOTE:
SLOPE PROTECTION AND UPPER AND LOWER TIE IN DETAILS ONLY PRESENT UNDER THE BRIDGE, STA. 1+75 TO 1+95

PROPOSED PATHWAY UNDER BRIDGE SECTION

STA. 1+75 TO 1+95

EXISTING SECTION UNDER BRIDGE

STA. 1+75 TO 1+95
SCALE 1:30

TYPICAL EXISTING PATH SECTION

STA. 0+90 TO 1+75 AND STA. 1+95 TO 2+35
SCALE 1:30

PROPOSED PATHWAY LOWEST WALL SECTION

STA. 0+90 TO 1+23 AND STA. 2+27 TO 2+35
SCALE 1:30

CONSTRUCTION JOINT DETAIL

BOTTOM OF RETAINING WALL SHOWN
SCALE 1:20

PROPOSED PATHWAY HIGHEST WALL SECTION

STA. 1+23 TO 1+75 AND STA. 1+95 TO 2+27 (DRAIN PIPE SHOWN AT STA. 1+40)
SCALE 1:30

NOTE

1. 50 mm DEEP SAWCUT INTO FACE AND TOP OF WALL TO MATCH 3.0 m TRANSVERSE SIDEWALK CUT.
2. 50 mm DEEP LONGITUDINAL SAWCUT ALONG CENTRELINE OF PATH.

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

NOTE:
These design documents are prepared solely for the use by the party with whom the design professional has entered into a contract and there are no representations of any kind made by the design professional to any party with whom the design professional has not entered into a contract.

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
WSP Canada Inc.
No. 5750

LOCATIONS APPROVED UNDERGROUND STRUCTURES
SIGNED BY: _____ SUPV U/G STRUCTURES _____ DATE
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT CONFIRMATION OF EXISTANCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING

No.	REVISIONS	DATE	BY
2	GENERAL REVISIONS	24.04.11	EH
1	ISSUED FOR TENDER	24.03.22	EH
0	90% SUBMISSION	23.05.05	EH

WSP Canada Group Limited
1600 Buffalo Place
Winnipeg MB R3T 6B8
T+ 1 204-477-6650
F+ 1 204-474-2864
www.wsp.com

DESIGNED BY	DV	CHECKED BY	EH
DRAWN BY	KD	APPROVED BY	SS
HOR. SCALE	AS NOTED	RELEASED FOR CONSTRUCTION	
VERTICAL	AS NOTED		
DATE	24.04.11	DATE	24.04.11

ENGINEER'S SEAL
PROVINCE OF MANITOBA
2024-04-12
E. HO
Member
22317
REGISTERED PROFESSIONAL ENGINEER

CONSULTANT PROJECT No.
20M-01243-00

Winnipeg
THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

KEEWATIN STREET PATHWAY
GALLAGHER AVE W TO BURROWS AVE

NEW PATHWAY
ACTIVE TRANSPORTATION PATH
CONCRETE DETAILS (SHEET 1 OF 2)

CITY DRAWING NUMBER P-3571-19
SHEET 19 OF 20
TENDER NO. 376-2023

A1 SIZE (594 mm x 841 mm)

Plotted: April 11, 2024 at 3:25:36 PM | Last saved by: CAK0065668
File: P:\2020\20M-01243-00 - 2020-2021 Keewatin_King Edward_Pembina_Lag\10 Drawings\99 Structures\03-Working Drawings\20M-01243-00 DD Keewatin Underpass AT Path - concrete.dwg