FILE NAME: 2019078MV0.dwg

DATE: 2022.12.01

SHEET TITLE: PARTIAL MAIN FLOOR PLAN - PLUMBING DEMOLITION AND RENOVATION

PROJECT No: 2019-078

ADDRESS: 510 KING ST.

PLUMBING DEMOLITION NOTES:

1. REMOVE EXISTING SINK AND CAP OFF PLUMBING LINES ON THE WALL, ON THE FLOOR OR IN THE CEILING. CONTRACTOR TO CONFIRM ON SITE.
2. REMOVE EXISTING 3 COMPARTMENT KITCHEN SINK. DISCONNECT PLUMBING LINES. CLEAN AND RE-INSTALL AS PER RENOVATION DRAWING.
3. EXISTING DOMESTIC WATER LINES IN THE CEILING SPACE TO REMAIN.
4. EXISTING PLUMBING VENT LINE IN THE CEILING SPACE TO REMAIN.
5. EXISTING UNDERSLAB SANITARY LINE TO REMAIN.

PLUMBING RENOVATION NOTES:

1. NEW DISHWASHER. PROVIDE HOT WATER TO NEW DISHWASHER C/W ISOLATION VALVE AND CONNECT THE DISHWASHER DRAIN TO NEW DRAIN TRAP AFTER GREASE INTERCEPTOR GI-1.
2. NEW 3 COMPARTMENT KITCHEN SINK LOCATION. RECONNECT THE NEW SINK TO THE EXISTING PLUMBING LINES, INCLUDING HOT WATER LINE, DRAIN AND VENT LINE.
3. NEW GREASE INTERCEPTOR (GI-1). (PROVIDED BY MECHANICAL CONTRACTOR) LOCATE UNDERNEATH THE COUNTER SINK.COORDINATE WITH ARCHITECTURAL FOR EXACT PLACEMENT.
4. NEW PLUMBING VENT LINE. CONNECT TO EXISTING VENT LINE.
5. NEW HAND WASH SINK (SK-2).
6. NEW ½" HOT WATER AND ½" COLD WATER LINES TO NEW HAND WASH SINK (SK-2).
7. NEW 1½" SANITARY LINE FROM SK-2 TO CONNECT TO EXISTING SANITARY LINE.

NORTH — 1 / M2 PARTIAL MAIN FLOOR PLAN - PLUMBING DEMOLITION
SCALE: 3/8" = 1'-0"

NORTH — 2 / M2 PARTIAL MAIN FLOOR PLAN - PLUMBING RENOVATION
SCALE: 3/8" = 1'-0"

NORTH — KEY PLAN
SCALE: NTS

NOTES:

THESE DRAWINGS SHALL NOT BE SCALED.

THIS DRAWING IS DIAGRAMMATIC ONLY. CONTRACTOR TO COORDINATE EXACT LOCATIONS OF AND ROUTING ON SITE WITH ALL NEW AND EXISTING SYSTEM.

THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY ONESELF ALL DIMENSIONS, DATUM, AND DETAILED INFORMATION SHOWN ARE CORRECT.

THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.

ALL OPENINGS THROUGH FIRE ASSEMBLIES ARE TO BE FIRE STOPPED AND SEALED WITH ULC APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE A SMOKE-TIGHT BARRIER.

ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS & APPLICABLE CODES.

NEW DUCT SHALL BE CONSTRUCTED AS RECOMMENDED BY SMACNA.

THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE REMOVAL OF ALL ITEMS FORMING THE PART OF THE RENOVATION WORK.

PLUMBING INSTALLATION SHALL CONFORM TO NATIONAL PLUMBING CODE OF CANADA.

THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING RISERS, SWING JOINTS AND DEEP CUP ESCUTCHEONS AS REQUIRED.

ELECTRICAL WIRING SHALL BE PERFORMED BY A QUALIFIED ELECTRICAL SUBTRADE.

PROVIDE MILCOR ACCESS DOORS IN DRYWALL CEILINGS AND WALLS FOR ACCESS TO MECHANICAL EQUIPMENT. MINIMUM SIZE 24" X 18".

THE MECHANICAL CONTRACTOR SHALL ARRANGE WITH MANITOBA HYDRO GAS DIVISION FOR REVISION TO GAS SERVICE INCLUDING PRESSURE REGULATOR. THE COST OF THIS SERVICE SHALL BE INCLUDED IN THE COST OF THIS CONTRACT.

No.	REVISION/DESCRIPTION	BY	DATE
2	ISSUED FOR CONSTRUCTION	DRM	02.02 2024
1	ISSUED FOR CONSTRUCTION	PAS	JULY 04 2023
0	ISSUED FOR PRICING	EAG	FEB 07 2023

SEAL

PROVINCE OF MANITOBA — REGISTERED PROFESSIONAL ENGINEER — 2024-02-02 — X. WU — Member — 20042

DRAWN	DRM	CHECKED		DESIGNED	XYW	APPROVED	
DATE	2022.12.01	USER APPROVAL					

Winnipeg

THE CITY OF WINNIPEG
PLANNING, PROPERTY AND DEVELOPMENT DEPARTMENT
MUNICIPAL ACCOMMODATIONS DIVISION
3–65 GARRY STREET, R3C 4K4

PROJECT

TURTLE ISLAND RECREATION CENTRE
KITCHEN RENOVATION
-
510 KING ST.

SHEET TITLE

PARTIAL MAIN FLOOR PLAN
PLUMBING DEMOLITION AND RENOVATION

SCALE	PROJECT No:	SHEET No:
AS SHOWN	2019-078	M2

DRAWING SHEET SIZE: A1 (841mm x 594mm) PLOT 1:1