NORTH 1 A2.2 REFLECTED CEILING PLAN - KITCHEN & PANTRY
SCALE: 3/8"=1'-0"

REFLECTED CEILING PLAN SYMBOL LEGEND

- NEW MECHANICAL DIFFUSER - WHITE FINISH REFER TO MECHANICAL DRAWINGS
- EXISTING FLUORESCENT CEILING LIGHT TO REMAIN.
- R — EXISTING FLUORESCENT CEILING LIGHT RELOCATED REFER TO ELECTRICAL DRAWINGS FOR DETAIL.
- EXIT — EXISTING EXIT LIGHTS.
- GWB # - # — FINISHED CEILING HEIGHT AND CEILING TYPE
- RETURN AIR VENT. REFER TO MECHANICAL DRAWINGS.
- RETURN AIR VENT. REFER TO MECHANICAL DRAWINGS.
- FT — EXISTING HEAT DETECTOR
- NEW SECURITY MIRROR

DRAWING NOTES

1. EXISTING CEILING HEIGHT SHOWN IS APPROXIMATE. SITE CONFIRM AND ADVISE DESIGNER.
2. PATCH AND PAINT CEILING IN KITCHEN & PANTRY, INCLUDING EXIST. ACCESS HATCH(ES). SEE FINISH SPECIFICATIONS FOR FURTHER DETAILS. EXISTING 45 FIRE RATING MUST BE MAINTAINED.
3. PROVIDE NEW BULKHEAD ON EAST WALL. BULKHEAD TO BE 113" (9'-5") A.F.F (+/-). REFER TO REFLECTED CEILING PLAN FOR DIMENSIONS & LOCATION.
4. PROVIDE NEW BULKHEAD ABOVE NEW RANGE HOOD C/W ACCESS HATCH. STEEL STUD & CEMENT BOARD CONSTRUCTION, PAINTED PER FINISH PLAN. ADJUST DEPTH TO ALIGN FRONT FACE OF BULKHEAD AT SLOPE OF RANGE HOOD. REFER TO SECTIONS FOR DETAILS. CONFIRM LOCATION OF ACCESS HATCH W/ CONTRACT ADMINISTRATOR. PAINT HATCH TO MATCH BULKHEAD.
5. ALL EXPOSED SIDES OF BULKHEADS TO BE PAINTED. SEE FINISH PLAN, ELEVATIONS, AND SPECIFICATIONS FOR DETAILS.
6. ALL NEW MECHANICAL GRILLES/DIFFUSERS OR CEILING ACCESS HATCHES TO BE WHITE.
7. RELOCATE ACCESS HATCHES, LIGHT FIXTURES, AND OTHER CEILING MOUNTED ITEMS AS REQUIRED TO SUIT NEW CONSTRUCTION.

NORTH KEY PLAN
SCALE: N.T.S.

NOTES:

THESE DRAWINGS SHALL NOT BE SCALED.

THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY ONESELF ALL DIMENSIONS, DATUM, AND DETAILED INFORMATION SHOWN ARE CORRECT.

THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.

THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ALL OF HIS SUBTRADES ARE MADE AWARE OF AND FOLLOW THE BUILDING GUIDELINES FOR CONTSTRUCTION. CONFIRM HOURS OF OPERATION FOR DEMOLITION/CONSTRUCTION WITH CITY CONTRACT ADMINISTRATOR PRIOR TO UNDERTAKING WORK AS OUTLINED ON DRAWINGS.

AS THE TENANT WILL CONTINUE TO CONDUCT BUSINESS DURING THE DEMOLITION /CONSTRUCTION PERIOD, ALL WORK MUST BE COORDINATED WITH CITY CONTRACT ADMINISTRATOR AND/OR OFFICE MANAGER. SOME WORK MAY NEED TO BE COMPLETED OUTSIDE OF THE REGULAR BUSINESS HOURS.

CARE TO BE TAKEN TO KEEP ALL COMMON CORRIDOR AND EXIT AREAS CLEAR OF DEBRIS AND OBSTRUCTIONS DURING DEMOLITION/CONSTRUCTION.

ALL OPENINGS THROUGH FIRE ASSEMBLIES ARE TO BE FIRE STOPPED AND SEALED WITH ULC APPROVED FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE SEPARATION, AND PROVIDE A SMOKE-TIGHT BARRIER.

ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS & APPLICABLE CODES.

THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE REMOVAL OF ALL ITEMS FORMING THE PART OF THE RENOVATION WORK.

WHERE NEW FLOORING AND BASE IS TO BE INSTALLED IN EXISTING AREAS (REFER TO FLOOR PLAN AND ROOM SCHEDULE) THE EXISTING FLOORING SURFACE AND BASE MUST BE REMOVED, UNLESS OTHERWISE NOTED. ALL FLOOR SURFACES SHALL BE PREPARED IN ACCORDANCE TO MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF NEW FLOOR.

WHERE PAINTING OF EXISTING WALLS IS INDICATED ON THE ROOM SCHEDULE, THESE WALLS MUST BE CLEANED OF ANY EXISTING WALL COVERING, PATCHED & PREPARED TO ACCEPT NEW MATERIAL, UNLESS OTHERWISE NOTED.

CONTRACTOR TO PROVIDE HOARDING WHERE REQ'D TO MAINTAIN HEALTH AND SAFETY. ALL ACCESS TO EXITS TO BE MAINTAINED THROUGHOUT CONSTRUCTION.

REFUSE TO REMOVED DAILY.

CONTRACTOR TO ATTEMPT TO RECYCLE ALL ITEMS REMOVED IN AN ENVIRONMENTALLY FRIENDLY MANNER.

ALL NEW LIGHTING FIXTURES & NEW RECEPTACLES TO BE CONNECTED TO APPROPRIATE PANELS.

GENERAL DUTY RECEPTACLES SHALL BE WHITE & CSA APPROVED, C/W STAINLESS STEEL TRIM PLATES MOUNTED 18" ABOVE FINISHED FLOOR OR OTHERWISE NOTED.

THERMOSTATS, FIRE ALARM PULL STATIONS & LIGHT SWITCHES SHALL BE MOUNTED 47" ABOVE FINISHED FLOOR OR OTHERWISE NOTED.

ALL ABANDONED ELECTRICAL FIXTURES, COMPONENTS, RECEPTACLE & DATA WIRING SHALL BE REMOVED BACK TO SOURCE & TERMINATED AS PER APPLICABLE CODES. IF APPLICABLE, THIS INCLUDES WIRING CONTAINED IN HEADER DUCTS IN-FLOOR.

DIMENSIONS ARE TO FINISHED FACE UNLESS OTHERWISE NOTED.
STAR (*) PRECEEDING DIMENSION DENOTES CRITICAL DIMENSION MUST BE MET.

WARNING:
ASBESTOS MAYBE PRESENT BEHIND WALLS, CEILING SPACE & FLOORS. IF ASBESTOS AND/OR ANY HAZARDOUS MATERIAL IS FOUND, STOP WORK IMMEDIATELY & CONTACT CITY OF WINNIPEG CENTRAL CONTROL AT **204-986-2351**.

No.	REVISION/DESCRIPTION	BY	DATE
4	ISSUED FOR CONSTRUCTION	CEA	FEB 2 2024
3	ISSUED FOR 99% CLIENT REVIEW	CEA	NOV 17 2023
2	ISSUED FOR PRICING	CEA	FEB 28 2023
1	ISSUED FOR 60% CLIENT REVIEW	CEA	OCT 31 2022
0	ISSUED FOR 30% CLIENT REVIEW	SFC	JUNE 19 2019

SEAL

PROVINCE OF MANITOBA
BRUCE HAMM PAULS
2024-02-02
REGISTERED ARCHITECT
MAA Digital Signature Applied

DRAWN	CHECKED	DESIGNED	APPROVED
CEA	BP	CEA	

DATE 2024.01.23 USER APPROVAL

Winnipeg
THE CITY OF WINNIPEG
PLANNING, PROPERTY AND DEVELOPMENT DEPARTMENT
MUNICIPAL ACCOMMODATIONS DIVISION
3–65 GARRY STREET, R3C 4K4

PROJECT
TURTLE ISLAND RECREATION CENTRE
KITCHEN RENOVATION

510 KING STREET

SHEET TITLE
PARTIAL MAIN FLOOR
REFLECTED CEILING PLAN

SCALE	PROJECT No:	SHEET No:
AS SHOWN	2019-078	A2.2

ADDRESS: 510 KING STREET
PROJECT No: 2019-078
SHEET TITLE: PARTIAL MAIN FLOOR - REFLECTED CEILING PLAN
DATE: 2024.01.23
FILE NAME: 2019078V1.dwg\A0-A4.1