

NOTES:


- 1. LAYOUT OF PLANT MATERIAL TO BE APPROVED BY CA PRIOR TO INSTALLATION.
- 2. PIT TO BE DUG WITH BACK HOE NOT TREE SPADE.
- 3. CONTRACTOR TO ENSURE 'T'-BARS DO NOT PENETRATE ROOT BALL.
- 4. SECURE 'T'-BARS TO TREE @ APPROX. 2/3 TOTAL TREE HEIGHT ABOVE FIN. GRADE.
- 5. TREE SHALL BE PRUNED
 IMMEDIATELY AFTER PLANTING TO
 REMOVE DEAD, BROKEN, DISEASED,
 DYING OR RUBBING BRANCHES.
 CO-DOMINANT STEMS LESS THAN
 100mm (4") DIA. AT THE FORKS SHALL
 BE PRUNED OFF AND ONE MAIN STEM
 SHOULD REMAIN. TREE TOPPING OR
 HEADING IS NOT PERMITTED AT ANY
 TIME.
- 6. STAKES & TIES TO BE REMOVED BY CONTRACTOR AT END OF MAINTENANCE PERIOD AND UPON ACCEPTANCE BY L.A.



TYPICAL CONIFEROUS TREE PLANTING

SCALE - 1:25

| LOCATION APPROVED UNDERGROUND STRUCTURES | B.M. ELEV. | | | SCATLIFF + MILLER + MURRAY | | | |
|---|---------------|-------------------|----------------------|----------------------------|-------------------------------------|------------------------------|--|
| SUPV. U/G STRUCTURES DATE | | | | | visienary urban design + landscapes | | |
| COMMITTEE | | | | | DESIGNED AJ | CHECKED IY | |
| NOTE: LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION | | | | | DRAWN AJ/DT | APPROVED CO | |
| AVAILABLE BUT NO QUÂRANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION. | | | | | SCALE: HORIZONTAL 1:25 | RELEASED FOR CONSTRUCTION | |
| | 0 | ISSUED FOR TENDER | 2023/08/22 | ΙY | VERTICAL | | |
| | N□. | REVISIONS | DATE (YYYY/MM/DD) | BY | DATE 2023 08 22 | DATE | |





THE CITY OF WINNIPEG

WATER AND WASTE DEPARTMENT SOLID WASTE DIVISION

2023 BRRMF LANDSCAPING AND TREE PLANTING PROJECT SHEET 5 OF 5

PLANTING DETAIL

1-0400A-B0003-002