



623-2023 ADDENDUM 2

HORIZONTAL DIRECTIONAL DRILLING (PIT LAUNCH) TO INSTALL COPPER WATER SERVICES 19MM TO 50 MM

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: JANUARY 15, 2024
BY: Dennis Kwast
TELEPHONE NO. 431-336-1767

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

FORM B: PRICES

Replace: 623-2023 Form B: Prices with 623-2023 Addendum 2 - Form B: Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R1): Part A – Horizontal Directional Drilling (Pit Launch) – Weekdays
(excluding statutory holidays)

Part B – Horizontal Directional Drilling (Pit Launch) – Weekends and statutory holidays

Part C – Additional Pricing (See E9)

PART B– BIDDING PROCEDURES

Add: B10.1.2 Bidder must specify the Flat Rate per Site in Form B: Prices. This Flat Rate represents the invoiced amount (excluding GST) for each completed service by the Contractor. Information about the expected number and length of services is described in section D2.6.

PART D – SUPPLEMENTAL CONDITIONS

Add: D2.2 (a) (iii) Horizontal earth coring

Add: D2.2 (a) (iv) Horizontal directional pushing

Add: D2.3 (c) (ii) The City will adjust the depth of the pit as requested by the Contractor to avoid contact with underground infrastructure.

Add: D2.3 (c) (iii) The City will provide and install shoring.

Revise: B2.4.2 to read: A Water & Waste representative will notify the Contractor when service is required.

Revise: B2.4.2 (a) to read: The Contractor is expected to arrive at the Site within 3 hours or less.

Add: D2.4.2 (a)(i) If the Contractor is unable to arrive at the Site at the time requested, the Contractor shall provide an estimated time of arrival.

- Add: D2.6 (a) The installed service length for each Site will range from approximately 15 to 90 feet.
- Add: D2.6 (a) (i) Approximately 85% of service lengths are expected to be in the range of 30 to 50 feet.
- Add: D2.6 (a) (ii) The approximate quantities and lengths of services are based on previous years and may vary.
- Add: D3.2 The Contractor is responsible for any damages to existing services caused by the Work and shall reinstate and/or repair existing services to the satisfaction of the City of Winnipeg.
- Add: D3.2 (a) The Contractor is responsible to determine depth of existing services.
- Add: D3.2 (b) The City will arrange for locates before the Contractor arrives to the Site.
- Add: D3.2 (c) The Contractor shall complete a risk assessment before initiating the Work, and notify the City of potential hazards.
- Revise: D4.1 (a) **“Horizontal Directional Drilling (Pit Launch)”** means using a compact trenchless method for boring, piercing, coring, or drilling. The equipment will be lowered into a ‘pit’ with an opening approximately 5’ by 8’, and will be used to install a copper service pipe. This method is commonly used when there is an inadequate amount of room at the Site for a surface launched horizontal directional drill.
- Delete: D4.1(b)
- Revise: D14.1 The Contractor shall not commence any Work until they are in receipt of a Purchase Order from the Award Authority authorizing the commencement of the Work, unless instructed otherwise by the City Representative.
- Delete: D16.
- Delete: D16.1

PART E – SPECIFICATIONS

- Delete: E4 – E8
- Revise: E9.1 In addition to a Flat Rate for the Installation of Copper Water Services 19mm to 50mm, the Contractor will have the option to claim a Standby Rate if all of the following apply:
- (a) the Contractor is on site and ready to proceed with the work
 - (b) the Contractor is delayed at least one (1) hour because the City is not prepared to proceed with the Work
- Revise: E9.2 The Standby Rate cannot be claimed for any time before the agreed-on start time determined in D2.4.2.
- Delete: E9.3 – E9.11

PART F – SECURITY CLEARANCE

- Revise: F1.1 Each individual proposed to perform Work under this Contract shall be required to obtain a Global Sanctions & PEP Check and a Police Information Check as detailed below.