

REFLECTED CEILING DEMOLITON PLAN

SCALE 1:100

FIRE SEPARATION LEGEND

FOR DRAWING CLARITY FIRE SEPARATION LINETYPES ARE NOT INDICATED THROUGH DOOR AND WINDOW OPENINGS, HOWEVER ALL WALLS ABOVE AND BELOW DOORS AND WINDOWS SHALL BE CONSTRUCTED TO MATCH ADJACENT FIRE SEPARATIONS INDICATED.

NFS NON RATED FIRE SEPARATION

1 HOUR FIRE SEPARATION

THE FOLLOWING NOTES AND DRAWINGS ARE INTENDED TO ASSIST THE CONTRACTOR IN DETERMINING THE EXTENT OF DEMOLITION AND REPAIR WORK NECESSARY IN ORDER TO CONSTRUCT THE NEW WORK CONTAINED IN THE CONTRACT DOCUMENTS.

THE DEMOLITION SHOWN INCLUDES BUT IS NOT NECESSARILY LIMITED TO THE NOTES INDICATED ON THESE DRAWINGS.

CEILING DEMOLITION NOTES:

1. REFER TO MECHANICAL & ELECTRICAL FOR REMOVAL OF DUCTS, FANS, LIGHTS, PANELS, ETC.
2. DEMOLISH ALL EXISTING CEILING FINISHES IN EXISTING OFFICES, LOCKER ROOMS, MAIN POOL DECK, RECEPTION ETC.
3. ALL EXISTING PLASTER CEILINGS ARE ASSUMED TO BE ASBESTOS CONTAINING MATERIALS. REFER TO SPECIFICATIONS FOR ABATEMENT REQUIREMENTS.
4. ALL EXISTING CEILINGS BETWEEN GRIDLINE B AND GRIDLINE D TO BE DEMOLISHED UNLESS OTHERWISE NOTED. CEILINGS TO REMAIN IN ROOMS ST-1, ST-2 AND 1:06. REFER TO MECHANICAL AND ELECTRICAL FOR RELATED DEMOLITION SCOPES.
5. REFER TO HAZARDOUS MATERIALS AND ASBESTOS ABATEMENT SPECIFICATIONS FOR REMOVAL OF ASBESTOS CONTAINING MATERIALS.

CEILING LEGEND:

EXISTING LIGHT FIXTURE TO REMAIN

EXISTING LIGHT FIXTURE TO BE REMOVED

ACOUSTIC CEILING SYSTEM TO BE DEMOLISHED

ABBREVIATIONS:

ACS	ACOUSTIC CEILING UNITS ON SUSPENSION SYSTEM
AP	ACCESS PANEL
EP	EPOXY PAINT
ES	EXPOSED STRUCTURE
GB	SUSPENDED GYPSUM BOARD CEILING
GBBH	GYPSUM BOARD BULKHEAD
P	PAINT
U	UNFINISHED
WD	WOOD
W/M	WALL MOUNTED
X	EXISTING

DEMOLITION KEYNOTES:

1. CEILING IN STAIRWAY AND CHLORINE ROOM TO REMAIN.
2. REMOVE EXISTING W/M FAN. REFER TO MECHANICAL AND ELECTRICAL.
3. REMOVE EXISTING FLAT PVC SHROUD AT HIGH LEVEL BETWEEN MASONRY AND GLAZING UNITS. EXISTING SHROUD SPANS FROM GRID LINE x1 TO x9.
4. DEMOLISH EXISTING WALL MOUNTED LIGHT FIXTURE. REFER TO ELECTRICAL.
5. REMOVE CEILING MOUNTED ANCHORS.
6. REMOVE CEILING MOUNTED SPEAKERS. TURN OVER TO OWNER. REFER TO ELECTRICAL FOR OTHER ASSOCIATED WORK.

No.	Date	Issue / Revision	By
0	22/12/2023	ISSUED FOR CONSTRUCTION	CF

Drawn By: DN

Printing Date: DEC. 22, 2023

PROVINCE OF MANITOBA — JOREY W. GREENHAM — 2023-12-22 — REGISTERED ARCHITECT

PROVINCE OF MANITOBA — LM ARCHITECTURAL GROUP — No. 052 — APPROVED PARTNERSHIP OF CORPORATIONS

Drawings and specifications, as instruments of service are the property of the architects, the copyright in the same being reserved to them. No reproduction may be made without the permission of the architects, and when made, must bear their names. All prints to be returned.

The contractor is to verify dimensions and data noted herein with conditions on the site and is held responsible for reporting any discrepancy to the architects for adjustment.

LM Architectural Group

500-136 Market Ave
Winnipeg Manitoba Canada R3B 0P4
t: (204) 942.0681 f: (204) 943.8676
www.lm-architects.com

CITY OF WINNIPEG
BONIVITAL POOL RENEWAL

1215 Archibald St, Winnipeg, MB.

REFLECTED CEILING DEMOLITION PLAN

Comm. No.: 2129 Sheet: **A1.3**

Plotted on: ##-##-##