

1 EDP2.1 MAIN FLOOR PLAN DEMOLITION POWER & SYSTEMS
SCALE: 1:100

NOTES:

1. DISCONNECT AND REMVOE EXISTING ELECTRICAL DEVICE AND ALL ASSOCIATED WIRE AND CONDUIT BACK TO SOURCE.
2. EXISTING DEVICE SHALL REMAIN AND BE MAINTAINED.
3. DISCONNECT AND REMOVE EXISTING SPEAKER AND REMOVE ALL EXISTING WIRE AND CONDUIT. SEE NEW WORK.
4. DISCONNECT AND RELOCATE EXISTING FIRE ALARM DEVICE AND REMOVE ALL EXISTING WIRE AND CONDUIT. SEE NEW WORK.
5. DISCONNECT EXISTING MECHANICAL EQUIPMENT AND REMOVE ALL EXISTING WIRE AND CONDUIT BACK TO SOURCE.
6. EXISTING DEVICES MOUNTED ALONG THE POOL ARE MOUNTED UP AT A HIGH LEVEL AND SHALL BE MAINTAINED UNLESS NOTED OTHEREWISE.
7. DISCONNECT EXISTING SAUNA EQUIPMENT AND RELOCATE TO NEW LOCATION.
8. DISCONNECT AND REMOVE EXISTING PANEL A & PANEL A-EAST. BRANCH CIRCUITS SHALL BE RELOCATED TO NEW PANEL A LOCATION. SEE NEW WORK.
9. RELOCATE CONTENTS OF PANEL EM THAT IS PRESENTLY BEING USED AS A JUNCTION BOX AND RELOCATE CONTROLS UP INTO CEILING SPACE.
10. DISCONNECT AND REMOVE EXISTING PA SYSTEM. SEE NEW WORK.
11. EXISTING DROWNING ALARM PANEL SHALL BE RELOCATED. SEE NEW WORK.
12. EXISTING LIGHTING CONTROL PANEL SHALL BE RELOCATED. EXTEND WIRING TO SUIT. SEE NEW WORK.
13. EXISTING MASTER CLOCK SYSTEM SHALL BE RELOCATED. EXTEND EXISTING WIRING. SEE NEW WORK.
14. RELOCATE EXHAUST FAN CONTROLS TO NEW PANEL A LOCATION.
15. DISCONNECT AND REMOVE EXISTING NETWORK 8000 PANEL C/W ALL ASSOCIATED WIRING AND CONDUIT.
16. REMOVE TELEPHONE OUTLET ONCE PAYPHONE HAS BEEN REMOVED.
17. RELOCATE CONDUIT AND OUTLET BOXES FOR DROWNING ALARM ON POOL SIDE TO ACCOMMODATE NEW FURRED OUT WALL.
18. DISCONNECT EXISTING CUH AND RECONNECT NEW ONE IN SAME LOCATION.
19. DISCONNECT EXISTING AC UNIT AND RECONNECT NEW ONE IN SAME LOCATION.
20. DISCONNECT EXISTING SUPPLY FAN AND HEATING COIL AND REMOVE ALL EXISTING WIRING AND CONDUIT.
21. SUPPLY AND INSTALL NEW MIRCOM FIRE ALARM ANNUNCIATOR IN EXISTING LOCATION.

PROVINCE OF MANITOBA
2023-12-21
K. E. ISAAK
REGISTERED PROFESSIONAL ENGINEER

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
MCW Consultants Ltd.
No. 7183

THIS IS A PRINT OF A DOCUMENT THAT HAS BEEN ELECTRONICALLY AUTHENTICATED WITH TECHNOLOGY AUTHORIZED BY THE EGM. THE ORIGINAL IS IN ELECTRONIC FORM.

MCW
13600
MCW Consultants Ltd.
210-1821 Wellington Avenue
Winnipeg, Manitoba, R3H 0G4
Phone - (204) 779-7900
mcw_wpg@mcw.com
www.mcw.com

No.	Date	Issue / Revision	By
0	22/12/2023	ISSUED FOR CONSTRUCTION	DG

Drawn By: MFP
Printing Date: 22/12/2023

Drawings and specifications, as instruments of service are the property of the architects, the copyright in the same being reserved to them. No reproduction may be made without the permission of the architects, and when made, must bear their names. All prints to be returned.

The contractor is to verify dimensions and data noted herein with conditions on the site and is held responsible for reporting any discrepancy to the architects for adjustment.

LM Architectural Group
500-136 Market Ave
Winnipeg Manitoba Canada R3B 0P4
t: (204) 942.0691 f: (204) 943.9676
www.lm-architects.com

CITY OF WINNIPEG
BONIVITAL POOL RENEWAL

1215 Archibald St, Winnipeg, MB.

MAIN FLOOR PLAN DEMOLITION POWER & SYSTEMS

Comm. No.: 2129 Sheet: **EDP2.1**
Plotted on: 22-12-23