


1 BASEMENT FLOOR PLAN DEMOLITION ELECTRICAL
ED2.0 SCALE: 1:100

NOTES:

1. DISCONNECT EXISTING MECHANICAL EQUIPMENT AND REMOVE ALL EXISTING WIRING AND CONDUIT.
2. EXISTING DEVICES IN BASEMENT SHALL REMAIN AND BE MAINTAINED.
3. REPLACE EXISTING EXIT SIGN WITH NEW RUNNING MAN EXIT SIGN.
4. DISCONNECT EXISTING METER AND TURN OVER TO MANITOBA HYDRO.
5. EXISTING DISTRIBUTION MD-1 SHALL BE RELABELED SD-1 AND SHALL BE FED FROM NEW TRANSFORMER.
6. MECHANICAL CONTROL AND SECURITY CONTROL SHARE A CABINET. EXISTING CONTROLS FOR SAME SHALL REMAIN IN CABINET AND BE MAINTAINED.
7. DISCONNECT ANY ELECTRICAL FOR CONTROL PANEL FOR EXISTING BOILERS BEING REMOVED AND RE-USE EXISTING CIRCUIT TO FEED NEW BOILER CONTROLS.
8. EXISTING FIRE ALARM CONTROL PANEL SHALL BE REPLACED WITH NEW. PROVIDE NEW ANNUNCIATOR IN VEST. SEE NEW WORK.
9. DISCONNECT AND REMOVE EXISTING LIGHTING IN THIS AREA. REUSE EXISTING CIRCUITS TO FEED NEW LIGHTING.
10. EXISTING FIRE ALARM DEVICES SHALL BE RELOCATED TO NEW CEILING.

PROVINCE OF MANITOBA
2023-12-21
K. E. ISAAK
REGISTERED PROFESSIONAL ENGINEER

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
**MCW Consultants Ltd.**
**No. 7183**

"THIS IS A PRINT OF A DOCUMENT THAT HAS BEEN ELECTRONICALLY AUTHENTICATED ABF(1) TECHNOLOGY AUTHORIZED BY THE EGM. THE ORIGINAL IS IN ELECTRONIC FORM."


MCW
MCW Consultants Ltd.
13600
210-1821 Wellington Avenue
Winnipeg, Manitoba, R3H 0G4
Phone - (204) 775-7900
mcw_wpg@mcw.com
www.mcw.com


| No. | Date | Issue / Revision | By |
|---|---|---|---|
| 0 | 22/12/2023 | ISSUED FOR CONSTRUCTION | DG |

Drawn By:
Printing Date: 22/12/2023


Drawings and specifications, as instruments of service are the property of the architects, the copyright in the same being reserved to them. No reproduction may be made without the permission of the architects, and when made, must bear their names. All prints to be returned.

The contractor is to verify dimensions and data noted herein with conditions on the site and is held responsible for reporting any discrepancy to the architects for adjustment.



LM Architectural Group
500-136 Market Ave
Winnipeg Manitoba Canada R3B 0P4
t: (204) 942.0691 f: (204) 943.8676
www.lm-architects.com


# CITY OF WINNIPEG
## BONIVITAL POOL RENEWAL

1215 Archibald St, Winnipeg, MB.

# BASEMENT FLOOR PLAN DEMOLITION ELECTRICAL

Comm. No.: 2129 Sheet: **ED2.0**