



# 763-2023 ADDENDUM 2

## DIRECT CURRENT FAST CHARGING AT 600 BRANDON AVE TRANSIT GARAGE

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL**

ISSUED: November 20, 2023  
BY: Andrei Aroutiounov  
TELEPHONE NO. 204 898-2623

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

---

### **NMS SPECIFICATIONS**

Section 26 24 02 SERVICE ENTRANCE BOARD

Revise: 2.8.1 to read: Acceptable Manufacturers: Eaton, Siemens and Square D

### **QUESTIONS AND ANSWERS**

Q1: Will the Attendance at the Site Investigation be published on MERX?

A1: Site Investigation Attendees – November 3, 2023 and November 7, 2023

Siemens	Wescan
The Secure Construction Group	Lowe Mechanical
Di-Tech Int.	Ion Electrical
NFI	Tri-Star Traffic
Powertec Electric	McCaine Electric
Robin Electric	ABB Emobility
Asiil Enterprises Ltd.	Forbes Bros Ltd.
Black + McDonald	BLCC
Power ON	Prairie Parking
NRG Management	Plan Group Inc.

Q2: Does the Storage Room floor contain in-floor heat?

A2:

Storage Room floor does not contain in-floor heat. However, there are two trap primer lines embedded in the floor. The ends of the lines are exposed just South of the double doors leading out of the Storage Room. The lines shall remain functional during the installation and after the completion of the installation.

Q3: Are exterior concrete bollards required as shown on Drawing 763-2023\_Drawing\_E-304\_R0, Detail 1?

A2:

The bollards shown in Detail 1 are not required.