

Full Site Area	0.0789	ha
Allowable C	0.15	

Catchment	m2	Area Takeoff	C	% Area	Weighted C
C1: Asphalt & Concrete	225	0.06	0.90	30.0%	0.27
C1: Roof	60	0.01	0.95	8.0%	0.08
C1: Gravel	24	0.01	0.50	3.3%	0.02
C1: Landscaping	439	0.11	0.25	58.7%	0.15
LNC: Asphalt & Concret	40	0.01	0.90	100.0%	0.90
LNC: Roof	0	0.00	0.95		
LNC: Gravel	0	0.00	0.50		
LNC: Landscaping	0	0.00	0.25		

Summary					
Catchment 1	748	0.18	0.51	94.9%	0.48
Uncontrolled	40	0.01	0.90	5.1%	0.05
Subtotal	789	0.2		100.0%	0.53

Site Allowable Outflow	3.599	lps
Rational Method, Q = 2.78CIA		

Time of Concentration	10.0	min	$t_4 = 1199$
Intensity, i5"	109.51	mm/hr	$t_4 = (t + 6)^{1.4828}$
Intensity, i25"	154.33	mm/hr	$t_{25} = (t + 9)^{1.4828}$
McLaren Report			

Site	Site Area (Ha)	C	Allow. 5-yr (lps)	25Yr C	25-yr (lps)	Restricted Discharge (lps)	Req'd Storage (m3)
Catchment 1	0.075	0.15	3.42	0.51	16.35	1.42	33.1
Uncontrolled	0.004	0.15	0.18	0.90	1.55		
Subtotal	0.08		3.60		17.90	1.42	33.08
Net Allowable			2.05		17.90	1.42	33.08

Location	Qty	Area (m2)	Depth (m)	Length (m)	Subtotal (m3)
Surface Ponding, CB1		(Volume determined from surface model)			30.06
CB1 (9000)	1.0	0.64		2.850	1.84
CATCHPIT 1 (9000)	1.0	0.64		1.390	0.88
CATCHPIT 2 (9000)	1.0	0.64		1.390	0.88
Pipe (1500)	1.0	0.018		15.340	0.27
Pipe (1500)	1.0	0.018		29.500	0.47
Subtotal					34.41




WWS Flow Estimation - Pre-Development	WWS Flow Estimation - Post-Development
Area	0.0789
Use	Public W/R
Persons	300.00
Residential ADWF	0.0417 lps
Peak Factor	4.08
PDWF	0.170 lps
Extraneous Weeping Tile	0.000
Groundwater	0.000
Pre Peak WW Flow	0.17
Post Peak WW Flow	0.17 lps
WWF Increase	0.00 lps

Criteria	Design Summary	Pre-Dev	Post-Dev
Wastewater		0.17	0.00 lps
Surface Runoff			
Allowable 5YR	3.42		lps
Restricted Discharge			1.42 lps
Uncontrolled (25-Yr)			1.55 lps
Sump Discharge (Groundwater)			0.000 lps
Subtotal	3.59	2.97	lps
Required Storage			33.08 m3
Provided Storage			34.41 m3

Design Criteria	Value	Units	Source
Public Lavatory	12	lps/day	0.00014 l/s
Source	McLaren & City, Wastewater Engineering, Treatment & Resource Recovery		
Extraneous Flows			
Weeping Tile	4.5	L/MH/Min	0.075 L/Connect/s
MH/CB	12	L/MH/Min	0.200 L/MH/s
Groundwater	2200	L/ha/Day	0.025 L/ha/s
Source	City of Winnipeg, Wastewater Flow Estimation Guidelines		


PLAN GRADING & SERVICING 1:80

- Construction Specifications**
- Where indicated, construction must conform to the City of Winnipeg, *Standard Construction Specifications* and all references contained herein refer to these specifications. "SD" refers to City of Winnipeg standard details.
  - All materials used for construction must conform to City of Winnipeg, *Approved Products for Underground Use Within the City of Winnipeg* except as indicated otherwise.
- Water & Wastewater Services**
- No new water or wastewater services proposed.
- Gravit Sewer Service to CW-2030**
- All gravity sewer installation shall be in accordance with CW 2030/2130, SD-014
  - Gravity service pipe shall be in accordance with CAN/CSA B182.2 and ASTM D3034, SDR-35.
  - All pipe installations through road right of way shall be completed with trenchless methods. Any open trench construction on site shall be as follows:
    - Class 'B' Bedding to SD-001
    - Backfill to SD-002, Class '2' Type 2 Backfill in gravel, hand-surfaced & traveled areas and all areas within 2.0m of Edge of Road Shoulder.
    - Class '5' in landscaped and untraveled areas.
    - To CW2030/2130, Detail SD-014
- Surface Drainage**
- All flows restricted to the 1-in-5yr storm and detention storage provided for up to the 25-yr design storm as shown in the design tables.
- General Notes**
- Contractor to obtain all necessary permits.
  - Contractor to obtain clearances from all utilities before excavating. Confirm all existing infrastructure information in field before construction. Notify the Engineer immediately of any discrepancies that affect installation or design.
  - Confirm all dimensions before beginning construction.
  - Consult Geotechnical Report and geotechnical engineer to confirm the suitability of native soils for backfill. Consult Geotechnical Engineer for erosion control measures including riprap in swale along building. Riprap detail provided as-is and should be reviewed by Geotechnical Engineer.
  - Civil drawings are to be read in coordination with Architectural, Structural, and Mechanical disciplines. Where a discrepancy is found between these plans and coordinated disciplines, notify the Engineer immediately.
  - Tempest flow curve has been extrapolated to demonstrate flow above 3m head. This may not be an exact representation of the true flow curve above 3m.
  - IPEX (the supplier) has verified that the LMF 30 will restrict the flow per design (1.42L/s) at the design head



Existing	Proposed	Existing	Proposed	Existing	Proposed
EG -0.88%	Surface Elev. (394.98)	2.98%	Hydrant	Contour	Proposed
150 W/W	Waterman	150 W/W	Curb Step	Ponding Area	Proposed
250 W/W/S	Wastewater Sewer	250 W/W/S	Valve		
300 L/D/S	Land Drainage Sewer	300 L/D/S	Manhole		
			Catchbasin		
			Topo Survey Point		

This is not a legal plan. Contours shown are approximated for reference only. Whole numbers are millimetres (mm). Decimal numbers are metres (m). Current Metric to Standard 1:0m = 3.28084. This plan is prepared only for the Client and may not be used by any other party without written consent.



**Building Verification Survey**

- By Stevens Surveys, File 23-135, dated 20th April, 2023.
- Elevations have been derived by GPS observations. Vertical Datum CGVD28.

**Coordination**

Civil design is based on coordinated design files provided by the project manager. Should there be a discrepancy between this and any other plans or design, notify the Project Manager immediately.

Designed: KP  
Checked: DM  
Approved: DM