FOOD AND NUTRITION EQUIPMENT CONNECTION SCHEDULE

NO.	DESCRIPTION	ROOM	LOAD HP	LOAD A	LOAD W	VOLT	PH	CIRCUIT	CIRCUIT BREAKER	CONDUIT & WIRE SIZE	STARTER COMPONENT	STARTER FURN. INST. WIRED	CONTROL DEVICE COMPONENT	CONTROL DEVICE FURN. INST. WIRED	DISCONNECT COMPONENT	DISCONNECT FURN. INST. WIRED	NOTES
EQ-03A	DISHWASHER			10 A		120 V	1	FN-32	15A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-20R RCPT	DIV 26 DIV 26 DIV 26	
EQ-03A	DISHWASHER			10 A		120 V	1	FN-33	15A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-20R RCPT	DIV 26 DIV 26 DIV 26	
EQ-03A	DISHWASHER			10 A		120 V	1	FN-35	15A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-20R RCPT	DIV 26 DIV 26 DIV 26	
EQ-03A	DISHWASHER			10 A		120 V	1	FN-36	15A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-20R RCPT	DIV 26 DIV 26 DIV 26	
EQ-03A	DISHWASHER			10 A		120 V	1	FN-37	15A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-20R RCPT	DIV 26 DIV 26 DIV 26	
EQ-03B	COMMERCIAL DISHWASHER			10 A		120 V	1	FN-34	15A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-15R RCPT	DIV 26 DIV 26 DIV 26	
EQ-04	REFRIGERATOR			10 A		120 V	1	FN-31	15A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-15R RCPT	DIV 26 DIV 26 DIV 26	
EQ-11	RANGE	1:107		40 A		208 V	1	FN-1,3	50A/2P	1 SET 21(3/4")C 3-#8R90 #10 BOND	---	---	---	---	14-50R RCPT	DIV 26 DIV 26 DIV 26	
EQ-11	RANGE	1:107		40 A		208 V	1	FN-20,22	50A/2P	1 SET 21(3/4")C 3-#8R90 #10 BOND	---	---	---	---	14-50R RCPT	DIV 26 DIV 26 DIV 26	
EQ-11	RANGE	1:107		40 A		208 V	1	FN-23,25	50A/2P	1 SET 21(3/4")C 3-#8R90 #10 BOND	---	---	---	---	14-50R RCPT	DIV 26 DIV 26 DIV 26	
EQ-11	RANGE	1:107		40 A		208 V	1	FN-24,26	50A/2P	1 SET 21(3/4")C 3-#6R90 #10 BOND	---	---	---	---	14-50R RCPT	DIV 26 DIV 26 DIV 26	
EQ-11	RANGE	1:107		40 A		208 V	1	FN-27,29	50A/2P	1 SET 21(3/4")C 3-#6R90 #10 BOND	---	---	---	---	14-50R RCPT	DIV 26 DIV 26 DIV 26	
EQ-11	RANGE	1:107		40 A		208 V	1	FN-28,30	50A/2P	1 SET 21(3/4")C 3-#6R90 #10 BOND	---	---	---	---	14-50R RCPT	DIV 26 DIV 26 DIV 26	
EQ-12	MICROWAVE			10 A		120 V	1	FN-38	20A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-20R RCPT	DIV 26 DIV 26 DIV 26	
EQ-12	MICROWAVE			10 A		120 V	1	FN-39	20A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-20R RCPT	DIV 26 DIV 26 DIV 26	
EQ-12	MICROWAVE			10 A		120 V	1	FN-40	20A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-20R RCPT	DIV 26 DIV 26 DIV 26	
EQ-12	MICROWAVE			10 A		120 V	1	FN-41	20A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-20R RCPT	DIV 26 DIV 26 DIV 26	
EQ-12	MICROWAVE			10 A		120 V	1	FN-42	20A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-20R RCPT	DIV 26 DIV 26 DIV 26	
EQ-12	MICROWAVE			10 A		120 V	1	FN-43	20A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-20R RCPT	DIV 26 DIV 26 DIV 26	
EQ-12	MICROWAVE			10 A		120 V	1	FN-13	20A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-20R RCPT	DIV 26 DIV 26 DIV 26	
EQ-15	UPRIGHT FREEZER			10 A		120 V	1	FN-17	15A/1P	1 SET 21(3/4")C 2-#12R90 #12 BOND	---	---	---	---	5-15R RCPT	DIV 26 DIV 26 DIV 26	
EQ-29	ELECTRIC COOKTOP	1:107		27 A		208 V	1	FN-2,4	40A/2P	1 SET 21(3/4")C 3-#8R90 #10 BOND	---	---	---	---	NFS	DIV 26 DIV 26 DIV 26	
EQ-30	WALL OVEN	1:107		31 A		208 V	1	FN-62,64	40A/2P	1 SET 21(3/4")C 3-#6R90 #10 BOND	---	---	---	---	NFS	DIV 26 DIV 26 DIV 26	

COMBINATION DISCONNECT TYPES:

FS	FUSED SWITCH
NFS	NON-FUSED SWITCH
MCP	MOTOR CIRCUIT PROTECTOR
CB	CIRCUIT BREAKER

ABBREVIATIONS:

EC	ELECTRICAL CONTRACTOR	SC	SPEED CONTROL
MC	MECHANICAL CONTRACTOR	TC	TIME CLOCK
AS	AQUASTAT	TS	THERMOSTAT
DCP	DUPLEX CONTROLLER	OWN	OWNER
GC	GENERAL CONTRACTOR		
HS	HUMIDSTAT		
INT	INTERLOCKED (WITH)		

GENERAL NOTES:

A. NONE.

SCHEDULE NOTES:

1. NONE.

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
Epp Siepman Engineering Inc.
No. 4035

This is a print of a document that has been electronically authenticated with technology authorized by the Engineers Geoscientists Manitoba. The original is in electronic form.

epp siepman engineering
400 - 136 Market Avenue
Winnipeg, MB R3B 0P4
T 204 453 1080

LM esp
LM Architectural Group | Environmental Space Planning
500-136 Market Avenue Winnipeg, Manitoba Canada R3B 0P4
t: 204.942.0681 lm-esp.ca

No.	REVISION/DESCRIPTION	BY	DATE
0	ISSUED FOR TENDER	JS/MP	24-04-01

SEAL

PROVINCE OF MANITOBA
M. G. PENNER
Member
23792
2024-04-01
LICENSED PROFESSIONAL ENGINEER

EW DRAWN	MP/KG CHECKED	KG DESIGNED	MP/KG APPROVED
DATE 2024-04-01	USER APPROVAL		

Winnipeg
THE CITY OF WINNIPEG
ASSETS & PROJECT MANAGEMENT DEPARTMENT
MUNICIPAL ACCOMMODATIONS DIVISION
3-65 GARRY STREET, R3C 4K4

PROJECT
PEMBINA TRAILS COLLEGIATE
VOCATIONAL WING
TENDER NO. 954-2023B
50 FRONTIER TRAIL, WINNIPEG, MANITOBA, R3Y 2H1

SHEET TITLE
Food And Nutrition Equipment Connection Schedule

SCALE	PROJECT No:	SHEET No:
1 : 96	2020-127	E6.4

DRAWING SHEET SIZE: A1 (594x841) PLOT 1:1
ESE 24049