

1 - B22 SECOND FLOOR PLAN WEST - LIGHTING

SCALE 1 : 100

KEY NOTES

1 INSTALL MEZZANINE LIGHT SWITCH AT TOP OF STAIRS.

2 PROVIDE TWO (2) ADDITIONAL TYPE SL02-8 WITH FINAL LOCATIONS TO BE COORDINATED WITH MECHANICAL DUCTWORK, PIPING, ETC.

GENERAL NOTES

A. WHERE NEW LIGHTING CONTROLS ARE ADJACENT EACH OTHER, PROVIDE GANGED DEVICE BOXES TO ACCOMMODATE TOTAL NUMBER OF CONTROLS, UNLESS NOTED OTHERWISE.

B. RECESSED LIGHTING FIXTURES IN LAY-IN CEILINGS SHALL BE INSTALLED WITH 1850MM (6'-0 ") LONG FLEXIBLE METAL CONDUIT.

C. REFER TO ARCHITECTURAL DRAWINGS FOR MOUNTING HEIGHTS OF EXTERIOR OR INTERIOR LUMINAIRES. ALL MOUNTING HEIGHTS FOR LUMINAIRES ARE TO THE BOTTOM OF THE LUMINAIRE UNLESS NOTED OTHERWISE.

D. CONFIRM QUANTITY OF STAIRWELL LIGHTING FIXTURES WITH ARCHITECTURAL DRAWINGS. PROVIDE ONE LUMINAIRE PER STAIR LANDING.

E. EMERGENCY LIGHTING CIRCUIT SHALL BE FED FROM LOCAL AC/DC INVERTER SYSTEM. LUMINAIRES SHALL BE CONTROLLED BY RELAY TYPE CONTROL THAT SENSES LOSS OF NORMAL POWER AND CONTROLS THE FIXTURE SUCH THAT LUMINAIRE COMES ON TO 100%, LOCKING OUT ALL OTHER CONTROL UNTIL NORMAL POWER IS RESTORED.

F. COORDINATE LOCATION AND MOUNTING HEIGHT OF LUMINAIRES WITHIN CRAWLSPACE WITH ALL DISCIPLINES AND TRADES PRIOR TO INSTALLATION. LUMINAIRES SHALL BE MOUNTED BELOW STRUCTURE CLEAR OF BEAMS, MECHANICAL DUCTWORK AND PIPING TO MAXIMIZE LUMINAIRE PERFORMANCE.

G. RELOCATE EXISTING LIGHTING CONTROLS AS REQUIRED TO ACCOMMODATE NEW DOOR CONFIGURATIONS.

H. EVERY NLIGHT ENABLED DEVICE, INCLUDING NLIGHT ENABLED FIXTURES, IS FURNISHED WITH ONE PERMANENTLY ADHERED ID TAG AND ONE MATCHING PARTIALLY ADHERED ID TAG. DURING INSTALLATION AND PRIOR TO STARTUP, CONTRACTOR SHALL PLACE EACH ID TAG BELOW EACH CORRESPONDING DEVICE SHOWN ON RISER DIAGRAM OR FLOOR PLAN TO FACILITATE FACTORY STARTUP.

I. ONE RELAY PACK OR NLIGHT ENABLED FIXTURE IS NEEDED PER CIRCUIT ZONE TO BE CONTROLLED AND CAN RESIDE WITHIN SENSORS, WALL PODS, OR RELAY PACKS.

J. RECHECK COUNTS TO VERIFY THE NUMBER OF RELAYS NEEDED TO SWITCH ALL DESIRED LOADS.

K. ADDITIONAL BRIDGES AND/OR SENSORS MAY BE REQUIRED DEPENDING ON BUILDING CHANGES, FINAL PARTITION HEIGHT PLACEMENT, FURNITURE PLACEMENT, EQUIPMENT HEIGHT PLACEMENT, AND SHELVING HEIGHT PLACEMENT.

L. ALL DEVICES HAVE RJ45 FEMALE PORTS. MAKING NETWORK CONTROL CABLES IS REQUIRED. UTILIZE T568B TERMINATIONS.

M. ALL NETWORK CONTROL CABLES SHALL BE TESTED WITH A LAN CABLE TESTER TO VERIFY PROPER TERMINATIONS.

N. DAISYCHAINED DEVICES SHALL BE POWERED UP AND WORKING ON DEFAULT PROGRAMMING PRIOR TO CONNECTION TO BRIDGE OR GATEWAYS.

O. LOW VOLTAGE NETWORK CONTROL CABLE CAT5E RUNS FOR LOCAL ZONES HOMERUNS AND BACKBONE SHOULD BE WHITE WITH CABLES LABELED.

P. CONTRACTOR TO VERIFY BLINK DIAGNOSTIC CODES. MAXIMUM CABLE LENGTH FROM START DEVICE TO END DEVICE IS 1500 FEET INCLUDING HOMERUN TO BRIDGE DEVICE IF PRESENT.

Q. QUANTITY AND TYPE OF POWERPACKS ARE SUBJECT TO CHANGE DEPENDING ON CIRCUITRY OR DIMMING TYPE.

R. CONTRACTOR TO VERIFY THE SEQUENCE OF OPERATIONS HAS BEEN MET IN ALL SPACES PRIOR TO AN ORDER BEING PLACED.

S. CONFIRM BALLAST DRIVER TYPES MATCH CONTROLS SELECTED PRIOR TO AN ORDER BEING PLACED.

T. ALL DIMMING IS ASSUMED TO BE 0-10V UTILIZING nPP16 D POWERPACKS UNLESS USING NLIGHT ENABLED FIXTURES. VERIFY POWERPACK COMPATIBILITY WITH FINAL APPROVED LIGHTING FIXTURE PACKAGE PRIOR TO PLACING LIGHTING CONTROL ORDER.

ENGINEERS GEOSCIENTISTS MANITOBA

Certificate of Authorization

Epp Siepman Engineering Inc.

No. 4035

This is a print of a document that has been electronically authenticated with technology authorized by the Engineers Geoscientists Manitoba. The original is in electronic form.

epp siepman engineering
400 - 136 Market Avenue
Winnipeg, MB R3B 0P4
T 204 453 1080



BUILDING KEYPLAN - SECOND

SCALE 1 : 2000

LM esp
LM Architectural Group | Environmental Space Planning
500-136 Market Avenue Winnipeg, Manitoba Canada R3B 0P4
t: 204.942.0681 lm-esp.ca

No.	REVISION/DESCRIPTION	BY	DATE
0	ISSUED FOR TENDER	JS/MP	24-04-01

SEAL

PROVINCE OF MANITOBA
M. G. PENNER
Member
23792
2024-04-01
REGISTERED PROFESSIONAL ENGINEER

EW DRAWN	MP/KG CHECKED	KG DESIGNED	MP/KG APPROVED
DATE 2024-04-01	USER APPROVAL		

Winnipeg

THE CITY OF WINNIPEG
ASSETS & PROJECT MANAGEMENT DEPARTMENT
MUNICIPAL ACCOMMODATIONS DIVISION
3-65 GARRY STREET, R3C 4K4

PROJECT

PEMBINA TRAILS COLLEGIATE
VOCATIONAL WING
TENDER NO. 954-2023B

50 FRONTIER TRAIL, WINNIPEG, MANITOBA, R3Y 2H1

SHEET TITLE

Second Floor West - Lighting Plan

SCALE	PROJECT No:	SHEET No:
As indicated	2020-127	EL2.2

DRAWING SHEET SIZE: A1 (594x841) PLOT 1:1

ESE 24049