## GRADING NOTES

1. ALL WORK TO CONFORM TO CURRENT CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS AND DETAILS UNLESS OTHERWISE NOTED.
2. DIMENSIONS ARE IN METERS UNLESS OTHERWISE NOTED.
3. DO NOT SCALE DRAWING.
4. PROTECT EXISTING TREES TO REMAIN, TYP.
5. PAVEMENT SLOPE: DIRECTIONAL SLOPE 5% MAX., CROSS SLOPE 2% MAX., UNLESS OTHERWISE NOTED.
6. PROPOSED ELEVATIONS ARE PATHWAY OR SOD GRADES UNLESS OTHERWISE NOTED.

## LEGEND

CONTOUR INTERVAL = 0.4 PROPOSED

EXISTING SLOPE: 2%

PROPOSED SLOPE: 2%

PROPOSED ELEVATION: 100m

EXISTING ELEVATION: 100m

PROPOSED CONTOURS:

EXISTING CONTOURS:

EXISTING CULVERT:

***for all TMB locations, refer to J.22-A1***

**TBM1 : 232.691**

***centre of 'O' on manhole cover***

***(north of proposed shelter)***

**TBM2 : 232.888**

***centre of 'O' on manhole cover***

***(north of proposed shelter)***

**TBM3 : 231.268**

***southeast corner of sign plinth***

CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

Winnipeg

THE CITY OF WINNIPEG
Planning, Property and Development Department
Planning and Land Use Division
Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

| | | | |
|---|---|---|---|
| DESIGNED BY | | CHECKED BY | |
| DRAWN BY | DL | APPROVED BY | |
| HORIZ. SCALE / VERT. SCALE | 1:150 | | |
| DATE | January 2025 | | |

MANAGER, PARK AND OPEN SPACES — DATE

MANAGER, PLANNING AND LAND USE DIVISION — DATE

DRAWING TITLE

**Jinnah Park**

**Picnic Shelter**

Grading Plan

SITE ADDRESS 335 Tim Sale Dr

DRAWING NO. **J.22-A3**

BID OPPORTUNITY NO. **1028-2024**

06-01-23 Template.mcd Monday, January 23, 2006