

NOTES :

CONSTRUCTION STANDARDS

TO BE CONSTRUCTED IN ACCORDANCE WITH MANITOBA HYDRO DISTRIBUTION AND SUBTRANSMISSION STANDARDS, LATEST EDITION.
NO MAJOR CHANGE SHALL BE MADE WITHOUT APPROVAL OF THE DESIGN ENGINEER OR DELEGATE.

REMOVED			
Quantity	Fixture Type	Wattage	Pole Type
38	LED	150	EXCLUSIVE
	LED	60	SHARED
1	LED	240	EXCLUSIVE
1	LED	40	EXCLUSIVE
	LED		SHARED

INSTALLED			
Quantity	Fixture Type	Wattage	Pole Type
1	LED	240	EXCLUSIVE
31	LED	150	EXCLUSIVE
4	LED	60	SHARED
	LED	90	SHARED

CONTACT	NAME	PHONE NUMBER	E-MAIL ADDRESS
DESIGN	DAVID RIBACHUK	204-360-7834	DRIBACHUK@HYDRO.MB.CA
DESIGN ENGINEER	KEVIN VANDENBERGH	431-334-9771	KVANDENBERGH@HYDRO.MB.CA
PORTFOLIO PM	DARIN WACH	204-451-2811	DWACH@HYDRO.MB.CA
ENTRY SERVICE MANAGER	RYAN AUBRY	204-360-7621	RAUBRY@HYDRO.MB.CA
U/G CONSTRUCTION	JEFF BREAKKEY	204-871-2007	JBREAKKEY@HYDRO.MB.CA
O/H CONSTRUCTION	BRYAN SANGSTER	204-489-4801	BSANGSTER@HYDRO.MB.CA
HYDRO GAS			
SHAW/ROGERS			
BELLMTS			
POSTERS REPRESENTATIVE			
DISTRICT ENG TECH	PHILIP BRUCE	204-360-3074	PBRUCE@HYDRO.MB.CA

INSTALL NEW STREET LIGHTS AND CABLE ON ALIGNMENT AS SHOWN.

INSTALL NEW GROUND RODS AS PER CD 50-5

ALL STREET LIGHT CABLE TO BE INSTALLED IN 2" CONDUIT

UPON DISCONNECTION BY MB HYDRO THE CONTRACTOR SHALL INSTALL TEMPORARY #6 OVERHEAD FEED IN ORDER TO MAINTAIN LIGHTING DURING CONSTRUCTION. AT THE END OF CONSTRUCTION TEMPORARY OVERHEAD SHALL BE DISCONNECTED BY THE CONTRACTOR.

U/G SL CABLE TO BE MINIMUM 1.0m AWAY FROM ALL OTHER UTILITIES UNLESS OTHERWISE NOTED

MB HYDRO SHALL CUT, CAP AND ABANDON ORIGINAL FEED TO THE STREET LIGHTS PRIOR TO REMOVAL. ALL FINAL CONNECTIONS WILL BE COMPLETED BY MB HYDRO.


SHEET 2

SHEET 3

KEY MAP

CONTACT "CLICK BEFORE YOU DIG MANITOBA" AT
ClickBeforeYouDigMB.com
THREE FULL WORKING DAYS
PRIOR TO CONSTRUCTION FOR LOCATION OF
WATER, WASTEWATER, LAND DRAINAGE UTILITIES AND
MANITOBA HYDRO UTILITIES

**PRELIMINARY NOT TO
BY USED FOR
CONSTRUCTION**



NO.	DATE	REVISIONS	BY	CHKD.	APP.	AREA
						4901, 5202
						MANITOBA HYDRO DISTRIBUTION ENGINEERING WO# P:39874 NETWORK # 4308417
						STATION NUMBER N/A
						FEEDER NUMBER N/A
						CSC: CITY CENTRE COW - INKSTER BLVD (EB SINCLAIR TO MAIN) CUSTOMER SERVICE PROJECT
						SALVAGE 38-35' 150 W LED STREET LIGHTS AND INSTALL 31-35' 150 W LED STREET LIGHTS
						SYSTEM VOLTAGE 120 V
						SCALE 1:200
						DATE 2024 04 XX
						1-04707-DE-50000-0648
						SHT. 01/03
						REV. 00

B1 SIZE - 1000 x 707