



162-2024 ADDENDUM 1

2024 WATER MAIN RENEWALS – CONTRACT 6

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL

ISSUED: 2024-03-28
BY: N. Kehler
TELEPHONE NO. 204 226-1008

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: Add 2024-02-01

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

FORM B: PRICES

Replace: 162-2024 Form B: Prices with 162-2024 Addendum 1 - Form B: Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R1): Revise unit for Item No. A.18(a).

PART B – BIDDING PROCEDURES

Revise: B2.1 The Submission Deadline is 12:00 noon Winnipeg time, April 5, 2024.

PART E – SPECIFICATIONS

Add: E8.12 Submittals

Add: E8.12.1 Submit proposed construction equipment specifications to the Contract Administrator for review a minimum of five (5) Business Days prior to construction. The equipment submission shall include:

- (a) equipment operating and payload weights;
- (b) equipment dimensions, including wheel or track base, track length or axle spacing, track widths or wheel configurations; and
- (c) load distributions in the intended operating configuration.

Add: E8.12.2 Submit a construction method statement to the Contract Administrator a minimum of five (5) business days prior to construction. The construction method statement shall contain the following minimum information:

- (a) proposed construction plan including excavation locations, haul routes, excavation equipment locations, and loading positions;

- (b) excavation plans, including shoring designs, for excavations occurring in close proximity to feeder mains (within 5 m horizontal of the pipe's centerline) where the excavation/shoring system is to be extended below the top of the feeder mains embedment zone (150 mm above the pipe); and,
- (c) any other pertinent information required to accurately describe the construction activities in close proximity to the feeder main and permit the Contract Administrator to review the proposed construction plans.

Revise: E16.3.3

Notwithstanding E16.3.1 and E17.3.1, temporary restoration for areas identified in E16.3.2 shall be completed using compacted granular backfill to grade. Temporary concrete and landscaping are not required.

QUESTIONS AND ANSWERS

Q1: The south side of Inkster is to be completed as temporary restoration only. What about the landscaping? Does Top Soil & Sod need to be allowed for on the south Blvd? How about the centre Blvd (where water services are being renewed to the N. P/L)?

A1: For everything south of median centerline, only temporary restoration is required using flood-tamped granular to grade (refer to E16.3). Temporary concrete and landscaping are not required. The intent is that finished areas are left tidy, safe, and passable for pedestrians. Permanent restoration will be completed by the road works contractor under 155-2024.

For everything north of median centerline, full permanent restoration is required including pavement slabs, sidewalk slabs, and landscaping. This includes the north half of the center median, westbound traffic lanes, north boulevard and north sidewalk of Inkster Blvd and any cross streets.