ELECTRICAL SITE PLAN
SCALE: 1:100

NOTES:

1. CONTRACTOR TO DEMOLISH EXISTING TELEPHONE LINE TO BUILDING AND CUSTOMER OWNED UTILITY SERVICE EQUIPMENT. CONTRACTOR TO COORDINATE SHUTDOWNS WITH MANITOBA HYDRO AND TELECOMM PROVIDER.
2. EXISTING COMBINED SEWER OUTFALL (CSO) MONITORING EQUIPMENT TO REMAIN. CONTRACTOR TO RELOCATE CSO MONITORING EQUIPMENT TO MAINTAIN OPERATION DURING CONSTRUCTION AS NEEDED. CONTRACTOR TO DEVELOP A CONTINUED SERVICE PLAN FOR THE CSO EQUIPMENT IN COORDINATION WITH THE CITY AND CONTRACT ADMINISTRATOR.
3. SEE AUTOMATION DRAWINGS FOR BELOW-GRADE CSO INSTRUMENT LOCATIONS.

THE INFORMATION CONTAINED IN THESE DRAWINGS SHALL BE ORIENTED IN THE SAME DATUM AS THE GIS, NAD 1983 JUNE 1990.

NO.	DRAWING NUMBER	REFERENCE DRAWING TITLE
10		
9		
8		
7		
6		
5		
4		
3		
2		
1	1-0131L-A0001	AUTOMATION DEMOLITION PLAN

REFERENCE DRAWINGS

0 2000 4000 6000 8000 10000
SCALE: 1:100

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES
UNLESS OTHERWISE NOTED

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
MPE, a division of Englobe Corp.
No. 4968 Date: MAR 19, 2024

B.M.
ELEV.

NO.	REVISIONS	DATE	BY
0	ISSUED FOR DEMOLITION	2024-03-19	

MPE a division of Englobe

DESIGNED BY	J. SWAIN	CHECKED BY	R. OFSTIE
DRAWN BY	J. SWAIN, T. SHRUFI	APPROVED BY	R. OFSTIE
SCALE: HORIZONTAL VERTICAL	1:100	RELEASED FOR CONSTRUCTION	
DATE	2024-03-19	DATE	

PLOT DATE: 2024 03 19

PROVINCE OF MANITOBA
R.G. OFSTIE
Member 44405
REGISTERED PROFESSIONAL ENGINEER
MARCH 21, 2024
CONSULTANT DRAWING NUMBER

BID OPPORTUNITY: --

Winnipeg
THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

CONWAY LIFT PUMPING STATION
2024 UPGRADES
ELECTRICAL SITE PLAN
PLANS AND SECTIONS
DEMOLITION

CITY DRAWING NUMBER 1-0131L-E0002-001-00 SHEET 43 OF 102

FILE PATH: M:\N-Data\84\00 City of Winnipeg\005 - Conway Lift Station\Autodesk\ACAD\
FILE NAME: E1.2 ELECTRICAL DEMO SITE PLAN.dwg