B REF.1,2 LIFT STATION SECTION LOOKING WEST
SCALE: 1:25

C REF.1,2 LIFT STATION SECTION LOOKING NORTH
SCALE: 1:25

GENERAL NOTES:

1. PERFORM WORK IN ACCORDANCE WITH ALL APPLICABLE CODES AND REGULATION.
2. EQUIPMENT LOCATIONS AND PIPE ROUTING IN THE DRAWING IS APPROXIMATE ONLY. CONFIRM ALL LOCATIONS IN THE FIELD. LISTED DIMENSIONS ARE APPROXIMATE AND ARE ONLY INTENDED FOR BIDDING PURPOSES. THE CONTRACTOR IS RESPONSIBLE TO VERIFY ALL DIMENSIONS AND ROUTING IN THE FIELD FOR ORDERING EQUIPMENT AND COMMENCING INSTALLATION WITHOUT EXTRA CHARGES TO THE PROJECT.
3. CONTRACTOR TO ENSURE PIPES ARE ADEQUATELY SUPPORTED AGAINST MOVEMENT PRIOR TO PRESSURIZATION.
4. ALL EQUIPMENT SHOWN ON THIS DRAWING IS NEW AND IS TO BE PROVIDED BY THE CONTRACTOR UNLESS OTHERWISE INDICATED AS EXISTING.

KEY NOTES:

1. INSTALL SHAFT GUARD SUPPLIED WITH PUMP SHAFT OR PROVIDE SHAFT MACHINE GUARDS IN ACCORDANCE WITH CSA Z432, SAFE GUARDING OF MACHINERY. GUARD PAINT FINISH SHALL BE SAFETY YELLOW.
2. SUPPLY AND INSTALL MAGNETIC FLOW METER IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS AND WITH A MINIMUM OF 5 PIPE DIAMETERS UPSTREAM AND 3 PIPE DIAMETERS DOWN STREAM OF STRAIGHT PIPE.
3. SUPPLY AND INSTALL GATE VALVE WITH MANUAL OPERATOR 875mm ABOVE THE FLOOR LEVEL.
4. FABRICATED STEEL MOTOR STAND SUPPLIED WITH PUMP TO BE BOLTED DIRECTLY TO HOUSEKEEPING PAD. PROVIDE ANCHOR BOLT DETAILS TO ENGINEER FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION.

THE INFORMATION CONTAINED IN THESE DRAWINGS SHALL BE ORIENTED IN THE SAME DATUM AS THE GIS, NAD 1983 JUNE 1990.

NO.	DRAWING NUMBER	REFERENCE DRAWING TITLE
10		
9		
8		
7		
6		
5		
4		
3	1-0131L-M0011-001-00	TYPICAL MECHANICAL DETAILS, PIPE SUPPORTS, SEAL WATER
2	1-0131L-M0006-001-00	MOTOR & PUMP ROOM HVAC & PLUMBING PLAN
1	1-0131L-M0005-001-00	MOTOR & PUMP ROOM PROCESS PIPING PLAN

REFERENCE DRAWINGS

0 500 1000 1500 2000 2500
SCALE: 1:25

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES
UNLESS OTHERWISE NOTED

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
MPE, a division of Englobe Corp.
No. 4968 Date: MAR 22, 2024

B.M.
ELEV.

NO.	REVISIONS	DATE	BY
0	ISSUED FOR CONSTRUCTION	2024-03-22	

MPE a division of Englobe

DESIGNED BY	P. NAYAK	CHECKED BY	P. GOERTZEN
DRAWN BY	D. MCMILLAN	APPROVED BY	P. GOERTZEN
SCALE: HORIZONTAL	AS SHOWN	RELEASED FOR CONSTRUCTION	
VERTICAL			
DATE	2024-03-19	DATE	

PLOT DATE: 2024 03 22

PROVINCE OF MANITOBA P.P. GOERTZEN Member 43822 REGISTERED PROFESSIONAL ENGINEER
MARCH 22, 2024
CONSULTANT DRAWING NUMBER

BID OPPORTUNITY: --

Winnipeg
THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

CONWAY LIFT PUMPING STATION
2024 UPGRADES
MECHANICAL PLAN
PLANS AND SECTIONS
PROCESS & MECHANICAL SECTION 2

CITY DRAWING NUMBER 1-0131L-M0009-001-00 | SHEET 37 OF 102

FILE PATH: M:\N-Data\84\00 City of Winnipeg\005 - Conway Lift Station\Autodesk\ACAD\
FILE NAME: M1.9-MECHANICAL SECTION.dwg