



WATER SERVICE INFORMATION					
ADDRESS	PIPE SIZE & MATERIAL (STREET)	PIPE SIZE & MATERIAL (PROPERTY)	STOP COCK LOCATION SHORT & LONG MEASUREMENT	CORP. LOCATION	REMARKS
619 ARLINGTON ST	20 CU	20 LEAD	11' SNHL & 258' SSL SARGENT AV	7.5' S SC	RECONNECT SERVICE
621 ARLINGTON ST	12 CU	20 CU	8' NSHL & 229' SSL SARGENT AV	2' S SC	RECONNECT SERVICE
623 ARLINGTON ST	12 CU	12 LEAD	5' NSHL & 204' SSL SARGENT AV	1' N SC	RECONNECT SERVICE
625 ARLINGTON ST	20 CU	20 CU	14' SNHL & 176' SSL SARGENT AV	OPP SC	RECONNECT SERVICE
627 ARLINGTON ST	20 CU	20 CU	10.5' NSHL & 140' SSL SARGENT AV	OPP SC	RECONNECT SERVICE
* 628 ARLINGTON ST		12 LEAD	3.5' NSHL & 248' SSL SARGENT AV	241' SSL SARGENT AV	RENEW TO PL W/20 CU WYED W/630 (SEPARATE SERVICES)
* 630 ARLINGTON ST		12 LEAD	1.5' SSSL & 248' SSL SARGENT AV	7' N SC	RENEW TO PL W/20 CU WYED W/628 (SEPARATE SERVICES)
632 ARLINGTON ST	20 CU	12 LEAD	OPP NL S WINDOW & 218' SSL SARGENT AV	OPP SC	RECONNECT SERVICE
* 634 ARLINGTON ST		12 LEAD	OPP NHL & 176' SSL SARGENT AV	OPP SC	RENEW TO PL W/20 CU WYED W/636 (SEPARATE SERVICES)
* 636 ARLINGTON ST		12 LEAD	OPP NHL #634 & 176' SSL SARGENT AV	OPP SC	RENEW TO PL W/20 CU WYED W/634 (SEPARATE SERVICES)
638 ARLINGTON ST	20 CU	20 CU	13' SNHL & 134' SSL SARGENT AV	OPP SC	RECONNECT SERVICE
* 796 SARGENT AV		12 LEAD	6.3' NSBL & 45.5' SSL SARGENT AV	43' SSL SARGENT AV	RENEW TO PL W/20 CU WYED W/MULTIPLE SERVICES (SEPARATE SERVICES)
795, 797 SARGENT AVE	16 LEAD	12 LEAD	6.2' SNL HOUSE 797 & 44.5' NNL SARGENT AVE	4.0' N CS	OUTSIDE LIMITS
* 798 SARGENT AV		12 LEAD	5' NSBL & 46.6' SSL SARGENT AV	43' SSL SARGENT AV	RENEW TO PL W/20 CU WYED W/MULTIPLE SERVICES (SEPARATE SERVICES)
801A SARGENT AVE	25 CU	20 CU	2.5m NSBL & 4.5m NSL SARGENT AVE	1.9m S S/C	OUTSIDE LIMITS

\* SERVICES TO BE RENEWED TO PL

BENCHMARK: 37-031  
 ELEV=232.472m  
 N.E. COR. ST. MATTHEWS AVE. & SIMCOE ST., TBLT. IN S. CONC.  
 FOUNDATION NO. 345 SIMCOE ST., 0.5m E. & 1m BELOW TYNDALL  
 STONE OF S.W. COR. OF BLDG.

NOTE: CHAINAGES SHOWN ARE ALONG CENTERLINE OF ROW

NOTE: VALVES TO BE INSTALLED COUNTER-CLOCKWISE TO CLOSE

FOR INDEX SEE D-16994

METRIC  
 WHOLE NUMBERS INDICATE MILLIMETRES  
 DECIMALIZED NUMBERS INDICATE METRES

0.0 5.0 10.0 15.0 20.0 25.0

**ENGINEERS**  
**GEOSCIENTISTS**  
**MANITOBA**

Certificate of Authorization  
 Stantec Consulting Ltd.  
 No. 1301

LOCATION APPROVED  
 UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE DATE

NOTE:  
 LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

VERTICAL DATUM: CGVD28 (HT2.0 Geoid)  
 HORIZONTAL DATUM: NAD83 (June 1990), Zone 14

00	ISSUED FOR TENDER	2024.04.18	RS
NO.	REVISIONS	DATE	BY

**Stantec**

DESIGNED BY: RS  
 CHECKED BY: WB  
 DRAWN BY: LA  
 APPROVED BY: RS  
 SCALE: HORIZONTAL 1:250  
 VERTICAL 1:50  
 DATE: 2024.04.18  
 RELEASED FOR CONSTRUCTION: SC  
 DATE: 2024.04.18

PLOT DATE: 2024 04 18

ENGINEER'S SEAL

CONSULTANT DRAWING NUMBER  
**C-213**

TENDER NUMBER: 194-2024

**THE CITY OF WINNIPEG**  
 WATER AND WASTE DEPARTMENT  
 ENGINEERING DIVISION

2024 WATER MAIN RENEWALS  
 CONTRACT 9  
**ARLINGTON STREET**  
 79.0 S OF SARGENT AVENUE TO  
 9.8 S OF SARGENT AVENUE

SHEET 15 OF 15  
 CITY DRAWING NUMBER  
**D-17007**

FILE PATH: u:\111220853\0300\_drawing\0302\_sheet\_files\02\_civil\20853c-210