





NOTES:

- 1. ALL UTILITIES SHOWN ON DRAWINGS ARE APPROXIMATE ONLY. LOCATIONS OF ALL UTILITIES TO BE CONFIRMED IN FIELD BY THE CONTRACTOR.
- 2. ALL UNDERGROUND AND SURFACE WORKS TO BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST REVISION OF THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS EXCEPT WHERE OTHERWISE NOTED IN THE PROJECT SPECIFICATIONS.
- 3. INSTALL FEEDER MAIN BY OPEN CUT METHODS, UNLESS OTHERWISE NOTED OR OTHERWISE APPROVED BY THE CONTRACT ADMINISTRATOR.
- 4. TEMPORARY SUPPORTING OF EXISTING UTILITIES TO FACILITATE EXCAVATION OR SHAFT CONSTRUCTION WILL BE CONSIDERED INCIDENTAL TO THE PIPE INSTALLATION, AS DESCRIBED IN THE SPECIFICATIONS.
- 5. INSTALL TRACER WIRE ON ALL FEEDER MAIN PIPING. INSTALL ACCESS PORTS AT ALL HORIZONTAL BENDS AS PER SPECIFICATION SECTION E28.
- 6. THE EXISTING GROUND ELEVATIONS SHOWN ON THE DRAWINGS ARE BASED ON LIDAR DATA OBTAINED NOV 2020.
- 7. THE ELEVATIONS OF BEDROCK AND TILL SHOWN ON THE DRAWING ARE APPROXIMATE ONLY AND SHOULD NOT BE INTERPRETED AS EXACT LINES OF CHANGE IN STRATIGRAPHY. SUBSURFACE CONDITIONS AT THE SITE MAY DIFFER FROM THE CONDITIONS SHOWN ON THE DRAWING. PLEASE REFER TO THE GEOTECHNICAL DATA REPORT (GDR) FOR LIMITATIONS OF THE GEOTECHNICAL INFORMATION OBTAINED FROM BOREHOLE DRILLING AND GEOPHYSICAL SEISMIC REFRACTION METHOD.
- 8. CONTRACTOR TO REFERENCE THE GEOTECHNICAL BASELINE REPORT (GBR) FOR A DESCRIPTION OF THE ANTICIPATED SUBSURFACE CONDITIONS ALONG THE FEEDER MAIN ALIGNMENT.
- 9. INSTALL ALL PIPING TO GRADES SHOWN. ENSURE MINIMUM 2.5m COVER OR PROVIDE INSULATION AS DIRECTED BY THE CONTRACT ADMINISTRATOR.
- 10. CONTRACTOR TO RESTORE SITE TO PRE-CONSTRUCTION CONDITION FOLLOWING COMPLETION OF CONSTRUCTION.



LIMITS OF TREE CLEARING COMPLETED AS PART OF TENDER 109-2024



LIMITS OF TEMPORARY CONSTRUCTION EASEMENT. COORDINATE ACCESS WITH CONTRACT ADMINISTRATOR

KGS GROUP IS NOT RESPONSIBLE FOR ANY CLAIMS, DAMAGES, OR LIABILITY ASSOCIATED WITH INTERPRETATION OF SUBSURFACE DATA OR FOR REUSE OF SUBSURFACE DATA.



KGS Group

No. 245

FOR INDEX SEE -0798F-D0002-001

> METRIC WHOLE NUMBERS INDICATE MILLIMETRES DECIMALIZED NUMBERS INDICATE METRES

20.0 30.0 40.0m SCALE: 1:500m (A1)

PROPERTY LIMITS DELINEATION

THOSE PROPERTY LIMITS.

DELINEATION OF PROPERTY LIMITS AS SHOWN ON THIS DWG DOES NOT REPRESENT A "LEGA SURVEY". KGS GROUP MAKES NO REPRESENTATION OR WARRANTY AS TO THE ACCURACY OF PROPERTY LIMITS DELINEATED ON THIS DWG, NOR ON THE DIMENSIONAL ACCURAC OF DWG FEATURES RELATIVE TO

WARNING

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:

1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION. 2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.

SEE PROVINCIAL REGULATION 210/72 FOR DETAILS

SUPV. U/G STRUCTURES COMMITTEE DATE NOTE: LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

LOCATION APPROVED

UNDERGROUND STRUCTURES

VERTICAL DATUM: CGVD28 (HT2.0 Geoid) KGS HORIZONTAL DATUM: NAD83 (June 1990), Zone 14 DESIGNED CHECKED DRAWN APPROVED SCALE: RELEASED FOR ISSUED WITH ADDENDUM 2 24/05/13 HORIZONTAL 1:500 ISSUED FOR TENDER 1:50 24/04/26 GTH VERTICAL DATE 2024 05 13 DATE YYYY/MM/DD

ENGINEER'S SEAL HEINRICHS Member 38162 CONSULTANT DRAWING NUMBER

Winnipèg

THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT ENGINEERING DIVISION

CENTREPORT SOUTH REGIONAL WATER AND WASTEWATER SHEET 7 OF 34 SERVICING - PHASE 1A CONTRACT 4A - FEEDER MAIN CITY DRAWING NUMBER

STURGEON ROAD ATHLETIC FIELD 1-0798F-C0008-001 STA 1+750 TO STA 2+000

BID OPP: 220-2024 CONTRACT NUMBER: 4A

C-4A-104

FILE PATH: U:\FMS\23-0107-009\
FILE NAME: 23-0107-009_C4A_Feedermain_CALL.dwg