





NOTES:

- 1. ALL UTILITIES SHOWN ON DRAWINGS ARE APPROXIMATE ONLY. LOCATIONS OF ALL UTILITIES TO BE CONFIRMED IN FIELD BY THE CONTRACTOR.
- ALL UNDERGROUND AND SURFACE WORKS TO BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST REVISION OF THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS EXCEPT WHERE OTHERWISE NOTED IN THE PROJECT SPECIFICATIONS.
- 3. INSTALL FEEDER MAIN BY OPEN CUT METHODS, UNLESS OTHERWISE NOTED OR OTHERWISE APPROVED BY THE CONTRACT ADMINISTRATOR.
- 4. TEMPORARY SUPPORTING OF EXISTING UTILITIES TO FACILITATE EXCAVATION OR SHAFT CONSTRUCTION WILL BE CONSIDERED INCIDENTAL TO THE PIPE INSTALLATION, AS DESCRIBED IN THE SPECIFICATIONS.
- INSTALL TRACER WIRE ON ALL FEEDER MAIN PIPING. INSTALL ACCESS PORTS AT ALL HORIZONTAL BENDS AS PER SPECIFICATION SECTION E28.
- 6. THE EXISTING GROUND ELEVATIONS SHOWN ON THE DRAWINGS ARE BASED ON LIDAR DATA OBTAINED NOV 2020.
- 7. THE ELEVATIONS OF BEDROCK AND TILL SHOWN ON THE DRAWING ARE APPROXIMATE ONLY AND SHOULD NOT BE INTERPRETED AS EXACT LINES OF CHANGE IN STRATIGRAPHY. SUBSURFACE CONDITIONS AT THE SITE MAY DIFFER FROM THE CONDITIONS SHOWN ON THE DRAWING. PLEASE REFER TO THE GEOTECHNICAL DATA REPORT (GDR) FOR LIMITATIONS OF THE GEOTECHNICAL INFORMATION OBTAINED FROM BOREHOLE DRILLING AND GEOPHYSICAL SEISMIC REFRACTION METHOD.
- 8. CONTRACTOR TO REFERENCE THE GEOTECHNICAL BASELINE REPORT (GBR) FOR A DESCRIPTION OF THE ANTICIPATED SUBSURFACE CONDITIONS ALONG THE FEEDER MAIN ALIGNMENT.
- 9. INSTALL ALL PIPING TO GRADES SHOWN. ENSURE MINIMUM 2.5m COVER OR PROVIDE INSULATION AS DIRECTED BY THE CONTRACT ADMINISTRATOR.
- CONTRACTOR TO RESTORE SITE TO PRE—CONSTRUCTION CONDITION FOLLOWING COMPLETION OF CONSTRUCTION.

KGS GROUP IS NOT RESPONSIBLE FOR ANY CLAIMS, DAMAGES, OR LIABILITY ASSOCIATED WITH INTERPRETATION OF SUBSURFACE DATA OR FOR REUSE OF SUBSURFACE DATA.





THE CITY OF WINNIPEG

WATER AND WASTE DEPARTMENT

ENGINEERING DIVISION

FOR INDEX SEE 1-0798F-D0002-001

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

0 10.0 20.0 30.0 40.0m SCALE: 1: 500m (A1)

PROPERTY LIMITS DELINEATION

DELINEATION

DELINEATION OF PROPERTY
LIMITS AS SHOWN ON THIS DWG
DOES NOT REPRESENT A "LEGAL
SURVEY". KGS GROUP MAKES
NO REPRESENTATION OR

IF POWER EQUIPMENT OR EXPLOSIVES
ARE TO BE USED FOR EXCAVATION ON
THIS PROJECT THE CONTRACTOR MUST:

1) NOTIFY THE GAS COMPANY OF THE
PROPOSED LOCATION OF EXCAVATION.

WARRANTY AS TO THE
ACCURACY OF PROPERTY LIMITS
DELINEATED ON THIS DWG, NOR
ON THE DIMENSIONAL ACCURACY
OF DWG FEATURES RELATIVE TO
THOSE PROPERTY LIMITS.

PROPOSED LOCATION OF EXCAVATION.

PROPOSED LOCATION OF EXCAVATION.

PROPOSED LOCATION OF EXCAVATION.

SEE PROVINCIAL REGULATION 210/72 FOR DETAILS

WARNING

LOCATION APPROVED UNDERGROUND STRUCTURES

VERTICAL DATUM: CGVD28 (HT2.0 Geoid)

SUPV. U/G STRUCTURES DATE
COMMITTEE

NOTE:

LOCATION OF UNDERGROUND STRUCTURES AS
SHOWN ARE BASED ON THE BEST INFORMATION
AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL
EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN
LOCATIONS ARE EXACT. CONFIRMATION OF
EXISTENCE AND EXACT LOCATION OF ALL
SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL
UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

KGS HORIZONTAL DATUM: NAD83 (June 1990), Zone 14 DESIGNED CHECKED APPROVED ZBC DRAWN SCALE: RELEASED FOR CONSTRUCTION ISSUED WITH ADDENDUM 2 24/05/13 HORIZONTAL 1:500 1:50 ISSUED FOR TENDER 24/04/26 GTH VERTICAL DATE 2024 05 13 DATE YYYY/MM/DD



C-4A-112

BID OPP: 220-2024 CONTRACT NUMBER: 4A

Winnipeg

CENTREPORT SOUT

SERVICING - PHA

CENTREPORT SOUTH REGIONAL WATER AND WASTEWATER SHEET 15 OF 34
SERVICING — PHASE 1A CONTRACT 4A — FEEDER MAIN CITY DRAWING NUMBER

STURGEON ROAD NORTH

STA 2+990 TO STA 3+255

13434

FILE PATH: U:\FMS\23-0107-009\
FILE NAME: 23-0107-009_C4A_Feedermain_CALL.dwg