



Tender 220-2024 ADDENDUM 5

CENTREPORT SOUTH REGIONAL WATER AND WASTEWATER SERVING – PHASE 1A CONTRACT 4A FEEDER MAIN

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: May 17, 2024
BY: Tristan Eldridge
TELEPHONE NO. 204 896 1209

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2024-02-01

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

FORM B: PRICES

Replace: Tender 220-2024 Form B: Prices with Tender 220-2024 Addendum 5 - Form B: Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R3): Corrected calculation error in cell H123

Page numbering on some forms may be changed as a result.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read The Submission Deadline is 12:00 noon Winnipeg time, **May 23, 2024.**

QUESTIONS AND ANSWERS

Q1: What is the intention of the Form B Item Supply of Fittings (A7) and Installation of Fittings (D4)?

A1: Form B Item A7 is intended to cover the supply cost of any additional large diameter fittings that may be required during the course of construction. This is to minimize any delays or down time for ordering additional fittings. All fittings listed in Item A7 shall be supplied and delivered to site. If the fittings are required during construction, the cost to install the fittings, including thrust blocks, valve boxes for tracer wire etc. shall be paid under Item D4. If some or all of the fittings listed under Item A7 are not required, the City will still pay the supply cost of all remaining fittings listed in A7 and take the fittings into their inventory.

Q2: Form B Item C3 (b) does not calculate a total amount, is this intentional?

A2: Yes, as per Specification E16, Item C3 (b) is intended for evaluation purposes only, and will not be included in the Total Bid Price.

Q3: Specification E33.2 (b) Subsurface Monitoring Points – indicates to install settlement rods 1.0m above obvert of pipe casing. However, based on the GDR, bedrock is likely present. Is the intent to drill these rods through bedrock to 1.0m above obvert of pipe casing?

A3: For bidding purposes, assume the installation of sub-surface settlement rods to 1.0m above the pipe obvert even if this is in bedrock.

Q4: Please clarify whether mechanical restraints are required for the steel encased feeder main pipe within the open cut section of Sturgeon Road.

A4: Mechanical restraints are not required for the steel encased feeder main pipe within the open cut section of Sturgeon Road, only for the encased CPKC Railway Crossing.