


ACCESSIBLE ELEVATED PLATFORM ENTRY

**MATERIAL NOTES**

1. ALL WORK TO CONFORM TO CURRENT CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS AND DETAILS UNLESS OTHERWISE NOTED.
2. DIMENSIONS ARE IN METERS UNLESS OTHERWISE NOTED.
3. DO NOT SCALE DRAWING.
4. PROTECT EXISTING TREES TO REMAIN, TYP.

**LEGEND**

- 1 NEW AGES 2-5 PLAY EQUIPMENT
- 2 NEW 8' TALL 2 BAY SWING SET C/W 2 BUCKET AND 2 BELT SWINGS
- 3 NEW ENGINEERED WOOD FIBRE SAFETY SURFACING C/W MANUFACTURER'S SPECIFIED DRAINAGE SYSTEM AS PER SCD-650 (HATCHED AREA, 252SM)
- 4 SUPPLY AND INSTALL SUBSURFACE DRAINAGE PIPE TO CATCH BASIN AS PER SCD 661 AND DETAIL 1/J.24-A4 (8LM). DRAINAGE LINE SHOWN FOR REFERENCE, BIDDER TO DETERMINE ROUTE OF SUBSURFACE DRAINAGE
- 5 NEW 2-TIER (13LM) AND 3-TIER (12LM) TIMBER EDGING AS PER SCD-651A. EXTENTS AS PER LAYOUT PLAN
- 6 NEW 4-TIER (7LM), 5-TIER (7LM) AND 6-TIER (28LM) TIMBER RETAINING WALL AS PER DETAIL 2/J.24-A8 AND DETAIL 1/J.24-A6. EXTENTS AS PER LAYOUT PLAN
- 7 SUPPLY & INSTALL ASPHALT PATHWAYS (75TONNE) C/W SEPARATION GEOTEXTILE (345SM), SUB-BASE (150TONNE), AND BASE COURSE (20CM) AS PER SCD-648
- 8 SECTION OF ASPHALT PAVING W/ COMBIGRID REINFORCEMENT AS PER DETAIL 1/J.24-A8 (DARK GREY, 55 SM)
- 9 SUPPLY AND INSTALL TOPSOIL AND SOD (GREEN AREA, 470SM)
- 10 SUPPLY AND INSTALL BAFFLE GATE AS PER SCD-633 (1)
- 11 SUPPLY AND INSTALL BACKED BENCH AS PER SCD-121A (1)
- 12 SUPPLY AND INSTALL BACKLESS BENCH AS PER SCD-121C (1)
- 13 SUPPLY AND INSTALL ACCESSIBLE PICNIC TABLE AS PER SCD-122A (1)
- 14 SUPPLY AND INSTALL NEW PARK SIGN AS PER SCD-153 (1)
- 15 SUPPLY AND INSTALL WASTE RECEPTACLE AS PER SCD-119 (1)
- ➡ ACCESSIBLE ENTRY AS PER SCD-651C (1)
- ➡ **APPROXIMATE LOCATION OF ACCESSIBLE ELEVATED PLATFORM ENTRY TO PLAY STRUCTURE (DETAIL 1/J.24-A5 & DETAIL 3/J.24-A5). EXACT LOCATION OF PLATFORM ENTRY WITHIN THE LANDING AREA TO BE DETERMINED BY BIDDER**



CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.



THE CITY OF WINNIPEG  
 Planning, Property and Development Department  
 Planning and Land Use Division  
 Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

DESIGNED BY	DL	CHECKED BY	
DRAWN BY	DL	APPROVED BY	
HORIZ. SCALE	1:275		
VERT. SCALE			
DATE	MARCH 2024		

MANAGER, PARK AND OPEN SPACES	DATE
MANAGER, PLANNING AND LAND USE DIVISION	DATE

DRAWING TITLE	DRAWING NO.
<b>John Steel Park Playground Redevelopment PLAYGROUND MATERIALS PLAN</b>	<b>J.24-A2</b>
SITE ADDRESS <b>300 Westwood Drive</b>	BID OPPORTUNITY NO. <b>245-2024</b>