

ASSET NUMBER	STREET	LOCATION DESCRIPTION	FLOW TYPE	WORK NAME TYPE	EST COST	COMMENTS	HEIGHT	WIDTH	ASSET LENGTH	REPAIR LENGTH
S-MA20012461	ALEXANDER AV	MH AT KEEWATIN ST TO 1ST MH W OF KEEWATIN ST	WWS	ABANDON	\$2,000	distance is approximate. install manhole and abandon section of pipe from Keewatin to lane	250	250	79.2	43.2
S-MA20012461	ALEXANDER AV	MH AT KEEWATIN ST TO 1ST MH W OF KEEWATIN ST	WWS	INSTALL MANHOLE	\$30,000	distance is approximate. install manhole and abandon the pipe from Keewatin to lane.	250	250	79.2	
S-MA00015014	ANDREWS ST (CL)	MH AT COLLEGE AV TO EOP	LDS	EXTERNAL PT REPAIR	\$21,500	After new MH has been installed, conduct EPR to relocate crossbored water service from 530 College Ave	300	300	40.3	3.0
S-MA00015014	ANDREWS ST (CL)	MH AT COLLEGE AV TO EOP	LDS	INSTALL MANHOLE	\$30,000	Install MH to allow for future lining - Also conduct EPR after MH is installed to relocate crossbored water service from 530 College Ave	300	300	40.3	
S-MA00006152	BACHMAN BY (\$ LEG)(\$ BV)	MH AT BACHMAN BY E LEG TO 1ST MH E OF ARGATE DR	WWS	EXTERNAL PT REPAIR	\$16,500	Hole with voiding	250	250	115.6	3.0
S-MA70054886	BORROWMAN PL	1ST MH S OF PORTAGE AV TO PLUG S OF MH70024566	CS	EXTERNAL PT REPAIR	\$34,000	SAP, SAM, HSV, FM, FL -- CHANGED FROM FSL TO FSR AS D&C NOTED IT CAN'T BE LINED WITHOUT AN U/S MH. ASSET IS SHORT ENOUGH TO JUST RENEW THE WHOLE ASSET AS OPPOSED TO A SHORTER EPR -- ADDED TO 2024 CSP NOW	300	300	5.6	4.5
S-MA70122074	CHESTERFIELD AVE.(N.PL)	1ST MH W.OF DAKOTA ST. TO MH AT DAKOTA ST.	WWS	EXTERNAL PT REPAIR	\$23,500	Open joint, HSV, dip in pipe	250	250	96.6	2.5
S-MA70001504	DAWSON RD N	2ND MH NW OF DUDALD RD TO 3RD MH NW OF DUGALD RD	CS	STABILIZATION	\$33,800	BRICK LINED CONCRETE SEWER. SOME AREAS OF MISSING BRICKS -- SHORT SECTION OF SEWER COULD STABILIZE ADDING BRICKS WHERE MISSING OR GROUT AREAS WITH MISSING BRICKS	2750	1825	5.9	6.1
S-MA40002379	EASEMENT W.OF ROCH ST.	1ST MH N.OF DEVON AV. TO MH AT DEVON AV.	CS	EXTERNAL PT REPAIR	\$16,500	HVV - SEPARATION OF PIPE SEGMENTS	250	250	50.2	2.7
S-MA70125153	EASEMENT(E.OF OSBORNE ST N)	1ST MH N OF BROADWAY TO 2ND MH N OF BROADWAY	CS	FULL SEGMENT RENEWAL	\$176,800	DR 30%, BSV, FM, CL, SSS	300	300	106.2	106.2
S-MA50005428	ELIZABETH RD (CL)	1ST MH W OF ORMISTON RD TO MH AT ORMISTON RD	CS	EXTERNAL PT REPAIR	\$21,800	Lateral service has pulled away from sewer and is causing voiding around the host pipe	600	600	99.4	2.2
S-MA50005428	ELIZABETH RD (CL)	1ST MH W OF ORMISTON RD TO MH AT ORMISTON RD	CS	EXTERNAL PT REPAIR	\$23,400	Lateral service has pulled away from sewer and is causing voiding around the host pipe	600	600	99.4	3.8
S-MA00008729	ENNISKILLEN AV.	2ND MH W.OF POWERS ST. TO 3RD MH W.OF POWERS ST.	CS	FULL SEGMENT RENEWAL	\$141,800		300	300	98.9	98.9
S-MA70002406	GALLAGHER AV W	MH AT MIDMAR AV TO MH AT KEEWATIN ST (WPL)	WWS	ABANDON	\$2,000	abandon sewer in coordination with sewer relocation from Keewatin to lane	250	250	38.9	38.9
S-MA60021208	GLENGARRY DR. (EASEMENT)	MH AT GLENGARRY DR. TO 1ST MH N.OF GLENGARRY DR.	LDS	EXTERNAL PT REPAIR	\$22,500	HOLE IN THE INVERT WITH VOIDING AND ROOTS VISIBLE AT 33.9M DS.	300	300	42.6	6.3
S-MA60009526	GROSVENOR AV.	MH AT STAFFORD ST. TO 1ST MH E.OF STAFFORD ST.	CS	EXTERNAL PT REPAIR	\$20,500	HOLE AND BROKEN AT TAP	375	375	86.3	0.7
S-MA40006404	HELMSDALE AVE	1ST MH E.OF HENDERSON HWY TO 1ST W.OF HENDERSON HWY	CS	INSTALL MANHOLE	\$30,000	Install MH where pipe begins to bend crossing Henderson Hwy @ approx 38.0m U/S from MH40005874 - to allow for sewer to be lined in the future	250	250	154.5	
S-MA70002423	KEEWATIN ST (W BV)	MH AT GALLAGHER AV W MH AT LOGAN AV	WWS	ABANDON	\$2,000	abandon sewer in coordination with sewer relocation from keewatin to back lane.	250	250	99.6	99.6
S-MA70002423	KEEWATIN ST (W BV)	MH AT GALLAGHER AV W MH AT LOGAN AV	WWS	FULL SEGMENT RENEWAL	\$167,000	to be relocated down back lane. Renewal requested by Wastewater Ops due to basement flooding at 1800 Logan. Wastewater Planning noted - New 250mm PVC sewer at 0.31% grade	250	250	99.6	99.6
S-MA20012494	KEEWATIN ST (WPL)	MH AT LOGAN AV TO MH AT ALEXANDER AV	WWS	ABANDON	\$2,000	to be abandoned in coordination with sewer renewal (new sewer to be installed in the back lane)	250	250	82.4	82.4
S-MA20012494	KEEWATIN ST (WPL)	MH AT LOGAN AV TO MH AT ALEXANDER AV	WWS	FULL SEGMENT RENEWAL	\$143,200	to be relocated down back lane. Renewal requested by Wastewater Ops due to basement flooding at 1800 Logan. Wastewater Planning noted - New 250mm PVC sewer at 0.31% grade	250	250	82.4	82.4
S-MA70016029	LANEWAY(W.OF DOMINION ST)	1ST MH S OF WOLSELEY AV TO TE AT WOLSELEY AV	WWS	FULL SEGMENT RENEWAL	\$142,000	HVV, FC, FL, CC, SAM, SAP, SSC	600	600	54.1	54.1
S-MA70002425	LOGAN AV	4TH MH E OF DEE ST TO MH AT KEEWATIN ST	WWS	ABANDON	\$2,000	to be abandon in coordination with sewer renewal in back lane (relocated from keewatin)	250	250	4.2	4.2
S-MA70002424	LOGAN AV (NPL)	2ND MH W OF KEEWATIN ST TO 1ST MH W OF KEEWATIN ST	WWS	ABANDON	\$2,000	distance is approximate. Abandon sewer section from lane to keewatin in coordination with sewer relocation and manhole install	200	200	96.0	96.0
S-MA70002424	LOGAN AV (NPL)	2ND MH W OF KEEWATIN ST TO 1ST MH W OF KEEWATIN ST	WWS	INSTALL MANHOLE	\$30,000	distance is approximate. install manhole in coordination with sewer renewal (relocated in lane). abandon section from lane to keewatin	200	200	96.0	
S-MA00007908	MAGNUS AV.	1ST MH E.OF LEO NOVAK ST. TO MH AT LEO NOVAK ST.	CS	EXTERNAL PT REPAIR	\$29,000	6.9m EPR (36.9-43.8m DS with 4 Reconnections)	300	300	64.0	6.9
S-MA00001000	MAIN ST.	MH AT BURRIN AVE. TO MH AT SEMPLE AVE.	CS	EXTERNAL PT REPAIR	\$13,500	20% DR, BVEXISTING TPR CHANGED TO EPR	250	250	100.4	0.6
S-MA00016990	MAIN ST. (\$ BOUND)	MH AT FORREST AV. TO MH AT LEILA AV.(CL)	CS	EXTERNAL PT REPAIR	\$15,500	CROSSBORE WATERMAIN 80.7M DS	375	375	87.4	0.6
S-MA00008371	MCADAM AV.	3RD MH E.OF PARR ST. TO 4TH MH E.OF PARR ST.	CS	EXTERNAL PT REPAIR	\$15,000		300		100.0	1.5
S-MA20005903	MOORGATE ST.	1ST MH S.OF NESS AV. TO 2ND MH S.OF NESS AV.	CS	STABILIZATION	\$14,300	SMW AND SAM @ 102.4M DS FROM 3-8 O'CLOCK.	2475	1900	107.3	2.0
S-MA60015898	PEMBINA HWY	MH AT DARTMOUTH DR. TO MH AT MARKHAM RD.	LDS	STABILIZATION	\$14,300	STABILIZATION WORK ORDER IS TO REMOVE CROSS BORED PIPE INSIDE LDS AT APPROX 93 METRES IN D/S DIRECTION. HOUSEFILES FOR 2280 PEMBINA CONFIRMS THIS PIPE IS THE OLD ABANDONED SEWER SERVICE TO THE MONTCLAM HOTEL (NOW DEMOLISHED) CROSS BORE CAN BE CUT OUT INT	1250	1250	161.2	2.0
S-MA60015898	PEMBINA HWY	MH AT DARTMOUTH DR. TO MH AT MARKHAM RD.	LDS	STABILIZATION	\$10,400	HSV AT 9 O'CLOCK	1250	1250	161.2	1.0
S-MA00011324	POLSON AV.	MH AT 1003 POLSON AV. TO MH AT 1015 POLSON AV.	CS	EXTERNAL PT REPAIR	\$18,000	HVV, FM	300	300	26.8	3.7
S-MA00011843	SEMPLA AV.	MH AT POWERS ST. TO 1ST MH W.OF POWERS ST.	CS	FULL SEGMENT RENEWAL	\$155,600	FULL SEGMENT RENEWAL TO ADDRESS FOUR LOCATIONS OF EPR REPAIRS 39.4M TO 40.3M, 47.1M TO 52.6M, 78.8M TO 79.8M, 90.5M TO 92.0M	375	375	101.0	101.0
S-MA00008936	SMITHFIELD ST	MH AT JONES ST TO 1ST MH E JONES ST	WWS	STABILIZATION	\$10,000	H w/ BACKFILL VISIBLE AT MH INTERFACE - PATCH THRU MH - IMAGES AVAILABLE	375	375	85.9	1.5
S-MA00009072	ST. ANTHONY AV.	2ND MH E OF JONES ST.(CL) TO MH AT SCOTIA ST.	WWS	EXTERNAL PT REPAIR	\$23,500	30% DR @ 26.5M WITH HSV, BSV WHERE TWO (2) CN'S TIE IN	300	300	57.1	2.5
S-MA00008598	ST.ANTHONY AV.	MH AT MCKENZIE ST. TO 1ST MH E.OF MCKENZIE ST.	CS	EXTERNAL PT REPAIR	\$57,000	SMW, HSV, MULT FRACTURES, CRACKS, SAP, SAV, SSS, 5-10% DAE	375	375	98.8	30.0
S-MA00011426	WIGINTON ST.	PLUG TO MH AT LANSLOWNE AV.	CS	EXTERNAL PT REPAIR	\$21,000	HSV, H, B, SAM	300	300	10.7	5.1
S-MA60011566	WILTON ST (CL)	MH AT CARTER AV TO PLUG N OF CARTER AV	CS	EXTERNAL PT REPAIR	\$16,000	Pipe collapsed - Need to install MH at high end to allow for inspection of remainder of pipe and to obtain limits for necessary EPR	300	300	33.5	2.0
S-MA60011566	WILTON ST (CL)	MH AT CARTER AV TO PLUG N OF CARTER AV	CS	INSTALL MANHOLE	\$30,000	Install MH at high end to allow for inspection of remainder of pipe and to obtain limits for necessary EPR	300	300	33.5	

\$1,579,900