



# 341-2024 ADDENDUM 1

## 2024 PAVEMENT RENEWALS – ELLICE AVENUE

### URGENT

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL**

ISSUED: May 27, 2024  
BY: Nick Tebinka  
TELEPHONE NO. 204-259-1875

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2024-02-01

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

### FORM B: PRICES

Replace: 341-2024 Form B: Prices with 341-2024 Addendum 1 - Form B: Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R1): Add Items A.7 i), A.8 i), A.9, A.10, A.11.

Revise Items A.12 i) b), A.12 i) c), A.15 i), A.16 i) b), A.16 i) c), A.16 ii)

Page numbering on some forms may be changed as a result.

### PART E – SPECIFICATIONS

Add:	<b>E15.</b>	<b>PORTLAND CEMENT CONCRETE SIDEWALK WITH BLOCK OUTS FOR INDICATOR SURFACES</b>
		DESCRIPTION
	E15.1	This specification shall supplement CW 3325-R5 “Portland Cement Concrete Sidewalks”.
		CONSTRUCTION METHODS
	E15.2	Add the following to section 9 :
	E15.2.1	As shown on the drawings and as directed by the Contract Administrator, construct sidewalk with block outs and/or monolithic curb and sidewalk with block outs, to allow for the installation of indicator surfaces.
	E15.2.2	Verify dimensions of paving stones (indicator surface) prior to construction of the block-outs. Gaps between paving stones and concrete pavement shall not exceed five (5) millimetres.
	E15.2.3	Concrete curbs for monolithic curb and sidewalk with block outs shall be constructed in accordance with CW 3240.
		MEASUREMENT AND PAYMENT
	E15.3	Add the following to section 12 :

- E15.3.1 Construction of concrete sidewalks with block outs for indicator surfaces will be measured on surface area basis. The surface area to be paid for shall be the number of square metres constructed in accordance with this specification and accepted by the Contract Administrator, as computed by measurements made by the Contract Administrator.

#### BASIS OF PAYMENT

- E15.4 Add the following to section 13 :

- E15.4.1 Construction of concrete sidewalks with block outs for indicator surfaces will be paid for at the Contract Unit Price per square meter for the "Items of Work" listed here below, measured as specified herein, which price shall be payment in full for supplying all materials and for performing all operations herein described and all other items incidental to the work included in this specification.

- E15.4.2 Items of Work:

- (a) 100 mm Sidewalk with Block Outs
- (b) 150 mm Reinforced Sidewalk with Block Outs
- (c) Monolithic Curb and 100 mm Sidewalk with Block Outs\*

\* - Type 1 Concrete, 100mm Reveal Height

- E15.4.3 Concrete thickness greater than the specified sidewalk thickness as a result of shaping the base material to accommodate the block outs is incidental to the listed Items of Work.

Add: **E16. PAVING STONES FOR INDICATOR SURFACES**

#### DESCRIPTION

- E16.1 This specification shall supplement CW 3330-R5 "Installation of Interlocking Paving Stones"

#### MATERIALS

- E16.2 Add the following to section 5 :

- E16.2.1 Paving Stones for indicator surfaces shall be as shown on the drawings.

- E16.2.2 Paving Stones for indicator surfaces shall be :

Barkman Concrete paving stones -

Charcoal Holland Paver (60mm X 210 mm X 210 mm)

<https://www.barkmanconcrete.com/>

#### CONSTRUCTION METHODS

- E16.3 Add the following to section 9.2 "Preparation of Sub-grade, Sub-base and Sand-base" :

- E16.3.1 Preparation of Sand-Base for Paving Stones in Sidewalk Block Outs.

- E16.3.2 Place a 15mm layer of bedding sand in the blocked out sidewalk areas.

- E16.3.3 The bedding sand shall be spread and levelled so that the paving stones when installed are 5 mm higher than the finished grade.
- E16.3.4 No more sand shall be spread than can be covered in with paving stone on the same day.
- E16.3.5 The bedding sand shall not be compacted or disturbed prior to laying the paving stones.
- E16.4 Add the following to section 9.3 "Installation of Paving Stones" :
- E16.4.1 For indicator surface paving stones, commence installation of paving stones against the long edge of the block out to obtain the straightest possible course of installation.

#### MEASUREMENT AND PAYMENT

- E16.5 Add the following to section 12 :
- E16.6 Supply and Installation of Paving Stones for Indicator Surfaces
- E16.6.1 Paving stones for indicator surfaces will be measured on surface area basis. The surface area to be paid for shall be the number of square metres constructed in accordance with this specification and accepted by the Contract Administrator, as computed by measurements made by the contract Administrator.

#### BASIS OF PAYMENT

- E16.7 Add the following to section 13 :
- E16.7.1 The supply and installation of paving stones for indicator surfaces will be paid for at the Contract Unit Price per square meter for "Paving Stone Indicator Surface", measured as specified herein, which price shall be payment in full for supplying all materials and for performing all operations herein described and all other items incidental to the work included in this specification.
- E16.7.2 Concrete thickness greater than the specified sidewalk thickness as a result of shaping the base material to accommodate the block outs is incidental to the listed Items of Work.

### **DRAWINGS**

Replace: 341-2024 \_Drawing\_P-3581-01-R0 with 341-2024 \_Addendum 1 \_Drawing\_P-3581-01-R1  
341-2024 \_Drawing\_P-3581-02-R0 with 341-2024 \_Addendum 1 \_Drawing\_P-3581-02-R1  
341-2024 \_Drawing\_P-3581-03-R0 with 341-2024 \_Addendum 1 \_Drawing\_P-3581-03-R1