



427-2024 ADDENDUM 6

CENTREPORT SOUTH REGIONAL WATER AND WASTEWATER SERVICING PHASE 1A CONTRACT 2A - FORCE MAIN

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: August 13th, 2024
BY: Tristan Eldridge
TELEPHONE NO. 204 896-1209

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2024-02-01

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D20.4 to read The City Intends to award this Contract by September 13, 2024 (following the Standing Policy Committee meeting on September 9th, 2024), but no later than October 9, 2024 (following the Standing Policy Committee meeting on October 4th, 2024). The Substantial Completion and Total Completion dates listed in the Tender will remain as listed and will not be shifted.

PART E – SPECIFICATIONS

Add: E27.3.1 (b)(ii): Backup rings and any other additional hardware required to install mechanical restraints on pipe fittings shall be included and considered incidental to the cost of the fitting.

Add: E33.3 (c) Cement Stabilized Fill in accordance with CW 2030 and Table CW 2160.1 shall be used as backfill for MH-01, MH-02, and MH-03. The Contractor shall install Cement Stabilized Fill in lifts and provide sufficient supports and measures to resist uplift of piping or structures due to backfilling.

QUESTIONS AND ANSWERS

Q1: Should the Subsurface Monitoring Points shown on Drawing 13497 be installed to elevation 236.0m?

A1: Yes, the Subsurface Monitoring Points shown on Drawings 13497 shall be installed to elevation 236.0m.