



## 447-2024 ADDENDUM 4

# NEWPCC PIPING INSTALLATION, SOIL REMEDICATION, AND SITE COMPOUND DEVELOPMENT

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
BID/PROPOSAL**

ISSUED: August 28, 2024  
BY: Arthur Anderson  
TELEPHONE NO. 204-801-7579

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID/PROPOSAL AND SHALL FORM  
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2024-02-01

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

---

### **DRAWINGS**

Replace: Drawing 447-2024\_Drawing\_YC2-E601-R0 with Addendum 4 - Drawing 447-2024\_Drawing\_YC2-E601-R1

### **QUESTIONS AND ANSWERS**

- Q1: As per Addenda #3 and drawing YC2-E601 we are to run teck cable and leave a coil for future connection to PNL-A7021. This cable is listed as a 3-conductor. Please confirm the panel inside the trailer is only a single-phase panel otherwise if it's a 3-phase panel the cable would be a 4-conductor.
- A1: Cable to PNL-A7021 shall be 4 conductor cable. See Addendum 4 - Drawing 447-2024\_Drawing\_YC2-E601-R1.
- Q2: Please confirm a 3-conductor cable is also sufficient for the HVAC panel A7022.
- A2: Cable to PNL-A7022 shall be 4 conductor cable. See Addendum 4 - Drawing 447-2024\_Drawing\_YC2-E601-R1.