



0.20

0.40

0.60

0.80

ELEV.

O ISSUED FOR CONSTRUCTION

REVISIONS

0.20 0.10 0

ELECTRICAL - EQUIPMENT ARRANGEMENT AND DISTRIBUTION - OUTDOOR MONITORING ENCLOSURE - SITE 3

REFERENCE DRAWING TITLE

SRB EXISTING CONCRETE CHAMBER PLAN AND SECTION

REFERENCE DRAWINGS

2 | 1-0524B-E0002-001

1-0524B-S0001-001

DRAWING NUMBER

SCALE: 1:8m (24"x36")

SCALE: 1: 40m (24"x36")

SCALE: 1:500m (24"x36")

GENERAL NOTES:

- 1. STORMWATER RETENTION BASIN MONITORING EQUIPMENT SHALL BE IN ELECTRICAL ENCLOSURE AND FLOOR MOUNTED ON A CONCRETE PAD. PROPOSED PAD LOCATION SHOWN IS APPROXIMATE AND TO BE CONFIRMED.
- 2. REFER TO STRUCTURAL DRAWING FOR PAD FOUNDATION DESIGN
- 3. WATER AND SEWER PIPE NETWORK PLAN (CAD FILE) AS PER CITY OF WINNIPEG DATED 2022/10/21.
- 4. ALL DIMENSIONS IN METERS UNLESS NOTED.
- 5. THE CABLE MUST BE NEW AND WITHOUT ANY SPLICE FROM MANITOBA HYDRO TRANSFORMER TO THE SRB PANEL.
- 6. THE LOCATION OF THE GROUNDING GRID IS TO BE DETERMINED ON THE FIELD.
- 7. THE SENSOR CABLE IS TO BE INSTALLED IN 25.4mm RIGID PVC CONDUIT AND PLACED 915mm BELOW GRADE.
- 8. THE CONTRACTOR IS TO EXCAVATE THE AREA WHERE THE POWER CABLE FOR THE PANEL IS TO BE INSTALLED USING OPEN TRENCH AND INSTALL THE POWER CABLE AS INDICATED IN THE CABLE TRENCH DETAIL. AFTER THE POWER CABLE HAS BEEN INSTALLED, THE CONTRACTOR IS TO BACK FILLED THE TRENCH AND REPAIR THE AREA OF EXCAVATION TO THE CONDITION FOUND.
- 9. THE CONTRACTOR IS TO EXCAVATE AND INSTALL THE RIGID PVC CONDUIT FOR THE WATER LEVEL SENSOR USING OPEN TRENCH. AFTER THE CONDUIT HAS BEEN INSTALLED, THE CONTRACTOR IS TO BACK FILL THE OPEN TRENCH AND REPAIR THE AREA OF EXCAVATION TO THE CONDITION FOUND.
- 10. THE CONTRACTOR IS TO INSTALL THE SRB PANEL AND ITS PAD
- 11. MANITOBA HYDRO IS TO CONNECT THE POWER CABLE FOR THE PANEL TO MH DISTRIBUTION TRANSFORMER.

LEGEND:

—— GAS —— GAS LINE

WATER SERVICE PIPE

SEWER SERVICE PIPE

BURIED POWER CABLE

BURIED SENSOR CABLE

MH TRANSFORMER

CP-B81 SRB

GROUND ROD

ENGINEERS
GEOSCIENTISTS **MANITOBA Certificate of Authorization** KGS Group

SHEET 1 OF 1



CONSULTANT DRAWING NUMBER

22-0107-022-E04.01

KGS

DESIGNED

SCALE:

DATE (YYYY/MM/DD)

HORIZONTAL

VERTICAL

R. GASPAR

2022/08/18 DATE

NTS

NTS

CHECKED BY

RELEASED FOR

CONSTRUCTION

D. SUSANTO

APPROVED D. SUSANTO

Winnipèg

CITY DRAWING NUMBER

THE CITY OF WINNIPEG

WATER AND WASTE DEPARTMENT **ENGINEERING DIVISION**

STORM RETENTION BASIN 6-14 WEST FORT GARRY BUSINESS SRB 2023 WATER LEVEL MONITORING UPGRADES ELECTRICAL

> SITE PLAN AND DETAILS OUTDOOR MONITORING ENCLOSURE

1-0524B-E0001-001

FILE PATH: C:\Users\tnguyen\OneDrive - KGS Group\FMS\22-0107-022\
FILE NAME: 1-0524B-E0001-001.dwg