



54-2024 ADDENDUM 03

RENFREW OUTFALL GATE CHAMBER 2024 UPGRADES

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: April 4, 2023
BY: Mark Baker, P.Eng.
TELEPHONE NO. 204-688-3805

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2024-02-01

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

FORM B: PRICES

Replace: 54-2024 Form B: Prices with 54-2024 Addendum 03 - Form B: Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

- Form B(R1): Revise Item No. 5 to read: Supply and Installation of Manhole, 7.0 m deep.
- Revise Item No. 20 units to read: Lump Sum
- Revise Item No. 25 Spec Ref to include: SD228B
- Add Items No. 26 to 27 inclusive.
- Revise Item No. 29 to read: MRST (for items 7-11)

Page numbering on some forms may be changed as a result.

PART D – SUPPLEMENTAL CONDITIONS

- Revise: D3.1 to read: The Work to be done under the Contract shall consist of the removal of one slide gate and the removal of two (2) flap gates. The gates are to be replaced with a new slide gate and a single new flap gate. A new flap gate chamber is to be constructed adjacent to the existing slide gate chamber and pump out chamber. A two-pump dewatering system complete with process piping is to be supplied and installed in the existing pump out chamber. A new forcemain is to be constructed from the pump-out chamber to the Academy Road interceptor. Various chamber modifications will be required.

PART E – SPECIFICATIONS

- Revise: E11.6(a)(iv) to read: Monolithic curb and sidewalk – in accordance with SD-228B.
- Add: E11.6(a)(v) Full depth patching of existing slabs and joints for works that require pavement removal including any excavation of Wellington Crescent or Academy Road – in accordance with CW 3230.

- Add: E16.1.2 E16.1.2 This Specification shall amend and supplement NMS Section 33 31 23 Sanitary Sewer Force Main Piping.
- Add: E16.4.3 Contractor to use trenchless methods where forcemain crosses Wellington Crescent to minimize disturbance of the roadway and sidewalks.
- Add: E17.4(f) Contractor to use trenchless methods where gravity sewer pipe crosses Academy Road to minimize disturbance of the roadway and sidewalks as directed by the Contract Administrator.

DRAWINGS

Replace: 54-2024 _Drawing_C0001-001-00 with 54-2024 _Addendum_03 _Drawing_C0001-001-00-R1

Replace: 54-2024 _Drawing_S0001-001 with 54-2024 _Addendum_03 _Drawing_S0001-001-R1

Replace: 54-2024 _Drawing_S0002-001 with 54-2024 _Addendum_03 _Drawing_S0002-001-R1

Replace: 54-2024 _Drawing_P0003-001-00 with 54-2024 _Addendum_03 _Drawing_P0003-001-R1

APPENDICES

Add: 54-2024 _Addendum_03-Appendix F_Existing Chamber Pictures

NMS SPECIFICATIONS

Section 05 14 10

Add: Section 05 14 10

Section 33 31 23

Add: Section 33 31 23

QUESTIONS AND ANSWERS

Q1: This forcemain is a brand-new line? There is no existing line? (Other than the 2440mm WWS and the 2820 SRS)

A1: The forcemain is new, there is no existing forcemain.

Q2: Can this be installed by directional drill - schedule says CI5 or CI2- implies open cutting?

A2: The forcemain may be installed by directional drill. Form B has and Drawing 54-2024 _Addendum_03 _Drawing_C0001-001-00-R1 have been clarified.